




NOTIFICATION OF POTENTIAL HAZARD

ASBESTOS CONTAINING MATERIAL (ACM) IS PRESENT IN THE BUILDING THAT MAY IMPACT THE WORK OF ALL TRADES. THE CONTRACTOR SHALL REQUIRE THEIR PERSONNEL AND ALL SUBCONTRACTOR PERSONNEL TO COORDINATE WITH OTHER TRADES AND CONDUCT THEIR WORK TO PREVENT WORKER EXPOSURE OR SITE CONTAMINATION. REFER TO DIVISION 01 AND 02 SPECIFICATIONS FOR SPECIFIC INFORMATION CONCERNING REMOVING AND DISPOSING OF THESE MATERIALS AND THE INSTALLATION OF NEW MATERIALS AND COMPONENTS. THIS NOTIFICATION IS PROVIDED IN ACCORDANCE WITH EPA AND OSHA REQUIREMENTS.



SHEET NOTES

- SAWCUT SLAB TO INSTALL UNDERFLOOR DWV PIPING FOR NEW FLOOR DRAIN/SINK. SEE 1/M2.1.
- RELOCATE BAS WORKSTATION, BAS WIRING, CONDUIT AND TELECOM OUTLET TO SUPPORT NEW DOOR AND BAS WORKSTATION LOCATION.
- DEMOLISH DUCTWORK TO SUPPORT INSTALLATION OF SMOKE DAMPER.
- VAV BOX ABOVE CONCRETE CEILING OF PHYSICS ROOM BELOW. DEMOLISH RHC PIPING BACK TO MAIN AND CAP. REMOVE RHC CONTROL VALVE AND COORDINATE WITH PROJECT MGR FOR RETURN TO UAA FOR SPARE PARTS.
- DEMOLISH EXISTING SUPPLY GRILLES AND BRANCH TAKE-OFFS IN PREPARATION FOR NEW DIFFUSER INSTALLATIONS. PATCH HOLES AIR TIGHT.
- EXISTING HEATING SYSTEM FLOW METER TO BE RELOCATED. FLOW METER INDICATOR TO REMAIN FOR REUSE. SEE M3.1.
- FIELD VERIFY EXISTING CONNECTIONS. COORDINATE LIMITS OF DEMOLITION WITH NEW WORK.
- THIS FACILITY IS PROTECTED BY AN EXISTING WET PIPE FIRE SPRINKLER SYSTEM. MODIFY THE EXISTING SYSTEM SERVING AREAS AFFECTED BY THIS PROJECT AS REQUIRED TO ACCOMMODATE THE REQUIREMENTS OF APPLICABLE CODES AND STANDARDS, AND THE LOCAL AUTHORITY HAVING JURISDICTION (AHJ).
- THE HYDRONIC HEATING SYSTEM FOR THIS FACILITY IS BEING CONVERTED FROM A 50% PROPYLENE GLYCOL SOLUTION TO CHEMICALLY TREATED WATER, AND A DEDICATED PREHEAT COIL GLYCOL HEATING SYSTEM ADDED. REFER TO SPECIFICATION SECTION 23 2113 HYDRONIC HEATING PIPING AND SPECIALTIES FOR INFORMATION REGARDING SYSTEM FLUSHING, CLEANING, FILLING, AND TREATMENT.



NSB EM-2 MECHANICAL SYSTEMS
CONVERSION/UPGRADE

Revisions		
No.	Date	Description

Design: RHP
Drawn: ERP/MPL
UAA Project No.: 16-0103
Date: 02/17/2017
Sheet Title
ENLARGED PLANS ☐
DEMO

Sheet Number
M1.1

100% CONSTRUCTION DOCUMENTS

