


SHEET NOTES:

- 1. INSTALL RECEPTACLE 6" ABOVE COUNTERTOP.
- 2. RECEPTACLE INSIDE RECESSED A/V BOX FOR OFCI TELEVISION. LOCATE BOX BEHIND LOWER HALF OF TELEVISION. SEE ARCHITECTURAL FOR ELEVATIONS. EXACT LOCATION SHOULD BE COORDINATED WITH TELEVISION MOUNTING HARDWARE TO AVOID CONFLICTS.
- 3. RECEPTACLE FOR OFCI A/V RACK. CONTRACTOR SHALL INSTALL RACK AT LOCATION SHOWN AND SECURE TO FLOOR. RACK IS A MIDDLE ATLANTIC 'AXS' SERIES SLIDE-OUT RACK, 43 RACK-MOUNT UNITS.
- 4. NEW PANEL '2Z'. SEE 1/E0.2 FOR ONE-LINE DIAGRAM.
- 5. RECEPTACLE FOR UNDER COUNTER REFRIGERATOR. CONNECT TO LOAD SIDE OF GFCI RECEPTACLE ABOVE COUNTER AND LABEL "GFCI PROTECTED".
- 6. JUNCTION BOX WITH 1"C TO ABOVE CEILING AND PANEL 2Z FROM DIVIDED SURFACE RACEWAY FOR POWER CABLING.

- 7. JUNCTION BOX FOR WIRING TO LAB ISLAND. RECEPTACLES WILL BE INSERTS PROVIDED WITH FURNITURE. PROVIDE CONNECTION TO CIRCUITS SHOWN.
- 8. INSTALL GFCI RECEPTACLE UNDER SINK FOR DISHWASHER.
- 9. QUAD RECEPTACLE FOR A/V CABINET. COORDINATE HEIGHT SO POSITIONED BEHIND CABINET, PRIOR TO ROUGH-IN.
- 10. CEILING-MOUNTED CORD REEL. EXTEND CIRCUIT AND RECONNECT TO EXISTING CIRCUITS USED FOR FLOOR-MOUNTED ASSEMBLY. COORDINATE LOCATION WITH TABLE LAYOUT PRIOR TO ROUGH-IN..
- 11. EXISTING FLOOR ASSEMBLY. RECONNECT RELOCATED LECTERN TO TELECOM AND POWER.

GENERAL NOTES:

COORDINATE WITH ARCHITECTURAL REFLECTED CEILING PLAN FOR FINAL LOCATION OF ELECTRICAL EQUIPMENT AND DEVICES.



- AREA OF WORK

TELECOM ROOM

100U9.

1ST FLOOR KEY PLAN

MAIN ELEC. RM.

SEE 2/E1.1 -

SIZE

FULL