

Revisions		
No.	Date	Description
Design:		EJK/NPS/KTR
Drawn:		ERP
Date:		04/26/2017
Sheet Title		
FIRST FLOOR PLAN FOOTH - FIRE ALARM		
Sheet Number		
E202		

1. FIRE ALARM NOTIFICATION STROBES SHALL BE 15 cd UNLESS OTHERWISE NOTED. 2. INSTALL CEILING MOUNTED DEVICES IN CEILING TILES WITH EXISTING DEVICES INSTALLED IN THEM, WHERE PRACTICABLE, TO MAINTAIN THE MAXIMUM NUMBER OF ACCESSIBLE TILES WITH NO DEVICES INSTALLED IN THEM. 3. CONNECT EXISTING MAGNETIC DOOR HOLDERS TO FIRE ALARM PANEL. PROVIDE POWER AND RELEASE CONTROL IN ACCORDANCE WITH SPECIFICATION SECTION 28 3100 – ADDRESSABLE FIRE ALARM SYSTEM. 4. CONTRACTOR'S OPTION: REMOTE BOOSTER POWER SUPPLY/SUPPLIES MAY BE ADDED TO SERVE THE NOTIFICATION APPLIANCE CIRCUITS. CONTRACTOR SHALL SUBMIT LOCATION(S) FOR APPROVAL PRIOR TO THE SHOP DRAWING SUBMITTALS. IF THE OPTION IS EXERCISED, INCLUDE ALL COSTS ASSOCIATED WITH THE REMOTE BOOSTER POWER SUPPLIES AS PART OF THE BASE BID. INCLUDE A MULTI-TECHNOLOGY DETECTOR AT THE BOOSTER PANEL LOCATION.	5. PROVIDE FIRE ALARM RELAYS FOR PHASE 1 ELEVATOR RECALL FUNCTIONS. CONNECT ELEVATOR CONTROLLER TO RELAY OUTPUTS AS COORDINATED WITH THE OWNER'S REPRESENTATIVE. REFER TO SPECIFICATION SECTION 28 3100 FOR ADDITIONAL INFORMATION.
---	--

