

1. FIRE ALARM NOTIFICATION STROBES SHALL BE 15 cd UNLESS OTHERWISE NOTED.
2. INSTALL CEILING MOUNTED DEVICES IN CEILING TILES WITH EXISTING DEVICES INSTALLED IN THEM, WHERE PRACTICABLE, TO MAINTAIN THE MAXIMUM NUMBER OF ACCESSIBLE TILES WITH NO DEVICES INSTALLED IN THEM.
3. CONNECT EXISTING MAGNETIC DOOR HOLDERS TO FIRE ALARM PANEL. PROVIDE POWER AND RELEASE CONTROL IN ACCORDANCE WITH SPECIFICATION SECTION 28 3100 - ADDRESSABLE FIRE ALARM SYSTEM.
4. CONTRACTOR'S OPTION: REMOTE BOOSTER POWER SUPPLY/SUPPLIES MAY BE ADDED TO SERVE THE NOTIFICATION APPLIANCE CIRCUITS. CONTRACTOR SHALL SUBMIT LOCATION(S) FOR APPROVAL PRIOR TO THE SHOP DRAWING SUBMITTALS. IF THE OPTION IS EXERCISED, INCLUDE ALL COSTS ASSOCIATED WITH THE REMOTE BOOSTER POWER SUPPLIES AS PART OF THE BASE BID. INCLUDE A MULTI-TECHNOLOGY DETECTOR AT THE BOOSTER PANEL LOCATION.



**UNIVERSITY OF ALASKA ANCHORAGE  
RASMUSON HALL FIRE ALARM REPLACEMENT  
PROJECT NUMBER 17-0071**

Revisions		
No.	Date	Description

Sheet Title

Sheet Number

## E204