

FILE NAME: X:\17601 UABASFA\Drawg\Edwg\Sheet Files\17601 - E205.dwg
PLOTED: ejk 4/26/2017 11:51 AM



1 THIRD FLOOR PLAN NORTH - FIRE ALARM
E205 SCALE: 1/8" = 1'-0"

SHEET NOTES

1. FIRE ALARM NOTIFICATION STROBES SHALL BE 15 cd UNLESS OTHERWISE NOTED.
2. INSTALL CEILING MOUNTED DEVICES IN CEILING TILES WITH EXISTING DEVICES INSTALLED IN THEM, WHERE PRACTICABLE, TO MAINTAIN THE MAXIMUM NUMBER OF ACCESSIBLE TILES WITH NO DEVICES INSTALLED IN THEM.
3. CONNECT EXISTING MAGNETIC DOOR HOLDERS TO FIRE ALARM PANEL. PROVIDE POWER AND RELEASE CONTROL IN ACCORDANCE WITH SPECIFICATION SECTION 28 3100 - ADDRESSABLE FIRE ALARM SYSTEM.
4. CONTRACTOR'S OPTION: REMOTE BOOSTER POWER SUPPLY/SUPPLIES MAY BE ADDED TO SERVE THE NOTIFICATION APPLIANCE CIRCUITS. CONTRACTOR SHALL SUBMIT LOCATION(S) FOR APPROVAL PRIOR TO THE SHOP DRAWING SUBMITTALS. IF THE OPTION IS EXERCISED, INCLUDE ALL COSTS ASSOCIATED WITH THE REMOTE BOOSTER POWER SUPPLIES AS PART OF THE BASE BID. INCLUDE A MULTI-TECHNOLOGY DETECTOR AT THE BOOSTER PANEL LOCATION.
5. PROVIDE DETECTOR FOR PHASE 1 ELEVATOR RECALL FUNCTIONALITY. LOCATE PER NFPA 72 REQUIREMENTS.
6. PROVIDE OPEN AREA SMOKE IMAGING PROTECTION BEAM TRANSMITTER/RECEIVER SMOKE DETECTION SYSTEM TO PROVIDE DETECTION IN OPEN ATRIUM AREA. LOCATE TRANSMITTER/RECEIVER PER MANUFACTURER'S RECOMMENDATIONS.

UNIVERSITY OF ALASKA ANCHORAGE
RASMUSON HALL FIRE ALARM REPLACEMENT
PROJECT NUMBER 17-0071

Revisions

No.	Date	Description

Design: EJK/NPS/KTR

Drawn: ERP

Date: 04/26/2017

Sheet Title

THIRD FLOOR PLAN
NORTH - FIRE ALARM

Sheet Number

E205