



INVITATION TO BID ADDENDUM TO THE CONTRACT

Project Name: JSOB 7th and 8th Floor Renovation
Project Number: 2018-0222-3725

ADDENDUM #:	Two
CURRENT BID OPENING DATE:	August 25, 2017 2:00 pm Local Time

PREVIOUS ADDENDA:	One
PREVIOUS BID OPENING	August 25, 2017 2:00 pm Local Time

ISSUED BY:	Statewide Facilities Physical Address: Department of Administration Shared Services of Alaska 333 Willoughby Ave 7th Floor Juneau, Alaska 99811-0210	Mailing Address: Department of Administration Shared Services of Alaska PO Box 110210 Juneau, Alaska 99811-0210
-------------------	---	--

DATE ADDENDUM ISSUED: August 22, 2017

The following items of the Contract are modified as herein indicated. All other items remain the same.

PROJECT CLARIFICATIONS AND QUESTIONS

Item No. 1: Q: Note 7 on sheets A2.1-7, A2.1-8 says the locksets are "cylindrical," but the specs 087100 say "mortise" locks. Which is correct?

A: All locksets shall be mortice locksets.

Item No. 2: Q: What is the keying system for the project?

A: Locksets should come with IC cores and the State will provide final cores and keying.

PROJECT DRAWINGS

Item No. 1: Sheet E1.0, LEGEND & DETAIL – Project Notes: **DELETE** Notes 1 and 4.

Item No. 2: Sheet E1.0, LEGEND & DETAIL – Project Notes: **Add** Note 5: "Work in 8TH, 7TH, and 6TH floors is the base bid item."

Item No. 3: Sheet E1.0, LEGEND & DETAIL – Project Notes: **Add** Note 6: "Remove any abandoned conductors and cable discovered during work."

Item No. 4: Sheet E1.0, LEGEND & DETAIL – Project Notes: **Add** Note 7: "Abandoned conductors and cables discovered during work in non-abated areas shall be identified as abandoned by electrical contractor and removed by abatement team."

Item No. 5: Sheet E1.0, LEGEND & DETAIL – Project Notes: **Add** Note 8: "Coordinate placement of

	receptacles for new café and break room equipment with architect.”
Item No. 6:	Sheet E1.0, LEGEND & DETAIL – Project Notes: Add Note 9: “Existing closet in Shared Services 800C to be removed (see sheets A1.1-8 and A2.1-8). Relocate existing duplex receptacle and four-port data outlet on existing closet to adjacent existing wall. Coordinate with abatement team.”
Item No. 7:	Sheet E1.1-7, PARTIAL 7 TH FLOOR DEMOLITION PLAN – Add floor junction box with “X” for demolition in center of wall at gridline G.
Item No. 8:	Sheet E1.1-7, PARTIAL 7 TH FLOOR DEMOLITION PLAN – Add floor duplex receptacle with “X” for demolition in center of wall at gridline G.
Item No. 9:	Sheet E1.1-7, PARTIAL 7 TH FLOOR DEMOLITION PLAN – Add duplex receptacle with “X” for demolition in lower left corner of existing conference room.
Item No. 10:	Sheet E1.1-7, PARTIAL 7 TH FLOOR DEMOLITION PLAN – Add double duplex receptacle with “X” for demolition in lower left corner of existing mail staff room.
Item No. 11:	Sheet E2.1-7, PARTIAL 7 TH FLOOR POWER PLAN–Notes: Add Note 5: “New devices on existing walls in new break room shall be installed on surface raceways. See note 1.”
Item No. 12:	Sheet E2.2-7, PARTIAL 7 TH FLOOR POWER PLAN– Delete new single pole switch marked “exhaust fan” in DOA MAIL EQUIPMENT room.
Item No. 13:	Sheet E2.2-7, PARTIAL 7 TH FLOOR POWER PLAN– Add Note 4: “Extend and route existing surface mount conduit and circuitry in Storage 710 around new door.”
Item No. 14:	Sheet E3.1-7, PARTIAL 7 TH FLOOR LIGHTING PLAN – Add to Note 3: “Relocate existing single pole switch to adjacent existing wall. Extend circuit if necessary. Coordinate with abatement team.”

END OF ADDENDUM No. Two

By: Brent Fagerstrom, Facilities Contracting Officer

Total number of pages contained within this Addendum: 2
