



CANOPY BRACKETS ARE ANCHORED INTO SIDEWALK

RESURFACE 2340 SF
CONCRETE SIDEWALK

COTTAGE 3

COTTAGE 5

SCHOOL

CAFETERIA


ELECTRICAL CONDUITS RUN
ALONG CANOPY AND POSTS
SEE NOTE 5

DEMOLITION ITEMS:



CONCRETE DEMOLITION / RESURFACING

--- SAWCUT LINE




DEMOLITION PLAN NOTES:

1. ALL ITEMS SCHEDULED FOR DEMOLITION WILL BE REMOVED FROM THE PROJECT SITE AND SHALL BE PROPERLY DISPOSED OF BY THE CONTRACTOR UNLESS NOTED OTHERWISE.
2. OWNER RESERVES THE RIGHT TO SALVAGE ITEMS FROM THE SITE PRIOR TO CONTRACTOR MOBILIZATION AND DURING DEMOLITION. CONTRACTOR TO NOTIFY OWNER 72-HOURS PRIOR TO SITE MOBILIZATION.
3. VERIFY EXISTING SITE CONDITIONS AND ALL DEMOLITION ITEMS WITH THE OWNER.
4. THE CONTRACTOR IS RESPONSIBLE FOR THE DEMOLITION AND REMOVAL OF ALL EXISTING ITEMS NECESSARY FOR COMPLETION OF THE WORK.
5. DO NOT DISTURB EXISTING CANOPY SUPPORTS AND ELECTRICAL CONDUITS.
6. MAINTAIN ACCESS TO ALL COTTAGES, SCHOOL AND CAFETERIA AT ALL TIMES.
7. MAINTAIN ELECTRICAL POWER TO ALL COTTAGES, SCHOOL AND CAFETERIA AT ALL TIMES.

CONCRETE RESURFACING PREPARATION NOTES:

1. CONCRETE SURFACE MUST BE CLEAN AND FREE OF LOOSE PARTICLES EFFLORESCENCE, PAINTS, TARs, GREASE, ASPHALTIC MATERIALS, BOND BREAKERS, CURING COMPOUNDS, WAX, AND ANY FOREIGN SUBSTANCE OR ANY CONDITIONS THAT MAY AFFECT PRODUCT PERFORMANCE OR PROPER BONDING.
2. ENSURE THAT ANY CONCRETE THAT HAS BEEN DAMAGED OR WEAKENED (SUCH AS BY DE-ICING SALTS) IS MECHANICALLY REMOVED. REMOVE CONCRETE UNTIL A SOUND SUBSTRATE HAS BEEN ACHIEVED.
3. MECHANICALLY PROFILE AND PREPARE CONCRETE SURFACES BY SHOTBLASTING TO A MODERATE PROFILE .
4. SWEEP AND VACUUM AREA TO COLLECT DEBRIS .



R&M CONSULTANTS, INC.

 9101 Vanguard Drive
 Anchorage, Alaska 99507
 rmconsult.com • email: rmconsult.com
 phone: 907.522.1707 • fax: 907.522.3403
 CERT. OF AUTH. AEC07111

STATE OF ALASKA
DEPT. OF HEALTH & SOCIAL SERVICES
MCLAUGHLIN YOUTH CENTER -
PARKING LOT RENOVATIONS
ANCHORAGE, ALASKA

[illegible]

Drawn By: CB	Checked By: NK
Date: August 3, 2018	
Phrase: Bid Documents	
Project No.: R&M 2649.01	

SHEET TITLE:
EXISTING SITE &
DEMOLITION
PLAN SIDEWALK

SHEET NO:

C3