



STATE OF ALASKA
DEPT. OF HEALTH & SOCIAL SERVICES
MCLAUGHLIN YOUTH CENTER -
PARKING LOT RENOVATIONS
ANCHORAGE, ALASKA

1. ENSURE THAT CONCRETE HAS BEEN PREPARED IN ACCORDANCE WITH THE *CONCRETE RESURFACING PREPARATION NOTES* ON C3, MANUFACTURERS RECOMMENDATIONS AND IS SATURATED SURFACE-DRY.
2. CONCRETE RESURFACING MATERIAL SHALL BE A ONE-COMPONENT, POLYMER MODIFIED, CEMENTITIOUS MATERIAL.
3. CONTRACTOR SHALL SUBMIT CONCRETE RESURFACING MATERIALS, ADMIXTURES AND SEALERS FOR APPROVAL. ALL COMPONENTS SHALL BE FROM ONE MANUFACTURER TO ENSURE COMPATIBILITY.
4. PRIME CONCRETE SURFACE WITH A WATER BASED ONE-COMPONENT LATEX ADDITIVE IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
5. MIX AND APPLY THE PRODUCT PER MANUFACTURERS RECOMMENDATIONS ENSURING THAT ALL EXPANSION AND CONTROL JOINTS ARE HONORED.
6. PROTECT AND CURE THE CONCRETE SURFACE PER MANUFACTURERS RECOMMENDATIONS.
7. SEAL THE SURFACE WITH A FILM-FORMING, WATER BASED SEALER AFTER SIDEWALKS HAVE CURED.

1. ALL NEW WORK SHALL MATCH EXISTING GROUND ELEVATIONS AND GRADES UNLESS OTHERWISE NOTED.
2. SIDEWALK SHALL BE IN ACCORDANCE WITH MASS SECTION 30.03 PORTLAND CEMENT CONCRETE SIDEWALK, CLASS A-3, 6 INCHES THICK AND BROOM FINISHED WITH 6x6-W2.9/W2.9 WELDED WIRE MESH PLACED MID DEPTH.
3. INSTALL EXISTING CANOPY BRACKETS IN SIDEWALK.
4. MAINTAIN ACCESS TO ALL COTTAGES, SCHOOL AND CAFETERIA AT ALL TIMES.
5. MAINTAIN ELECTRICAL POWER TO ALL COTTAGES, SCHOOL AND CAFETERIA AT ALL TIMES.
6. SIDEWALK SHALL BE CROWNED IN THE MIDDLE WITH 1% SLOPES TO EACH SIDE.
7. ALL NEW TO EXISTING SIDEWALK CONNECTIONS TO BE DOWELED PER DETAIL F/C7.

[illegible]

Drawn By: CB	Checked By: NK
Date: August 3, 2018	
Phrase: Bid Documents	
Project No: R&M 2649.01	

SHEET TITLE:

SITE PLAN

SIDEWALK

SHEET NO:

C6