

**Alaska Department of Natural Resources
Division of Support Services**

Invitation to Bid # 10-003-20

**Battery Creek Fish Passage Improvement
Project Anton Larsen Bay Road
Addendum Three**

Date of Issue: March 2, 2020

Addendum Three provides an answer to a question received from a vendor. This Addendum Three is hereby made part of the ITB and is a total of 2 pages.

Issued by:

Chris Brooks, Procurement Officer

Phone: (907) 269-8666

Question 1: On Sheet C10, Detail 2 (Step 4) shows the 690(11) Root Wad Bank Reconstruction and 690(12) Waterway Bank Revegetation and Protection work items being performed after all of the stream diversion and detour road have been removed. This will cause turbid water to be created during the performance of these activities, as the creek will be diverted to the active excavation during the rainy month of September. Will this be acceptable?

Answer: The stream diversion plan is an example to what can be done to perform the work.

I point the contractor to the Diversion Notes on Sheet C9 that state, “Temporary dikes or berms may be used to isolate the work area from waters of the surrounding area. This work may require a diversion of stream water. The designers recognize that different contractors will have various approaches for controlling water and construction sequencing. This diversion plan has been developed to check for constructability and as a starting point for a contractor-generated plan. Contractor must submit traffic control plans to ADOT&PF for approval prior to implementation.”

Contractor is also responsible for complying with permits.

End of Addendum Three