



State of Alaska
Department of Environmental Conservation
Village Safe Water Program

555 Cordova Street
Anchorage, AK 99501
Evan.patterson@alaska.gov

November 17, 2021

To: Vendor List

Re: Amendment 1
ITB 22-VSW-TLT-032
Packaged Water Treatment System
ITB Due Date: December 6, 2021 @ 10:00 AM AST

The following are vendor questions and the department's response:

1. Vendor: First, CRW spec'd AWC's ST plant which is great but they also spec'd Westech's AC plant. The ST cannot compete with the AC at all commercially, but they are NOT the same and are "apples and oranges" by comparison. The ST technology can handle much lower water quality, but it is more expensive and has a larger footprint. If AWC Solutions is expected to bid their ST against the competition's AC system, AWC will have to respectfully decline to bid.

Will you please consider allowing AWC to bid their AC system, issuing an addendum allowing them to bid their AC system? If you require, AWC Solutions will submit a list of exceptions/clarifications they would have to take to the AC portion of the spec so that you know exactly what would be different. All changes would be minor and the performance of AWC's AC plant is the same as the competition's. They are very similar despite the key differences.

It is important to note that AWC Solutions cannot bid an AC system the way it is spec'd because it is spec'd per the competition's design and AWC's AC plant operates a little differently. The

main difference is AWC uses non-buoyant media whereas the competition uses buoyant media in the clarifier section.

Department: Adsorption Clarifiers (AC)'s are not allowed. See attached updated specification 46 07 13. The following changes are required:

- a. Delete from 46 07 13 – 2, Paragraph 1.2.B.: “or by adsorption bed clarification, in which solids are captured by a bed of media suspended in the tank from water flowing upward”
- b. Delete from 46 07 13 – 7, Paragraph 2.6-F-4. “or adsorption clarifier”
- c. Delete from 46 07 13 – 8, Paragraph 2.6-F-4-b. This paragraph is deleted in its entirety.

Bidders must acknowledge this amendment on Submittal Form A – Bidder Information. A bid that doesn't acknowledge this amendment may be found non-responsive and rejected.

Evan Patterson



Procurement Specialist

SECTION 460713
PACKAGED WATER TREATMENT EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes work necessary to furnish a packaged water treatment system with a treated water capacity of 20 gpm for treatment of iron, manganese, and arsenic laden groundwater with high organics and color. The water treatment equipment will be located in a new modular facility located adjacent to the water wells and a new water storage tank.
- B. The water treatment system will treat water from an existing groundwater well. After treatment the water will be disinfected and conveyed to a water storage tank and then to the distribution system. Settled solids and filter backwash water will be conveyed to an on-site lift station for conveyance to the Community's sewage lagoon.
- C. It is the intent of this specification that a complete, pre-fabricated, packaged water treatment system be supplied by a single supplier and that it shall include, but not be limited to, the following components, designated with an * on the Drawings:
 - 1. Raw, backwash, and treated water flow meters
 - 2. Oxidation detention tank
 - 3. Factory-built, welded-steel-packaged water treatment system, with necessary tankage and equipment, capable of treating groundwater to meet potable standards.
 - 4. Oxidant blending and dosing
 - 5. Coagulant blending and dosing
 - 6. Flocculation
 - 7. Clarification
 - 8. Gravity filter
 - 9. Blowers
 - 10. Backwash pump
 - 11. Chlorine disinfection
 - 12. Filter piping manifolds and valves
 - 13. Allen-Bradley PLC based automatic Process control system
 - 14. J-Boxes for wire terminations on treatment train
 - 15. Required instrumentation for process control
 - 16. Grating
 - 17. Handrail and access ladder
 - 18. Bolts and lifting lugs
- D. Work by the Supplier includes:
 - 1. Submission of Shop Drawings, Operation and Maintenance Manuals, and other descriptive information.
 - 2. Fabrication of the equipment.
 - 3. Factory test of each unit to be supplied.
 - 4. Delivery of the equipment to Bethel, Alaska.
 - 5. Installation assistance, quality control, quality assurance, and inspection.
 - 6. Onsite performance testing, equipment startup, and training of the Owner's staff.

TULUKSAK NATIVE COMMUNITY
WTP AND WASHTERIA

- E. The Supplier shall manufacture and supply the equipment. The Contractor will integrate the equipment into the water treatment facility.
- F. The following system components will be designed by the Engineer and installed by the Contractor:
 - 1. Raw water supply and yard piping
 - 2. Water treatment plant building
 - 3. Water storage tank and distribution pumping
 - 4. Connecting piping and power to the packaged water treatment system, chemical feed systems, blower, and backwash pump.

1.2 DEFINITIONS

- A. ADEC or DEC: The Alaska State Department of Environmental Conservation.
- B. Clarification: Treatment process that removes suspended solids from water. Clarification may be accomplished by gravity settling, in which solids settle to the bottom of a settling tank, ~~or by adsorption bed clarification, in which solids are captured by a bed of media suspended in the tank from water flowing upward.~~
- C. Coagulation: Treatment process that causes colloid-size suspended solids in source water to coalesce into clumps with sufficient mass to settle under the influence of gravity.
- D. Coliform Bacteria: General class of bacteria used as indicators of potential contamination of drinking water.
- E. Contractor: General contractor responsible for delivery and assembly of the WTP building, transport of the packaged water treatment system from Bethel to Tuluksak, AK, and installation of the equipment in the WTP Building.
- F. Design Flow: Required treated water flow rate.
- G. Disinfection: Destruction of bacteria and protozoa and deactivation of viruses by the action of a chlorine solution.
- H. Filtration: Treatment process that removes small, suspended solids after the clarification process by means of granular media.
- I. Flocculation: A process wherein colloids come out of suspension in the form of floc or flakes by the addition of a clarifying agent.
- J. Good: All equipment and materials supplied under this Specification.
- K. HMI: Human machine interface.
- L. Installer: Supplier provided field technician for installation assistance, on site performance testing, equipment start up and training of Owner's staff.
- M. Modular Building Manufacturer: The vendor responsible for fabrication of the water treatment plant building including the plumbing, electrical, and control systems inside the building.

TULUKSAK NATIVE COMMUNITY
WTP AND WASHTERIA

- N. NSF: NSF International, an independent, non-profit organization which provides voluntary consensus standards, product testing procedures, and certification services in the areas of public health, safety, and the environment.
- O. Supplier: Packaged water treatment equipment supplier.
- P. Raw Water: Water supplied from the groundwater well to the water treatment plant.

1.3 SUBMITTALS

- A. Product Data: Manufacturer's product data for system materials and component equipment.
- B. Submittals required with Bid Documents:
 - 1. Submittals provided with Bid shall be for the purpose of advancing the design of the WTP to facilitate the project schedule.
 - a. Exceptions: Identify any exceptions to these Contract Documents.
 - b. Drawings: provide drawings showing WTP equipment plan, minimum space between units or equipment and minimum separation clearances on all sides.
 - c. Preliminary Shop Drawings:
 - 1) Equipment dimensions, weights (shipping and installed), and connection points.
 - 2) Process and Instrumentation Diagrams.
 - a) Details of backwash and solids removal frequency, duration, and flow rates.
 - 3) Total connected electrical load in kW, kVA, and amperes for complete system.
 - 4) Location of single point of connection for power supply to the packaged water treatment system.
 - d. Process Control Narrative.
- C. Submittals required after Notice of Award:
 - 1. Detailed Shop Drawings:
 - a. Final complete shop drawings of all water treatment system equipment.
 - b. System materials and component equipment, including detailed wiring and control diagrams.
 - c. Fabrication, installation, anchoring, fasteners, and other details.
 - 2. Electrical:
 - a. One-line diagram(s), including transformers, drives, panelboards, meters, and protective devices.
 - b. Panel elementary diagrams of prewired panels, including control devices and auxiliary devices.
 - c. Wiring and control diagrams of systems and equipment.
 - d. Interconnecting wiring diagrams. Include conductor size, type, and number between all electrical and control components. Include conduit size and type.
 - e. List number and capacity of transformer(s), if any.
 - f. List of special motor features being furnished (i.e., space heaters, altitude corrections, and thermal protectors).
 - g. Complete motor rating for motors 3 horsepower and larger, including motor no-load, starting, and full-load current at rated voltage; full-load speed and full-load

current at 100 percent voltage; motor efficiency and power factor at 1/2, 3/4, and full load at rated voltage.

3. Instrumentation and Control:
 - a. Process and instrumentation diagrams and description of functions monitored, controlled, and alarmed.
 - b. Describe instrumentation and control components and features including software, hardware, control features, remote system capabilities, monitoring, data storage, and alarms. Provide examples of HMI screens that have been provided on previous projects. Provide a block diagram of proposed control system including HMI(s), PLC(s), and data highway.
 - c. Software Description: Provide narrative description of control system, logic diagrams, summary of control functions, summary of monitoring functions, description of alarms, and other information to describe control system.
 - d. Copy of all PLC programming.
4. Product Data Sheets for all components used in the packaged system.
5. Paint data sheets for prime and finish coating systems for each equipment item.
6. NSF 61 certifications for all materials or coatings in contact with water (raw, treated, and chemical batching).
7. Commissioning Plan.
8. Training Plan.
9. Operating and Maintenance Manuals.
10. Crating: Provide an electronic copy and one paper copy of the shipping index for all crates to be delivered. Include in the shipping index the actual scale weight, cube, dimensions, individual piece numbers for all crates, and a detailed listing of the contents of each crate.
11. Manufacturer's Certificate: Products meet or exceed specified requirements.
12. Manufacturer Instructions: Installation requirements, including storage and handling procedures, anchoring, and layout.
13. Source Quality-Control Submittals: Indicate results of factory tests and inspections.
14. Field Quality-Control Submittals: Indicate results of Supplier-furnished tests and inspections.

D. Qualifications Statements:

1. Qualifications for manufacturer, installer, and licensed professional.
2. Manufacturer's approval of installer.

1.4 CLOSEOUT SUBMITTALS

- A. Final O&M Manuals: Include updates to any items that were modified during fabrication, installation, and start up.

1.5 QUALITY ASSURANCE

- A. The water treatment system equipment shall be the product of a recognized manufacturer whose personnel have been regularly engaged in the design and manufacturing of water treatment systems for at least five years. The manufacturer must be able to demonstrate experience with the design, fabrication, supply and successful operation of at least five systems of similar

TULUKSAK NATIVE COMMUNITY
WTP AND WASHTERIA

process and capacity within the last two years. The manufacturer/supplier shall demonstrate upon the request of the engineer that:

1. They maintain a reasonable stock of spare parts for this equipment.
 2. They employ sufficient qualified technical personnel to insure adequate servicing and operational control advice covering chemical, hydraulic, mechanical, and electrical optimization of water treatment procedures and practices.
- B. Welders: AWS-certified within previous 12 months.

1.6 WARRANTY

- A. Furnish five-year manufacturer's warranty for packaged water treatment equipment.
- B. Furnish one-year manufacturer's warranty for chemical metering equipment.

PART 2 - PRODUCTS

2.1 GENERAL

- A. The water treatment system shall be provided complete, with all necessary components, pumps, valves, instruments, control systems, accessories, and appurtenances to make a complete and operable system.
- B. Products that will be in contact with process water (raw, treated, chemical batching) shall have NSF 61 certification. No exceptions.

2.2 PERFORMANCE AND DESIGN CRITERIA:

- A. Flow Rate: 25 gpm.
- B. 2021 Average Daily Production: 5,150 gallons per day.
- C. 2041 Piped System Average Daily Production: 42,830 gallons per day, with second treatment skid.
- D. Finished Water Quality Goals:
1. Turbidity (NTU): < 0.1 NTU.
 2. Color (TCU): < 10 CU.
 3. Total Organic Carbon (TOC, mg/L): 46.3% Removal
 4. Iron (mg/L): < 0.2 mg/L
 5. Manganese (mg/L): <0.03 mg/L.
 6. Arsenic (µg/L): <5 µg/L.
 7. pH: 6.5 – 8.5.
 8. Total Trihalomethanes (TTHM µg/L): <60 µg/L.
 9. Haloacetic Acids (HAA5, µg/L): <40 µg/L.

TULUKSAK NATIVE COMMUNITY
WTP AND WASHTERIA

2.3 SERVICE CONDITIONS

- A. Influent Water Quality Conditions:
 - 1. Raw water will be pumped to the WTP and supplied at an influent pressure of 15 psi.
 - 2. Typical raw water quality is:
 - a. Arsenic: 36.3 µg/L.
 - b. Iron: 6.99 mg/L.
 - c. Manganese: 0.331 mg/L.
 - d. Total Organic Carbon: 47.1 mg/L.
 - e. Dissolved Organic Carbon: 44.8 mg/L.
 - f. True Color: 65 PCU.
 - g. pH 7.06
 - h. Turbidity 0.85 NTU.
 - i. Temperature: 35 F, preheated to 45 F.
- B. The WTP equipment will be located indoors with the room temperature between 60 and 70 F.
- C. Treatment Chemicals:
 - 1. Pre-Oxidant: 1% Potassium Permanganate dosed at 5 mg/L.
 - 2. Coagulant: 2%, dosed at 10 mg/L.
 - a. 80% Nalco 8185 (Aluminum Chlorohydrate).
 - b. 20% MagnaFloc LT27 (anionic polymer).
 - c. Diluted to 2% solution.
 - 3. Disinfectant: 2% Calcium Hypochlorite dosed at 1.5 mg/L.

2.4 MATERIALS

- A. Equipment shall fully comply with OSHA standards.
- B. Electrical material and equipment shall have NRTL listing wherever standards have been established by that agency.
- C. Complete electrical assembly shall meet requirements of National Electrical Code (NEC), National Electrical Manufacturers Association (NEMA), and National Fire Protection Association (NFPA) and be listed as an assembly (Control panels, VFDs etc).
- D. Components, including equipment, coatings and other parts of system, shall comply with AWWA standards.
- E. Terminal point connections shall be ANSI standard flanges.

2.5 OXIDATION VESSEL

- A. Closed FRP vessel with bottom diffuser to provide minimum of 40 minutes of reaction time at a flow rate of 25 gpm for permanganate with iron, manganese, and arsenic.
- B. Dimensions: 63" diameter x 99" high, 900 gallon capacity.
- C. NSF 61 certified.

TULUKSAK NATIVE COMMUNITY
WTP AND WASHTERIA

- D. Pentair #CH31327, or Approved Equal.

2.6 PACKAGED FILTER EQUIPMENT

- A. Single process train rated for the design flow rate and criteria defined in Article 2.2 and Article 2.3.
- B. The WTP operation shall be as simple as practical while maintaining finished water quality.
- C. The packaged water treatment equipment shall be factory assembled and tested to the greatest extent possible. Allowable connection points:
1. Post-oxidation coagulated water
 2. Filtered water
 3. Clarified solids removal
 4. Backwash supply and discharge
 5. Air scour
 6. Power
- D. Valves required by the treatment equipment supplier shall be installed at the filter fabrication facility to the greatest extent possible. Off-skid valves and piping will require the Supplier to provide a service technician to complete the plumbing, electrical, and controls connections in addition to the required start-up and commissioning time. The Installing Contractor will be responsible for installing the plumbing, electrical and controls up to the final connection points.
- E. The maximum dimensions for the footprint of the filter skid and the ceiling height are shown on the Drawings.
- F. Process Components
1. Raw Water Flow Control:
 - a. Supplier's standard via flow control valve to maintain constant flow rate through the treatment process.
 2. Chemical Blending (3)
 - a. Inject treatment chemicals into an inlet pipe section equipped with baffles for hydraulically induced blending of chemicals with incoming raw water.
 - b. Provide mixers for installation by Installing Contractor.
 - c. Provide static mixer Westfall 2800, or Approved Equal.
 3. Flocculation
 - a. Chambers: Minimum total retention time of 40 minutes at design flow rate through two chambers.
 - b. Furnish each flocculation chamber with an independent mechanical flocculator with variable-speed drive.
 - c. Furnish flow-straightening vanes to prevent vortexing, and to ensure establishment of a uniform particle contact/floc formation regime.
 - d. Velocity Gradient: $G=15-100/\text{sec}$.
 4. Clarification (inclined tubes ~~or adsorption clarifier~~)
 - a. Inclined Tubes:
 - 1) Provide entire surface with tube settlers fabricated from minimum 20-mil PVC.
 - 2) Minimum Horizontally Projected Bottom Area: Not less than 12 sq. ft. per sq. ft. of plan area

TULUKSAK NATIVE COMMUNITY
WTP AND WASHTERIA

- 3) Uniformly introduce flow into lower chamber section through low-velocity distribution header
 - 4) Include launder system in upper section, with overflow-leveling provisions
 - ~~b. Adsorption Clarifiers:~~
 - ~~1) Media depth: 48 inches.~~
 - ~~2) Media retention screen to allow for upflow, restrained operation, without fluidizing bed during normal forward flow operation. Screen shall be corrosion-resistant assembly that allows free passage of water but contains media particles.~~
 - ~~3) Media readily fluidized by addition of small amounts of diffused air.~~
 - ~~4) Media:~~
 - ~~a) Buoyant adsorption media specifically manufactured for use in water treatment. Media shall be buoyant with specific gravity of less than 1.0.~~
 - ~~b) Designed to optimize the removal of coagulated particles with clean bed head loss of less than 18 inches at 10 gpm per sq. ft.~~
 - ~~c) Capable of building solids to a head loss of 6 feet without disruption or movement of the media~~
 - c. Sludge wasting: operator adjustable, initially set to 15-20 minutes.
 - 1) Single sludge draw-off header.
 - 2) Automatic and timer controlled, entirely independent of filter function.
 - 3) Possibly only with system in ON operating mode.
5. Filtration
- a. Separate chamber with total area provided to establish maximum application rate of 2.0 gpm/sq-ft, except during backwash.
 - b. Provide wash-water trough with adjustable weirs.
 - c. Provide surface agitation assembly to augment backwash process.
 - d. Filter Media:
 - 1) Anthracite: Depth: 18"; Specific Gravity: 1.5-1.7; Effective Size: 0.9-1.1 mm; Uniformity Coefficient: <1.7.
 - 2) Silica Sand: Depth: 14"; Specific Gravity: 2.5-2.7; Effective Size: 0.45-0.55 mm; Uniformity Coefficient: <1.7; Silica Content: ≥98%.
 - 3) Garnet: Depth: 4"; Specific Gravity: 3.8-4.2; Effective Size: 1.5-1.7 mm; Uniformity Coefficient: <1.2.
 - 4) Gravel: Depth: As Required; Specific Gravity: 2.5-2.7; Effective Size: 3/16" (#4 mesh) – 3/8".
6. Filter Underdrain
- a. Provide for uniform collection of filtered water and even distribution of backwash water and air scour across the full area of the filter bed. It shall be capable of accepting air scour, without further modification, even if this is not provided initially.
 - b. Ensure mal-distribution of the backwash flow and air scour does not exceed +/- 5%.
 - c. Be of HDPE or stainless steel construction.
 - d. Incorporate either:
 - 1) A nozzle/plenum design. Nozzles shall be of plastic construction and incorporate a diffuser with slots no wider than 0.2mm. The nozzle spacing shall be no greater than 6.0 inch centers. The plenum shall be not less than 14 inches in depth and shall extend over the full area of the filter. The plenum roof shall be plane with no intrusions from supporting structures that