

# NELSON LAGOON POWER SYSTEM UPGRADE PROJECT

## ON SITE CONSTRUCTION

CIVIL DRAWINGS	
G1	VICINITY MAP
G.2	SURVEY CONTROL SHEET
C1	SITE PLAN
C2	TYPICAL SECTIONS
ARCHITECTURAL DRAWINGS	
A1	FLOOR PLAN, REFLECTED CEILING PLAN, CODE ANALYSIS, & GENERAL NOTES
A2.1	INTERIOR ELEVATIONS
A2.2	DOOR & WINDOW DETAILS & SCHEDULE
A3	EXTERIOR ELEVATIONS & ROOFING NOTES & TRIM DETAILS
A4	BUILDING SECTIONS & DETAILS
STRUCTURAL DRAWINGS	
S1.1	FOUNDATION PLAN, CODE ANALYSIS & STRUCTURAL NOTES
S1.2	FOUNDATION DETAILS
S2	MODULE FRAMING PLANS & DETAILS
S3	MODULE SECTIONS & DETAILS
S4	ROOF FRAMING PLAN & DETAILS
S5.1	STAIRS, LANDINGS, LOADING DOCK, & RADIATOR SUPPORT PLAN
S5.2	STAIRS/LANDINGS FABRICATION DETAILS
S5.3	LOADING DOCK FABRICATION DETAILS
S5.4	RADIATOR SUPPORT FABRICATION DETAILS


MECHANICAL DRAWINGS	
M1.1	MECHANICAL LEGENDS & SCHEDULES
M1.2	WARNING SIGN & FIRE EXTINGUISHER PLAN, SIGN & VALVE TAG SCHEDULES
M1.3	SYSTEM START UP & SEQUENCE OF OPERATIONS
M1.4	OVERALL PROJECT AREA PLAN & POWER PLANT AREA MECHANICAL SITE PLAN
M1.5	POWER PLANT ENLARGED MECHANICAL SITE PLAN & DETAILS
M1.6	INTERMEDIATE TANK INSTALLATION ELEVATIONS & DETAILS
M1.7	INTERMEDIATE TANK DETAILS
M1.8	4,000 GALLON DOUBLE WALL INTERMEDIATE TANK FABRICATION DETAILS
M2.1	MECHANICAL PENETRATIONS PLAN, ELEVATIONS & DETAILS
M2.2	MECHANICAL PENETRATION DETAILS
M2.3	MECHANICAL SUPPORT PLANS & DETAILS
M2.4	MECHANICAL SUPPORT HORIZONTAL WALL STRUT INSTALLATION
M2.5	MECHANICAL SUPPORT VERTICAL WALL STRUT INSTALLATION
M3.1	EQUIPMENT LAYOUT PLAN, SECTION, & DETAILS
M3.2	WALL ELEVATIONS & PIPING DETAILS
M3.3	MECHANICAL DETAILS
M3.4	GENERATOR FABRICATION DETAILS
M4.1	COOLANT & HEAT RECOVERY PIPING PLAN & DETAILS
M4.2	COOLANT & HEAT RECOVERY ISOMETRICS & DETAILS
M4.3	COOLANT & HEAT RECOVERY PIPING DETAILS
M4.4	GLYCOL STORAGE & EXPANSION TANKS FABRICATION
M5.1	DIESEL FUEL & USED OIL PIPING PLAN, DIAGRAM, & DETAILS
M5.2	DIESEL FUEL & USED OIL PIPING ELEVATIONS & DETAILS
M5.3	USED OIL HOPPER & BLENDER INSTALLATION DETAILS
M5.4	200 GALLON DAY TANK FABRICATION
M5.5	USED OIL BLENDER FILTER BANK LAYOUT & CONFIGURATION
M5.6	USED OIL BLENDER TYPICAL FILTER HOUSING DETAILS
M5.7	USED OIL BLENDER 25 GALLON HOPPER FABRICATION
M6	EXHAUST & CRANK VENT PLAN & DETAILS
M7.1	VENTILATION PLAN & DETAILS
M7.2	SHEET METAL FABRICATION DETAILS
M8.1	HEAT RECOVERY SYSTEM OVERALL PLAN, SCHEMATIC, & EQUIPMENT SCHEDULE
M8.2	HEAT RECOVERY SYSTEM ARCTIC PIPE DETAILS
M8.3	HEAT RECOVERY SYSTEM TOURISM BUILDING PLAN & DETAILS
M8.4	HEAT RECOVERY SYSTEM STORAGE COMPOUND PLANS & PIPING ELEVATION
M8.5	HEAT RECOVERY SYSTEM STORAGE COMPOUND PIPING ISOMETRIC & DETAILS
M8.8	HEAT RECOVERY SYSTEM STORAGE COMPOUND PIPING DETAILS
M8.7	HEAT RECOVERY SYSTEM ICEHOUSE PLAN, PIPING ISOMETRIC, & DETAILS
M8.8	HEAT RECOVERY SYSTEM ICEHOUSE PIPING DETAILS
FS1	FIRE SUPPRESSION SYSTEM PLAN, SECTION, LEGEND, & NOTES

ELECTRICAL – POWER PLANT	
E1.1	ELECTRICAL LEGENDS & SCHEDULES
E1.2	POWER PLANT AREA ELECTRICAL SITE PLAN
E1.3	POWER PLANT ENLARGED ELECTRICAL SITE PLAN
E1.4	POWER PLANT AREA STAKING SHEET & DISTRIBUTION DETAILS
E1.5	POWER PLANT SITE ELECTRICAL DETAILS
E1.6	POWER PLANT AREA ELECTRICAL SERVICE DETAILS
E1.7	POWER PLANT COMMUNICATION PLAN & DETAILS
E2	MODULE GROUNDING PLAN & DETAILS
E3.1	WIREWAY PLAN, BUILDING SECTION, & DETAILS
E3.2	ELEVATIONS & DETAILS
E3.3	ELEVATIONS & DETAILS
E4.1	RECEPTACLE & LIGHTING PLANS & PANELBOARD
E4.2	STATION SERVICE PLAN, DETAILS, & PANELBOARD
E5	INSTRUMENTATION & DATA PLAN & DETAILS
E6.1	SWITCHGEAR ENCLOSURE LAYOUT, SETTING TABLE, & DETAILS
E6.2	SWITCHGEAR ONE–LINE & DETAILS
E6.3	24VDC ENGINE WIRING JUNCTION BOX
E7.1	DAY TANK CONTROL PANEL LOGIC DIAGRAM & BILL OF MATERIALS
E7.2	DAY TANK CONTROL PANEL LAYOUT & TERMINAL STRIPS
E7.3	DAY TANK CONTROL PANEL NOTES, SEQUENCE OF OPERATIONS & INTERCONNECT DETAILS
E7.4	DAY TANK FILTER WATER INDICATION PANEL
E8	HEAT RECOVERY SYSTEM END USER BUILDINGS ELECTRICAL PLANS
2004	BFU E–07 LADDER DIAGRAM TANK FARM CONTROL
2004	BFU E–08 INTERCONNECT DIAGRAM & NOTES
2004	BFU E–09 POWER PLANT TANK – TRANSFER CONTROL PANEL

ELECTRICAL – DISTRIBUTION	
E10.1	DISTRIBUTION LEGEND, ABBREVIATIONS, SPECIFICATIONS & NOTES
E10.2	DISTRIBUTION DETAILS
E10.3	TRENCH DETAILS
E10.4	DISTRIBUTION ONE–LINE DIAGRAM
E11.0	OVERALL DISTRIBUTION SITE PLAN
E11.1	DISTRIBUTION DEMOLITION PLAN (1 OF 7)
E11.2	DISTRIBUTION DEMOLITION PLAN (2 OF 7)
E11.3	DISTRIBUTION DEMOLITION PLAN (3 OF 7)
E11.4	DISTRIBUTION DEMOLITION PLAN (4 OF 7)
E11.5	DISTRIBUTION DEMOLITION PLAN (5 OF 7)
E11.6	DISTRIBUTION DEMOLITION PLAN (6 OF 7)
E11.7	DISTRIBUTION DEMOLITION PLAN (7 OF 7)
E12.1	DISTRIBUTION PLAN (1 OF 7)
E12.2	DISTRIBUTION PLAN (2 OF 7)
E12.3	DISTRIBUTION PLAN (3 OF 7)
E12.4	DISTRIBUTION PLAN (4 OF 7)
E12.5	DISTRIBUTION PLAN (5 OF 7)
E12.6	DISTRIBUTION PLAN (6 OF 7)
E12.7	DISTRIBUTION PLAN (7 OF 7)



THIS DRAWING SET INCLUDES DRAWINGS THAT SHOW WORK THAT IS INCLUDED IN THIS CONTRACT AND REFERENCE DRAWINGS THAT SHOW WORK PERFORMED UNDER THE PRIOR MODULE ASSEMBLY CONTRACT. SEE RED NOTES ON EACH SHEET FOR DELINEATION OF SCOPE.

THIS DRAWING SET SHOWS WORK THAT IS UNDER THE BASE BID AND ADDITIVE ALTERNATES. ALL WORK SHOWN IS INCLUDED IN THE BASE BID UNLESS SPECIFICALLY INDICATED AS ADDITIVE ALTERNATE.






























ISSUED FOR  
CONSTRUCTION  
MAY 2023



<div></div> <div>ALASKA ENERGY AUTHORITY</div>		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: ON-SITE CONSTRUCTION SCHEDULE OF DRAWINGS		
<div><div>Gray Stassel Engineering, Inc.</div></div> <div>P.O. 111405, Anchorage, AK 99511 (907)349-0100</div>	DRAWN BY: BCG	SCALE: NO SCALE
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP G1	SHEET:
	PROJECT NUMBER:	G0



PIPING LEGEND	
	BUTTERFLY VALVE
	BALL VALVE
	CHECK VALVE
	HOSE END DRAIN VALVE
	GAUGE COCK
	Y-STRAINER
	AUTOMATIC AIR VENT
	FLEXIBLE CONNECTOR
	FLANGED JOINT
	UNION
	ELBOW TURNED UP
	ELBOW TURNED DOWN
	PIPING CONNECTION (TEE)
	PIPING REDUCER
	DIRECTION OF FLOW
INSTRUMENT/CONTROL LEGEND	
	PRESSURE GAUGE
	ANALOG THERMOMETER
	DIGITAL THERMOMETER
	TEMPERATURE TRANSMITTER
	PRESSURE TRANSMITTER
	DIFFERENTIAL PRES GAUGE
	FLOW METER
	FLOAT SWITCH
	LOW COOLANT SWITCH
	TANK LEVEL MONITOR
	LEVEL SENSOR PROBE
	GLYCOL LEVEL SENSOR
NOTE: SEE ELECTRICAL FOR ADDITIONAL DETAIL ON CONTROL & INSTRUMENTATION DEVICES	
ABBREVIATIONS	
Ø	DIAMETER (PHASE)
A	AMPS
AFF	ABOVE FINISHED FLOOR
BTU	BRITISH THERMAL UNIT
DFR	DIESEL FUEL RETURN
DFS	DIESEL FUEL SUPPLY
ECR	ENGINE COOLANT RETURN
ECS	ENGINE COOLANT SUPPLY
EWI	ENTERING WATER TEMPERATURE
EXIST	EXISTING
FPT	FEMALE PIPE THREAD
GA	GAUGE
GALV	GALVANIZED
GPM	GALLONS PER MINUTE
GRC	GALVANIZED RIGID CONDUIT
HP	HORSEPOWER
HYR	HYDRONIC RETURN
HYS	HYDRONIC SUPPLY
ID	INSIDE DIAMETER
KW	KILOWATT
LT	LIQUID TIGHT
LWT	LEAVING WATER TEMPERATURE
MAX	MAXIMUM
MBH	THOUSAND BTU PER HOUR
MIN	MINIMUM
MPT	MALE PIPE THREAD
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
OC	ON CENTER
OD	OUTSIDE DIAMETER
PRV	PRESSURE RELIEF VALVE
PSI	POUNDS/PER SQUARE INCH
PSID	PSI DIFFERENTIAL
PSIG	PSI GAUGE
SCH	SCHEDULE
TDH	TOTAL DEVELOPED HEAD
TYP	TYPICAL
UOR	USED OIL RETURN
V	VOLTS
W	WATTS
WG	WATER GAUGE



ENGINE COOLING SYSTEM EQUIPMENT SCHEDULE:				
SYMBOL	SERVICE/FUNCTION	DESCRIPTION	MANUFACTURER/MODEL	
<u>R-1</u> <u>R-2</u>	GLYCOL RADIATOR	SINGLE PASS, 4 ROW, VERTICAL CORE, 3" FLANGED CONNECTIONS, GALVANIZED COATING, EXPANDED METAL GUARD. 6,000 BTU/MIN AT 77°F AMBIENT, 50 GPM 50% ETHYLENE GLYCOL AT 192F IN, 0.22 PSI MAX GLYCOL PRESSURE DROP. 3 HP, 460 V, 3 PH, MOTOR SUITABLE FOR VFD OPERATION AT 10:1 TURNDOWN RATIO.	DIESEL RADIATOR PART NO. DR3490	
<u>TV-1</u>	COOLANT THERMOSTATIC VALVE	3" ANSI 125# FLAT FACED FLANGES, CAST IRON BODY, FACTORY SET NON-ADJUSTABLE FIELD REPLACEABLE THERMOSTATIC ELEMENTS, 175F NOMINAL TEMPERATURE	FPE PART NO. A3010-175	
<u>TV-2</u>	HEAT RECOV. THERMOSTATIC VALVE	2" ANSI 125# FLAT FACED FLANGES, CAST IRON BODY, FACTORY SET NON-ADJUSTABLE FIELD REPLACEABLE THERMOSTATIC ELEMENTS, 185F NOMINAL TEMPERATURE,	FPE PART NO. AF2012-185	
<u>ET-1</u>	GEN COOLANT EXPANSION TANK	24 GALLON CAPACITY TANK, 12.75" O.D x 48" LONG FABRICATED STEEL TANK, SEE FABRICATION DETAIL	CUSTOM FABRICATION	
<u>HP-EC</u>	ENGINE COOLANT FILL HAND PUMP	DOUBLE ACTION PISTON HAND PUMP, ALUM HOUSING, SS PISTON SHAFT & LINER, BUNA-N SEALS, ANTI-SIPHONING VALVE.	GPI MODEL HP-100	
<u>G-EC</u>	ENGINE COOLANT GLYCOL TANK LEVEL GAUGE	MAGNETIC OPERATED SPIRAL GAUGE FOR #1 DIESEL, 25 PSIG MAX OPERATING PRESSURE, 35" LIQUID COLUMN PLUS 4" RISER.	ROCHESTER MODEL 8660	
<u>GT-1</u>	ENGINE COOLANT GLYCOL STORAGE TANK	60 GALLON CAPACITY, 36"x10"x44"HIGH FABRICATED RECTANGULAR STEEL TANK, SEE FABRICATION DETAIL	CUSTOM FABRICATION	
HEAT RECOVERY & PLANT HEATING EQUIPMENT SCHEDULE:				
<u>HX-1</u>	POWER PLANT HEAT EXCHANGER	316 SS PLATES, BRAZED CONST. 2" SOLDER CUP PORTS, 290 MBH MIN CAPACITY. PRIMARY: 35 GPM 195F EWT (50% ETHYLENE) 2.0 PSI MAX WPD, SECONDARY: 28 GPM 185F LWT (50% PROPYLENE) 1.3 PSI MAX WPD	SWEP INTERNATIONAL AB B120Thx60/1P	
<u>P-CUH1</u>	CONTROL ROOM HEAT	1 GPM AT 18' TDH, 1/25HP, 115V, 1Ø. PROVIDE WITH 3/4" SOLDER COMPANION SHUT OFF FLANGES, GASKETS, & BOLTS.	GRUNDFOS UPS 15-58FC SPEED 3	
<u>P-HR1A</u>	HEAT RECOV. PRIMARY	30 GPM AT 7' TDH, 1/8 HP, 115V, 1Ø. PROVIDE WITH 1-1/4" NPT COMPANION FLANGES, GASKETS, & BOLTS. SET TO CP-1	GRUNDFOS MAGNA1 32-60 F CONSTANT PRESSURE	
<u>P-HR1B</u>	HEAT RECOV. SECONDARY	20 GPM AT 21' TDH, 1/3 HP, 115V, 1Ø. PROVIDE WITH 1-1/2" NPT COMPANION FLANGES, GASKETS, & BOLTS. SET TO CP-3. FIELD INSTALL OWNER FURNISHED CIM 500 MODULE.	GRUNDFOS MAGNA3 40-80 F CONSTANT PRESSURE CIM 500 PART# 98301408	
<u>CUH-1</u>	CONTROL ROOM HEAT	WALL MOUNTED HOT WATER CABINET UNIT HEATER, 17 MBH AT 1 GPM 180F EWT & 60F EAT.	TOYOTOMI HC-190 WITH WALL MOUNT BRACKET	
<u>ET-2</u>	HEAT RECOV. EXP. TANK	BLADDER TYPE EXPANSION TANK, 44 GALLON TANK, 22 GALLON ACCEPTANCE VOL, 125 PSIG WORKING PRESSURE, 12 PSIG PRE-CHARGE.	AMTROL AX-80	
PIPE/TUBING STRUT CLAMP SCHEDULE				
PIPE/TUBE	CLAMP #	PIPE/TUBE	CLAMP #	NOTES: 1) ALL CLAMP NUMBERS ARE B-LINE. EQUIVALENT EQUALS ACCEPTABLE. 2) ALL COPPER TUBE CLAMPS TO BE CUSHIONED, VIBRA-CLAMP. 3) ALL STEEL PIPE CLAMPS NOT CUSHIONED. USE FOR ALL STEEL PIPE AND RIGID CONDUIT. 4) SEE PLANS, ELEVATIONS, ISOMETRICS, AND DETAILS FOR ACTUAL PIPE SIZES.
1/2" COPPER	BVT062	1/2" STEEL	B2008	
3/4" COPPER	BVT087	3/4" STEEL	B2009	
1" COPPER	BVT112	1" STEEL	B2010	
1-1/4" COPPER	BVT125	1-1/4" STEEL	B2011	
1-1/2" COPPER	BVT162	1-1/2" STEEL	B2012	
2" COPPER	BVT212	2" STEEL	B2013	
2-1/2" COPPER	BVT262	2-1/2" STEEL	B2014	
3" COPPER	BVT312	3" STEEL	B2015	

VENTILATION EQUIPMENT SCHEDULE:			
SYMBOL	SERVICE/FUNCTION	DESCRIPTION	MANUFACTURER/MODEL
<u>EF-1</u> <u>EF-2</u>	GENERATION ROOM EXHAUST FANS	DIRECT DRIVE 14"Ø PROPELLER SIDEWALL EXHAUST FAN, 2,100 CFM AT 0.375" SP, 1,750 RPM. SPECIAL 1/2 HP, 115 V, 1 PH VARIGREEN MOTOR WITH OPTIONAL 0-10V LEADS AND OPTIONAL TRANSFORMER	GREENHECK SE1-14-436-VG (1/2 HP)
<u>EF-1</u> <u>EF-2</u> COMB.	FAN & INTAKE DAMPERS	OPPOSED BLADE LOW-LEAKAGE CONTROL DAMPER, AIRFOIL BLADES, GALV STEEL CONSTRUCTION, ACETAL BEARINGS, STAINLESS STEEL JAMB SEALS, TPE BLADE SEALS.	GREENHECK VCD-33
<u>MD</u>	MOTORIZED DAMPER ACTUATOR	MULTI-VOLTAGE SPRING RETURN ACTUATOR	BELIMO AF-BUP
FUEL SYSTEM EQUIPMENT SCHEDULE			
<u>P-DF1</u>	DAY TANK FILL PUMP	ROTARY GEAR PUMP, 5 GPM @ 25 PSID, C-FRAME MOUNT, 1" FPT INLET AND OUTLET, IRON CONSTRUCTION, STEEL SHAFT, CARBON GRAPHITE BUSHINGS, BUNA-N LIP SEAL, WITH 75 PSID INTERNAL PRV. DIRECT MOUNT TO FOOT MOUNT 56C FRAME MOTOR, 1,200 RPM, 1/2 HP, 115VAC.	GORMAN RUPP GMC1DC4-B-40C PUMP AND CENTURY #C827 MOTOR FOR FIELD ASSEMBLY
<u>P-DF2</u>	DIESEL CIRC. PUMP		
<u>P-U01</u>	USED OIL DRAIN PUMP		
		ROTARY GEAR PUMP GEAR PUMP - 1.2 GPH @ 15 PSID, 1/8" FPT INLET AND OUTLET, PEEK GEARS, PTFE SEALS, MAGNETICALLY COUPLED TO FOOT MOUNT 56C FRAME MOTOR, 1,725 RPM, 1/2 HP, 115VAC.	MICROPUMP GA-V21J8FS.A PUMP WITH #81518 ADAPTER & CENTURY #C826V1 MOTOR
<u>HP-DT</u>	DAY TANK FILL HAND PUMP	DOUBLE ACTION PISTON HAND PUMP, ALUM HOUSING, SS PISTON SHAFT & LINER, BUNA-N SEALS, ANTI-SIPHONING VALVE.	GPI MODEL HP-100
<u>G-DT</u>	DAY TANK LEVEL GAUGE	MAGNETIC OPERATED SPIRAL GAUGE FOR #1 DIESEL, 25 PSIG MAX OPERATING PRESSURE, 35" LIQUID COLUMN PLUS 4" RISER.	ROCHESTER MODEL 8660
<u>M-DT</u>	DAY TANK METER	STEEL BODY, 1" ANSI 150# FLANGED ENDS, 20-800 GPH FLOW RANGE, O-RINGS AND SEALS COMPATIBLE WITH #1 DIESEL, DIRECT READ 6-DIGIT REGISTER TO 0.1 GAL, DRY CONTACT PULSER.	ISTEC CONTOIL 9226-F
<u>F-DT</u>	DAY TANK FILTER	THREE FILTER BANK WITH INDIVIDUAL FILTER ISOLATION VALVES, IMPACT RESISTANT "SEE-THRU" BOWLS, 15 PSIG WORKING PRESSURE. WITH 1/2" WATER PROBE PORT & 3 EACH WATER-IN-FUEL DETECTION KITS. INSTALL 3 EACH 10 MICRON AQUABLOC FILTER ELEMENTS & FURNISH 3 SPARES.	RACOR TURBINE 791000FV10-P WATER-IN-FUEL RR30880E ELEMENTS 2020V10
<u>F-GEN</u>	GENSET FILTER	SINGLE FILTER, IMPACT RESISTANT "SEE-THRU" BOWL, 15 PSIG WORKING PRESSURE. INSTALL 10 MICRON AQUABLOC FILTER ELEMENTS & FURNISH 1 SPARE.	RACOR TURBINE 1000FV-10 ELEMENT 2020V10
<u>F-UOB</u>	USED OIL BLENDER FILTER	CUSTOM FABRICATED FILTER BANK. FURNISH WITH TWO STAGE ELEMENTS: 10 MICRON HYDROSORB II FILTER 2 MICRON PARTICULATE FILTER	CIM-TEK #30034 (HYDROSORB) CIM-TEK #30066 (2 MICRON)
		PROVIDE 3 OF EACH ELEMENT TYPE	
<u>ABV-1</u>	1" ACTUATED BALL VALVE (ON SITE)	ACTUATED BALL VALVE ASSEMBLY RATED TO -50F. TYPE 304 STAINLESS STEEL FABRICATED COUPLING BRACKET, SHAFT, AND FASTENERS CONFIGURED TO ALLOW WRENCH ACCESS FOR MANUAL OPERATION OF VALVE WITHOUT REMOVING ACTUATOR. LOW TEMP BALL VALVE, 150# RF FLANGED ENDS. ELECTRIC ACTUATOR WITH OPERATING VOLTAGE, NEMA RATING, AND TORQUE AS INDICATED. CONFIGURE WITHOUT MANUAL OVERRIDE SHAFT EXTENSION. FURNISH WITH PTC SELF REGULATING HEATER, AUXILIARY SWITCH SET (AUXILIARY SWITCHES 3 & 4), AND EXXON BEACON 325 SEVERE COLD LUBRICANT.	VALVE ASSEMBLY: DG VALVE (780) 413-1760  1" BALL VALVE - KECKLEY PART # BVF1RF2RSSRGSL-100  2" BALL VALVE - KECKLEY PART # BVF1RF2RSSRGSL-200  NEMA 7 ACTUATOR - 600 IN-LBS TORQUE, 10 SECOND STROKE TIME, 0.50 LOCKED ROTOR AMPS. RCS MODEL SXR-1023


INSTRUMENTATION SCHEDULE			
SYMBOL	SERVICE/FUNCTION	DESCRIPTION	MANUFACTURER/MODEL
<u>TT</u>	TEMPERATURE TRANSMITTER	RTD, 20-240°F RANGE, 4-20mA OUTPUT, 1/2" NPT PIPING CONNECTION, 6mm DIAMETER BY 2.5" LONG STEM, HIRSCHMANN ELECTRICAL CONNECTION	NOSHOK 800-20/240-1-1-8-8-025-6
<u>PT</u>	PRESSURE TRANSMITTER	0-60 PSIG RANGE, 4-20mA OUTPUT, 1/4" NPT PIPING CONNECTION, HIRSCHMANN ELECTRICAL CONNECTION	NOSHOK 100-60-1-1-2-2-7
<u>LCA</u>	GLYCOL TANK LOW COOLANT ALARM	LOW COOLANT LEVEL ALARM FLOAT SWITCH, SEE MECHANICAL FOR INSTALLATION DETAILS	MURPHY EL-150-K1
<u>GLS</u>	GLYCOL TANK LEVEL SENSOR PROBE	12" PROBE, 2" NPT TANK CONNECTION, SS FLOAT, 1/4" RESOLUTION, NEMA 4 ENCLOSURE WITH SIGNAL CONDITIONER AND 1/2" NPT CONDUIT CONNECTION	INNOVATIVE COMPONENTS CLM-2012-SS 5343A 2-WIRE TRANSMITTER
<u>FS</u>	DAY TANK/HOPPER FLOAT SWITCH	VERTICAL ACTION FLOAT SWITCH, REVERSIBLE 70VASPST NC/NO SWITCH, 1/8" NPT, 1"MAX Ø BUNA-N FLOAT FOR S.G.=.47, MINIMUM 60" LONG PVC COATED #20 AWG LEAD WIRES	INNOVATIVE COMPONENTS LS-12-111/2
<u>TLM</u>	TANK LEVEL MONITOR PANEL	TANK LEVEL MONITOR CONSOLE FOR UP TO SIX TANKS, COLOR LCD SCREEN, ETHERNET CONNECTION WITH WEB INTERFACE, PROGRAMMABLE VOLUME CALCULATIONS WITH TEMPERATURE COMPENSATION	FRANKLIN/INCON EVO 200
<u>LSP</u>	DAY TANK/HOPPER TANK LEVEL SENSOR PROBE (SHOP FAB.)	TOP-MOUNT TANK PROBE WITH INSTALLATION KIT FOR 2" NPT RISER, WATER TIGHT COMPRESSION GLAND FITTING FOR CABLE ENTRANCE. FRANKLIN FUEL SYSTEMS, NO SUBSTITUTES. PROBE AND RISER LENGTH AS INDICATED ON INSTALLATION DETAILS.	4' TANK PROBE: FMP-LL3-53-I 2' TANK PROBE: FMP-LL3-29-I FLOAT: TSP-IDF2 2" FOR DIESEL INSTALLATION KIT: TSP-C2A
<u>LSP</u>	INTERMEDIATE TANK LEVEL SENSOR PROBE (ON SITE)	TOP-MOUNT TANK PROBE WITH INSTALLATION KIT FOR 2" NPT RISER, WATER TIGHT COMPRESSION GLAND FITTING FOR CABLE ENTRANCE. FRANKLIN FUEL SYSTEMS, NO SUBSTITUTES. PROBE AND RISER LENGTH AS INDICATED ON INSTALLATION DETAILS.	7'Ø TANK PROBE: FMP-LL3-89-I FLOAT: TSP-IDF2 2" FOR DIESEL INSTALLATION KIT: TSP-C2A
<u>LS</u>	INTERMEDIATE TANK THREE POINT FLOAT TYPE LEVEL SWITCH (ON SITE)	THREE POINT MAGNETIC FLOAT SWITCH - 2-1/2" ANSI 150# FLAT FACE FLANGE MOUNT, 3/4" NPT CONDUIT ENTRY, 8MM DIAMETER FIXED LENGTH STAINLESS STEEL STEM, 3 EACH 1.2" MAX. DIAMETER STAINLESS STEEL FLOATS FOR MINIMUM S.G.=0.65, 50VA FORM A CONTACTS. 47.25" OVERALL STEM LENGTH. ACTUATION LENGTHS 13"(N.O.) & 18"(N.O.) & 46"(N.C.).	APC MODEL FLE-0A2-B3-B-A2-E-47.25in.-13in.NO-18in.NO-46in.NC

EQUIPMENT REQUIREMENTS FOR APPROVED EQUALS (APPLIES TO ALL SCHEDULES): SPECIFIC PARTS MANUFACTURER AND MODEL SELECTED NOT ONLY TO MEET PERFORMANCE FUNCTION BUT ALSO TO COORDINATE AND INTERFACE WITH OTHER DEVICES AND SYSTEMS. APPROVED EQUAL SUBSTITUTIONS WILL BE ALLOWED ONLY BY ENGINEER'S APPROVAL. TO OBTAIN APPROVAL, SUBMITTALS MUST CLEARLY DEMONSTRATE HOW SUBSTITUTE ITEM MEETS OR EXCEEDS SPECIFIED ITEM QUALITY AND PERFORMANCE CHARACTERISTICS AND ALSO COMPLIES WITH MECHANICAL AND/OR ELECTRICAL CONNECTIONS AND PHYSICAL LAYOUT REQUIREMENTS.

ALL MATERIALS AND EQUIPMENT ON SCHEDULES THIS SHEET WERE FURNISHED AS PART OF THE PRIOR MODULE ASSEMBLY PROJECT EXCEPT FOR THOSE ITEMS SPECIFICALLY INDICATED IN RED CLOUDS WHICH ARE TO BE FURNISHED AND INSTALLED AS PART OF THE ON SITE SCOPE.

1	DELETE FLOW METER, CHANGE P-HR1B TO MAGNA 3, & ADD OWNER FURN CIM 500	8/16/23	BCG
REV.	DESCRIPTION	DATE	BY
<div> ALASKA ENERGY AUTHORITY</div>			
PROJECT: <div>NELSON LAGOON POWER SYSTEM UPGRADE</div>			
TITLE: <div>MECHANICAL LEGENDS &amp; SCHEDULES</div>			
<div> Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100</div>		DRAWN BY: JTD DESIGNED BY: BCG FILE NAME: NELS PP M1 PROJECT NUMBER:	SCALE: AS NOTED DATE: 5/30/23 SHEET: <div>M1.1</div>





VALVE TAG SCHEDULE:	
WHITE (EQUIPMENT)	
01	"GEN#1 100KW" (DECAL)
02	"GEN#2 100KW" (DECAL)
03	"GEN#3 65KW" (DECAL)
GREEN (DIESEL FUEL)	
21	"NORMALLY OPEN, CLOSE ONLY FOR EMERGENCIES & TEMPORARY MAINTENANCE OF DAY TANK & DEVICES"
22	"NORMALLY CLOSED, OPEN ONLY FOR HAND PRIMING DAY TANK"
23	"NORMALLY OPEN, CLOSE ONLY FOR TEMPORARY MAINTENANCE OF BLENDER"
24	"NORMALLY OPEN, CLOSE ONLY FOR TEMPORARY MAINTENANCE OF ENGINE"
25	"NORMALLY CLOSED, OPEN ONLY TO FILL TANK"
BROWN (USED OIL)	
41	"NORMALLY CLOSED, OPEN ONLY FOR ENGINE OIL CHANGE"
42	"BLENDER FILTER #1, 10 MICRON HYDROSORB" (DECAL)
43	"BLENDER FILTER #2, 2 MICRON PARTICULATE" (DECAL)
44	"CHECK CONDENSATE LEVEL DAILY, DRAIN AT EACH OIL CHANGE" (DECAL)
PINK (COOLING/ETHYLENE GLYCOL)	
51	"NORMALLY CLOSED, OPEN ONLY FOR ADDING COOLANT – ETHYLENE GLYCOL ONLY"
52	"NORMALLY CLOSED, OPEN ONLY ON HIGH COOLANT TEMPERATURE ALARM"
53	"NORMALLY OPEN, CLOSE ONLY ON HIGH COOLANT TEMPERATURE ALARM"
54	"NORMALLY OPEN, HEAT RECOVERY SUPPLY"
55	"NORMALLY OPEN, HEAT RECOVERY RETURN"
YELLOW (HEAT RECOVERY/PROPYLENE GLYCOL)	
61	"NORMALLY CLOSED, OPEN ONLY FOR ADDING FLUID – PROPYLENE GLYCOL ONLY"
62	"NORMALLY OPEN, HEAT RECOVERY SUPPLY"
63	"NORMALLY OPEN, HEAT RECOVERY RETURN"
64	"NORMALLY CLOSED, OPEN ONLY FOR AIR BLEED & PURGE"
65	"NORMALLY OPEN, CLOSE ONLY TO CLEAN STRAINER"
66	"NORMALLY OPEN, CLOSE ONLY FOR TEMPORARY MAINTENANCE"
RED (ELECTRICAL)	
71	"THIS PANEL IS POWERED FROM THE MAIN TANK FARM PANEL. LOCK & TAG OUT PRIOR TO SERVICING"
SPECIFICATIONS:	
VALVE TAGS – 3"x5"x.08" ALUMINUM, 3/16" HOLES IN ALL FOUR CORNERS, BLACK GERBER THERMAL TRANSFER FILM PRINTED LETTERS ON GERBER 220 HIGH PERFORMANCE VINYL BACKGROUND, COLOR AS INDICATED, ONE SIDE ONLY. WARNING LITES OR APPROVED EQUAL.	
DECALS – WHERE NOTED AS DECALS PROVIDE WITHOUT ALUMINUM BACKING PLATE.	
INSTALLATION NOTES:	
1) SEE DRAWINGS THAT FOLLOW FOR LOCATIONS OF ALL SPECIFIC FUNCTION TAGS.	
2) SECURE EACH METAL TAG TIGHT TO VALVE, PIPE, OR DEVICE WITH STAINLESS STEEL SAFETY WIRE THROUGH ALL FOUR CORNERS OR FASTEN TO ADJACENT WALL OR SECTION OF STRUT WITH SCREWS.	
3) APPLY DECALS TO SMOOTH SURFACES OF EQUIPMENT OR ON ADJACENT WALL. ENSURE SURFACE IS CLEAN, DRY, AND WARM PRIOR TO APPLICATION. USE HEAT GUN AS REQUIRED.	
4) FOR ALL VALVES NOT INDICATED WITH A SPECIFIC FUNCTION TAG PROVIDE 1–1/2" ROUND BRASS TAG LABELED "N.O." FOR NORMALLY OPEN VALVES AND 1–1/2" SQUARE BRASS TAG LABELED "N.C." FOR NORMALLY CLOSED VALVES. SECURE TAGS TO VALVE OR ADJACENT PIPE WITH BEADED BRASS CHAIN.	

WARNING SIGN & INFORMATIONAL PLACARD SCHEDULE:	
PROVIDE DECALS AND SIGN BOARDS AS SPECIFIED BELOW IN ACCORDANCE WITH THE SCHEDULE. INSTALL WHERE SHOWN ON THE WARNING SIGN/PLACARD PLAN THIS SHEET AND OTHER REFERENCED SHEETS.	
# DECALS	DECALS TO BE WHITE NON–REFLECTIVE VINYL BACKGROUND, 3M 3650–10, WITH 3M SERIES 225 HIGH PERFORMANCE VINYL LETTERS, ONE SIDE ONLY, SELF ADHESIVE BACK. NOMINAL 10"x14" SIZE UNLESS INDICATED OTHERWISE OR REQUIRED TO BE LARGER FOR SPECIFIED LETTER SIZE. WARNING LITES OR EQUAL. APPLY DECALS TO SMOOTH SURFACES OF DOORS, EQUIPMENT, OR ON ADJACENT WALL. ENSURE SURFACE IS CLEAN, DRY, AND WARM PRIOR TO APPLICATION. USE HEAT GUN AS REQUIRED.
# BOARDS	SIGN BOARDS TO BE EQUAL TO DECALS EXCEPT MOUNTED ON 0.08" ALUMINUM PLATE. PROVIDE 3/16" HOLES IN ALL FOUR CORNERS. ATTACH TO CHAIN LINK FENCING WITH HOG RINGS OR STAINLESS STEEL TIES. ATTACH TO WALLS OR STRUCTURES WITH STAINLESS STEEL SCREWS OR BOLTS.
WARNING SIGNS – RED LETTERING ON WHITE BACKGROUND.	
A	"FIRE ALARM"
C	"CAUTION, ROOM PROTECTED BY WATER MIST FIRE PROTECTION SYSTEM, IN CASE OF FIRE KEEP DOOR CLOSED AND DO NOT ENTER"
D	"FLASHING LIGHT MEANS FIRE SUPPRESSION AGENT HAS DISCHARGED"
1	"DANGER FLAMMABLE, NO SMOKING OR OPEN FLAMES"
10	"CAUTION: THIS UNIT STARTS AUTOMATICALLY, LOCK & TAG OUT PRIOR TO SERVICE"
11	"DANGER HIGH VOLTAGE, AUTHORIZED PERSONNEL ONLY"
12	"CAUTION HEARING & EYE PROTECTION REQUIRED"
13	"FUEL OIL DAY TANK ALARM"
14	"IN CASE OF SPILL CALL DEC 1–800–478–9300"
INFORMATIONAL PLACARDS – BLACK LETTERING ON WHITE BACKGROUND.	
15	"CHECK INTERMEDIATE TANK LEVEL DAILY, FILL WHEN BELOW 3'–6"
16	"TO MANUALLY FILL DAY TANK IN CASE OF EMERGENCY: 1) TURN OFF POWER TO THE DAY TANK CONTROL PANEL 2) MANUALLY OPEN ACTUATOR VALVE AT INTERMEDIATE TANK USING A WRENCH 3) OPEN NORMALLY CLOSED VALVE BY HAND PUMP 4) OPERATE HAND PUMP WHILE MONITORING LEVEL GAUGE"
17	"TO CHANGE ENGINE OIL: 1) VERIFY ENGINE OIL HAS NOT BEEN CONTAMINATED WITH GLYCOL OR OTHER FLUIDS. 2) LOCK & TAG GENERATOR OUT OF SERVICE 3) OPEN NORMALLY CLOSED DRAIN VALVE AT GEN 4) TURN ON PUMP TIMER & PUMP OUT ENGINE OIL 5) CHANGE FILTER & PLACE OLD ONE IN HOPPER 6) CLOSE DRAIN VALVE & REFILL ENGINE 7) RUN ENGINE, SHUT OFF, & CHECK DIPSTICK 8) TOP OFF & PLACE ENGINE BACK IN SERVICE"
18	"INTERMEDIATE TANK MAX FILL LEVEL 5'–10" (90% TANK CAPACITY)"

ALL DECALS, SIGN BOARDS, FIRE EXTINGUISHERS, AND VALVE TAGS WERE FURNISHED AND INSTALLED AS PART OF THE PRIOR MODULE ASSEMBLY PROJECT EXCEPT FOR THOSE ITEMS SPECIFICALLY INDICATED IN RED CLOUDS WHICH ARE TO BE FURNISHED AND INSTALLED AS PART OF THE ON SITE SCOPE.

REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023



1	ADD DECAL 44	8/16/23	BCG
REV.	DESCRIPTION	DATE	BY
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: WARNING SIGN & FIRE EXTINGUISHER PLAN, SIGN & VALVE TAG SCHEDULES			
		DRAWN BY: JTD	SCALE: AS NOTED
		DESIGNED BY: BCG	DATE: 8/30/23
		FILE NAME: NELS PP M1	SHEET: M1.2
P.O. 111405, Anchorage, AK 99511 (907)349-0100		PROJECT NUMBER:	



Demand Control Table (PLC)				
Demand Control	Generator(s) On Line	On-line kW (Overload)	Level Increase	Level Decrease
Level 1	#3	65	55	---
Level 2	#1 or #2	100	90	45
Level 3	#3 & #1 or #2	165	145	80
Level 4	All	265	---	125
Note : Gen #1 & #2 are equal capacity. Manually select lead unit.				
Engine-Generator Alarm Settings (Easygen - EZGN)				
Function		Normal Range	Alarm	Shut Down
Overspeed		1795-1805	----	1900 RPM
Oil Pressure		30-50 PSI	14.5 PSI	10 PSI
Air Filter Vacuum		1-10" H2O	15" H2O	20" H2O
Coolant Temp.		180-200°F	210°F	215°F
Exhaust Temp.		500-850°F	900°F	-----
Under Frequency		59.5-60.5 Hz	----	58.2 Hz
Over Frequency		59.5-60.5 Hz	----	61.8 Hz
Under Voltage		470-490 V	----	432 V
Over Voltage		470-490 V	----	528 V
Reverse Power		0	----	10%
Generator Breaker Settings (Easygen - EZGN)				
Function				Setting
Gen #1 Breaker Trip Setpoint (EZGN Rated Current)				200 A
Gen #2 Breaker Trip Setpoint (EZGN Rated Current)				200 A
Gen #3 Breaker Trip Setpoint (EZGN Rated Current)				150 A
Gen Breaker Level 1 (100%) Time Over Current				3 sec.
Gen Breaker Level 2 (120%) Time Over Current				1 sec.
Gen Breaker Level 3 (250%) Time Over Current				0.4 sec.
Feeder Breaker Settings (Feeder Protection Relay - FPR)				
Function (Note: Element 1 is the only active element)				Setting
T.O.C. Trip Pickup (amps) Note: 5A = 100% of CT rating				5.0
T.O.C. Curve Selection				U4
T.O.C. Time Dial				5.00
E.M Reset delay (Y/N)				N
Constant Time Adder (seconds)				0.00
Minimum Response Time (seconds)				0.00
Maximum Phase T.O.C. Torque Control				1
Radiator VFD Settings				
Function				Setting
Min PID Feedback				20
Max PID Feedback				240
rSL (Wake UP Threshold)				1
PID Reference Temperature				175°F
Proportional Gain				0.93
Integral Gain				0.3
Derivative				0
Minimum Speed				10 Hz.
Low Speed Timeout				10 sec.
Loss of Phase				Ignore

POWER PLANT GENERATION SWITCHGEAR OPERATION

THIS POWER PLANT IS DESIGNED TO OPERATE IN AUTOMATIC MODE UNDER CONTROL OF THE PROGRAMMABLE LOGIC CONTROLLER (PLC). MONITORING AND CONTROL IS PRIMARILY DONE THROUGH THE OPERATOR INTERFACE UNIT (OIU). IN AN EMERGENCY SUCH AS A FAILURE OF THE PLC IT CAN ALSO BE OPERATED IN MANUAL MODE. EACH ENGINE IS CONTROLLED BY AN INDIVIDUAL EASYGEN (EZGN) GENSET CONTROLLER LOCATED IN EACH GENERATOR SECTION. FOLLOWING ARE INSTRUCTIONS FOR OPERATING THE SYSTEM. SEE SECTION 3.1 OF THE O&M MANUAL FOR DETAILED SEQUENCES.

AUTOMATIC OPERATION:

- 1) VERIFY THAT THE “SYSTEM MODE” SWITCH ON THE MASTER SECTION IS SET TO AUTO.
- 2) CHECK THE MASTER SECTION FOR ANY FAULTS AS INDICATED BY THE ALARM LAMPS. CORRECT THE CAUSE OF THE FAULT (EMERGENCY STOP, LOW COOLANT LEVEL, FEEDER BREAKER TRIPPED, ETC.) PRESS THE ALARM RESET BUTTON ON THE MASTER SECTION AND VERIFY THAT THE ALARMS CLEAR.
- 3) CHECK EACH GENERATOR SECTION FOR ANY FAULTS. FOR ENGINE–GENERATOR RELATED FAULTS CORRECT THE CAUSE OF THE FAULT (LOW OIL LEVEL, HIGH TEMPERATURE, CIRCUIT BREAKER TRIPPED, ETC.). TO CLEAR ANY ALARMS PRESS THE “ALARM RESET” BUTTON ON THE GENERATOR SECTION.
- 4) PLACE EACH AVAILABLE GENERATOR IN SERVICE BY PRESSING THE “AUTO” BUTTON. IF A GENERATOR IS OUT OF SERVICE FOR REPAIR, VERIFY THE STOP BUTTON IS ILLUMINATED.
- 5) THE PLC WILL AUTOMATICALLY START ALL GENERATORS IN AUTO AND PARALLEL THEM TO THE BUS, AS SOON AS THE BUS IS ENERGIZED THE STATION SERVICE POWER WILL TURN ON.
- 6) AFTER THE AVAILABLE GENERATORS ARE ON LINE, THE PLC WILL WAIT FOR A BRIEF INTERVAL (USUALLY 15 SECONDS) AND CLOSE THE FEEDER BREAKER TO ENERGIZE THE COMMUNITY. THE RED BREAKER CLOSED LAMP WILL ILLUMINATE.

DEMAND CONTROL OPERATION (AUTO MODE):

- 1) GENERATORS ARE CONSIDERED AVAILABLE FOR DEMAND CONTROL ONLY WHEN THEIR EZGN IS IN THE AUTO MODE AND THERE ARE NO ALARMS. THE DEMAND CONTROL SYSTEM WILL UTILIZE ALL AVAILABLE GENERATORS AS REQUIRED TO MEET THE LOAD ON THE SYSTEM.
- 2) ON INITIAL STARTUP THE DEMAND CONTROL IS ACTIVATED AFTER THE FEEDER BREAKER HAS BEEN CLOSED FOR ONE MINUTE. THIS ALLOWS THE PLC TIME TO DETERMINE THE POWER DEMAND ON THE SYSTEM. THE PLC MONITORS THE LOAD ON THE SYSTEM AND COMPARES IT TO THE CONNECTED GENERATING CAPACITY.
- 3) THE DEMAND CONTROL PROVIDES TWO TYPES OF CONTROL FOR INCREASING LOAD – INCREASE AND OVERLOAD. THE OVERLOAD SETPOINT IS TYPICALLY THE PRIME RATING OF THE GENSET AND THE INCREASE SETPOINT IS TYPICALLY 90% OF THE OVERLOAD SETPOINT. WHEN THE LOAD EXCEEDS THE INCREASE SETPOINT FOR A PRE–SET TIME DELAY (USUALLY 30 SECONDS) THE DEMAND CONTROL WILL SWITCH TO THE NEXT HIGHER LEVEL OF GENERATING CAPACITY. WHEN THE LOAD EXCEEDS THE OVERLOAD SETPOINT THE DEMAND CONTROL WILL IMMEDIATELY SWITCH TO THE NEXT HIGHER LEVEL OF GENERATING CAPACITY (NO TIME DELAY).
- 4) THE DEMAND CONTROL PROVIDES ONE TYPE OF CONTROL FOR DECREASING LOAD. THE DECREASE SETPOINT IS TYPICALLY 80% OF THE OVERLOAD SETPOINT. WHEN THE LOAD DROPS BELOW THE DECREASE SETPOINT FOR A PRE–SET TIME DELAY (USUALLY 2 MINUTES) THE DEMAND CONTROL WILL SWITCH TO THE NEXT LOWER LEVEL OF GENERATING CAPACITY.
- 5) NOTE THAT GENERATORS #1 & #2 ARE EQUAL CAPACITY AND THE OPERATOR MUST SELECT A LEAD GENERATOR USING THE SCADA SYSTEM.
- 6) SEE THE DEMAND CONTROL TABLE THIS SHEET FOR DEMAND LEVEL SETPOINTS AT THE TIME OF COMMISSIONING. ON THE SCADA SYSTEM GO TO THE DEMAND TAB TO VERIFY THE PRESENT SETPOINTS.

MANUAL OPERATION:

- 1) PLACE THE MASTER CONTROL “SYSTEM MODE” SWITCH IN THE MANUAL POSITION.
- 2) CHECK THE MASTER AND GENERATOR SECTIONS FOR ANY FAULTS AND CLEAR AS DESCRIBED UNDER AUTOMATIC OPERATION STEPS 2 AND 3.
- 3) TO PLACE A GENERATOR IN SERVICE, PRESS THE EZGN MAN BUTTON, THEN PRESS THE “I” (START) BUTTON. AFTER THE ENGINE STARTS AND STABILIZES, PRESS THE CONTACTOR CLOSE BUTTON ON THE EZGN. THE RED BREAKER CLOSED LAMP WILL ILLUMINATE.
- 4) REPEAT THIS PROCESS FOR AT LEAST ONE MORE GENERATOR.
- 5) WITH TWO GENERATORS ON LINE ROTATE THE FEEDER BREAKER CONTROL KNOB FOR THE MAIN FEEDER BREAKER TO THE CLOSE POSITION TO ENERGIZE THE COMMUNITY. MONITOR THE LOAD ON THE SYSTEM FOR ONE MINUTE THEN SELECT THE APPROPRIATE GENERATOR(S) TO MATCH THE LOAD.
- 6) TAKE ANY GENERATOR(S) NOT NEEDED OFF LINE BY PRESSING THE RED EZGN STOP BUTTON. THE ENGINE WILL COOL DOWN FOR THREE MINUTES THEN SHUT OFF. NOTE THAT PRESSING THE RED STOP BUTTON TWICE WILL IMMEDIATELY SHUT DOWN THE GENERATOR.
- 7) TO MANUALLY SWITCH TO A DIFFERENT GENERATOR AS THE LOAD CHANGES REPEAT STEPS 3 AND 6.

SERVICE DUE / OIL CHANGE PROCEDURE:

NOTE THAT UNDER AUTOMATIC OPERATION, WHENEVER THE SERVICE TIME HAS BEEN EXCEEDED THE GENERATOR WILL AUTOMATICALLY BE TAKEN OFF LINE AS LONG AS ANOTHER GENERATOR IS AVAILABLE IN AUTO. AN “ENGINE SERVICE” MESSAGE WILL DISPLAY ON THE EZGN AND THE RED “ENGINE ALARM” LAMP WILL ILLUMINATE.

- 1) IF THE SWITCHGEAR IS IN MANUAL MODE, PERFORM MANUAL OPERATION STEPS 3 AND 6 ABOVE THEN CONTINUE AT STEP 3 BELOW (LOCK OUT).
  - 2) IF THE SWITCHGEAR IS IN AUTOMATIC MODE, PRESS THE EZGN MAN BUTTON ON THE GENERATOR TO BE SERVICED. THE PLC WILL START ANOTHER GENERATOR. ONCE THE OTHER GENERATOR IS ON LINE, PRESS THE EZGN STOP BUTTON ON THE GENERATOR TO BE SERVICED. NOTE THAT IF THE STOP BUTTON IS PRESSED BEFORE ANOTHER UNIT IS ONLINE, AN OUTAGE WILL OCCUR.
  - 3) LOCK THE UNIT OUT USING THE KEY SWITCH AND TAG OUT OF SERVICE.
  - 4) SERVICE ENGINE (OIL CHANGE, FUEL FILTER, AIR FILTER, ETC.).
  - 5) REMOVE TAG AND TURN THE GENERATOR LOCKOUT SWITCH TO RUN.
  - 6) PRESS THE “SERVICE HOURS RESET” BUTTON AND HOLD FOR 10 SECONDS.
  - 7) PRESS THE “ALARM RESET” BUTTON.
  - 8) AFTER ALL ALARMS HAVE BEEN CLEARED PRESS THE EZGN “HOME” BUTTON.
  - 9) START THE ENGINE BY PRESSING THE MAN BUTTON AND THEN “I” (START) BUTTON.
    - a) AFTER THE ENGINE COMES UP TO SPEED VERIFY THAT THE ENGINE OIL PRESSURE IS IN THE NORMAL RANGE.
    - b) CHECK THE OIL FILTER FOR LEAKS.
  - 10) AFTER THE ENGINE RUNS FOR ONE MINUTE PRESS THE STOP BUTTON.
  - 11) CHECK THE OIL LEVEL USING THE DIPSTICK AND ADD OIL AS REQUIRED.
  - 12) PLACE THE GENERATOR BACK IN SERVICE BY PRESSING THE AUTO BUTTON ON THE EZGN.
- NOTE: AT EACH OIL CHANGE THE LEAD SELECTION TO THE NEXT UNIT TO DISTRIBUTE THE RUN TIME EQUALLY.

ENGINE–GENERATOR PROTECTION ALARMS:

SEE THE TABLES THIS SHEET FOR ALARM LEVEL SETPOINTS AND BREAKER TRIP SETTINGS AT THE TIME OF COMMISSIONING. SEE SECTION 3.1 OF THE O&M MANUAL FOR DETAILED DESCRIPTIONS OF WARNING ALARM AND PROTECTION SEQUENCES.

FUEL/OIL SYSTEM

AUTOMATIC DAY TANK FILL – THE DAY TANK IS FILLED FROM THE INTERMEDIATE TANK. IT HAS AUTOMATIC FILL CONTROLS WITH REDUNDANT HIGH AND LOW LEVEL ALARMS AND TIMERS. SEE FUEL SYSTEM CONTROL PANEL DRAWING SHEET E7.3 FOR DETAILED SEQUENCE OF OPERATION.

DAY TANK FILTER – THE DAY FILTER HAS WATER DETECTION PROBES. AN ALARM LAMP WILL ILLUMINATE WHEN WATER IS PRESENT IN THE FUEL. SEE WATER INDICATION PANEL DRAWING SHEET E7.4.

MANUAL USED ENGINE OIL DRAIN – USED OIL PUMP P–U01 IS USED TO PUMP USED ENGINE OIL FROM THE ENGINE OIL PANS TO THE USED OIL HOPPER. P–U01 RUNS THROUGH A MANUAL 0–5 MINUTE TIMER SWITCH.

AUTOMATIC USED ENGINE OIL BLENDING SYSTEM – THE USED ENGINE OIL BLENDING SYSTEM FILTERS USED OIL AND MIXES IT WITH DIESEL FUEL IN THE DAY TANK TO BE BURNED BY THE ENGINES. THE PUMPING RATES ARE SET TO BLEND APPROXIMATELY 0.5% USED OIL TO 99.5% DIESEL FUEL. NOTE THAT WHEN THERE IS NO USED OIL IN THE HOPPER THE DIESEL PUMP STILL RUNS TO USE THE BLENDER AS A FUEL “POLISHING” FILTER. SEE FUEL SYSTEM CONTROL PANEL DRAWING SHEET E7.3 FOR DETAILED SEQUENCE OF OPERATION.

MANUAL INTERMEDIATE TANK FILL – THE INTERMEDIATE TANK IS LOCATED ADJACENT TO THE POWER PLANT. IT NEEDS TO BE FILLED WHENEVER IT DROPS BELOW THE 50% FULL LEVEL. FILLING THE INTERMEDIATE TANK IS A MANUAL PROCEDURE USING THE EXISTING INTERMEDIATE TANK FILL CONTROL PANEL THAT HAS BEEN RELOCATED TO THE NEW POWER PLANT.

ENGINE COOLING SYSTEM

RADIATORS – RADIATOR FAN MOTORS WILL OPERATE UNDER VARIABLE FREQUENCY DRIVE (VFD) CONTROL. WHEN THE COOLANT RETURN TEMP REACHES THE PID REFERENCE SETPOINT THE MOTOR WILL START AT MINIMUM SPEED AND RAMP UP TO THE REQUIRED SPEED. USING PID CONTROL, THE VFD WILL MODULATE THE FAN SPEED AS REQUIRED TO MAINTAIN COOLANT RETURN TEMP AT THE PID REFERENCE SETPOINT. AS THE COOLANT RETURN TEMP RISES, THE VFD WILL INCREASE THE SPEED OF THE FAN MOTOR UP TO 100%. ONCE THE FAN REACHES THE MINIMUM SPEED, THE VFD WILL MAINTAIN THAT SPEED UNTIL THE LOW SPEED TIME OUT EXPIRES. WHEN THE LOW SPEED TIME OUT EXPIRES THE MOTOR WILL STOP. THE MOTOR WILL REMAIN OFF UNTIL THE COOLANT RETURN TEMP RISES TO THE PID REFERENCE SETPOINT. SEE THE RADIATOR VFD SETTINGS TABLE THIS SHEET FOR SETPOINTS AT THE TIME OF COMMISSIONING.

THERMOSTATIC VALVE TV–1 WILL MIX HOT COOLANT FROM THE ENGINE DISCHARGE PIPE WITH COLD COOLANT FROM THE RADIATOR RETURN PIPE TO MAINTAIN 175°F +/- TEMPERATURE COOLANT RETURN TO THE ENGINES.

ENGINE COOLANT RETURN HIGH TEMPERATURE ALARM. WHEN THE ENGINE COOLANT RETURN TEMPERATURE RISES ABOVE 190°F FOR A MINIMUM OF 2 MINUTES, THE “HIGH COOLANT RETURN TEMPERATURE” LAMP SHALL ILLUMINATE. LAMP SHALL REMAIN ON UNTIL MASTER RESET BUTTON IS PRESSED.

POWER PLANT HEATING AND VENTILATION SYSTEM

GENERATION ROOM – THE OPERATING AND OFF LINE GENERATORS REJECT MORE HEAT TO THE GENERATION ROOM THAN IS REQUIRED SO EXHAUST FANS WITH INTAKE AIR DUCTS ARE INSTALLED TO PROVIDE COOLING.

GENERATION ROOM VENTILATION – THERE ARE THREE AIR INTAKES IN THE GENERATION ROOM CEILING. ONE OF THE AIR INTAKES IS USED FOR COMBUSTION AIR AND THE DAMPER IS OPEN ANY TIME THE STATION SERVICE POWER IS ON. THE OTHER TWO AIR INTAKES ARE LABELED “EF–1” AND “EF–2”. THESE DAMPERS OPEN WHENEVER THE ASSOCIATED EXHAUST FAN RUNS. THE FANS ARE EACH EQUIPPED WITH A DISCHARGE MOTORIZED DAMPER THAT OPENS EACH TIME THE ASSOCIATED EXHAUST FAN RUNS.

EXHAUST FANS – THERE ARE TWO EXHAUST FANS ON THE WALL ABOVE THE FRONT OF THE GENERATORS, EF–1 AND EF–2. EACH FAN IS EQUIPPED WITH A MOTORIZED DAMPER THAT OPENS WHENEVER THE FAN RUNS ON A CALL FOR COOLING THROUGH A 24VAC DIGITAL MODULATING THERMOSTAT. THE THERMOSTAT WILL PROVIDE A 0–10V SIGNAL TO MODULATE THE FAN SPEED AS REQUIRED TO MAINTAIN GENERATING ROOM TEMP, TYPICALLY SET TO 80°F.

MOTOR OPERATED DAMPERS – ALL DAMPER MOTORS ARE NORMALLY CLOSED SPRING RETURN AND WILL CLOSE ON LOSS OF POWER (FIRE ALARM) IN LESS THAN 30 SECONDS.

CONTROL ROOM VENTILATION – COOLING AND VENTILATION FOR THE CONTROL ROOM IS PROVIDED BY AN OPERABLE WINDOW.

CONTROL ROOM HEATING – THE CONTROL ROOM IS HEATED BY A CABINET UNIT HEATER. PUMP P–CUH1 CIRCULATES ENGINE COOLANT FROM THE PIPING MAINS THROUGH THE CABINET UNIT HEATER IN THE CONTROL ROOM. THE TEMPERATURE CONTROLLER ON THE HEATER CYCLES THE PUMP AND THE HEATER FAN ON AND OFF AS REQUIRED TO MAINTAIN TEMPERATURE IN THE CONTROL ROOM, TYPICALLY SET TO 65°F.

HEAT RECOVERY SYSTEM

THE POWER PLANT HEAT EXCHANGER (HX–1), THE PRIMARY (HOT SIDE) ENGINE COOLANT CIRCULATING PUMP (P–HR1A), AND THE SECONDARY (COLD SIDE) HEAT RECOVERY FLUID MAIN CIRCULATING PUMP (P–HR1B) ARE LOCATED IN THE POWER PLANT. BOTH PUMPS OPERATE CONTINUOUSLY UNDER MANUAL CONTROL.

PEX ARCTIC PIPE TEMPERING SYSTEM – THE HEAT RECOVERY ARCTIC PIPE IS PEX (PLASTIC) PIPE WHICH HAS A LIMITED LIFE AT ELEVATED TEMPERATURES. THE HEAT RECOVERY SUPPLY TEMPERATURE IS TEMPERED BY A THREE–WAY THERMOSTATIC VALVE “TV–2” THAT IS INSTALLED BETWEEN THE HEAT EXCHANGER AND THE ARCTIC PIPE. THE VALVE MIXES COLD RETURN FLUID WITH HOT FLUID FROM THE HEAT EXCHANGER TO LIMIT THE SUPPLY TEMPERATURE TO APPROXIMATELY 185°F.

HEAT RECOVERY LOSS OF PRESSURE – WHEN THE SYSTEM PRESSURE IN THE HEAT RECOVERY PIPING DROPS BELOW 15 PSIG FOR 15 MINUTES, A RED LAMP “HEAT RECOVERY LOSS OF PRESSURE” LOCATED IN THE SWITCHGEAR MASTER SECTION WILL ILLUMINATE.

NO LOAD ON HEAT RECOVERY SYSTEM – WHEN THE HEAT RECOVERY RETURN TEMP. IS EQUAL TO OR GREATER THAN THE HEAT RECOVERY SUPPLY TEMP. FOR 60 MINUTES, AN AMBER LAMP “NO LOAD ON HEAT RECOVERY” LOCATED IN THE SWITCHGEAR MASTER SECTION WILL ILLUMINATE. WHEN THE HEAT RECOVERY SUPPLY TEMP. IS A MIN. OF 1°F GREATER THAN THE HEAT RECOVERY RETURN TEMP. THE LAMP WILL TURN OFF.

HEAT RECOVERY LOSS OF FLOW – WHEN THE FLOW RATE IN THE HEAT RECOVERY PIPING FALLS BELOW 10 GPM FOR 15 MINUTES, A RED LAMP “HEAT RECOVERY LOSS OF FLOW” LOCATED IN THE SWITCHGEAR MASTER SECTION WILL ILLUMINATE.

THE HEAT RECOVERY SYSTEM PROVIDES INTERRUPTIBLE HEAT TO ADJACENT BUILDINGS IN THE COMMUNITY USING UNIT HEATERS AND CABINET UNIT HEATERS AS SHOWN ON SHEET M8.1.

SYSTEM STARTUP

FUEL OIL PUMPS – PRIOR TO STARTING FUEL AND OIL PUMPS PRIME CAVITIES WITH LUBE OIL AND RUN MOMENTARILY TO VERIFY CORRECT ROTATION AND TO CONFIRM INLET AND OUTLET CONNECTIONS.

FUEL OIL PIPING – AFTER PRESSURE TESTING, FILL ALL FILTER BODIES, PRIME ALL PIPING, AND BLEED OFF AIR.

VERIFY OPERATION OF ALL FUEL SYSTEM CONTROLS IN ACCORDANCE WITH SEQUENCES OF OPERATION ON THE CONTROL PANEL DRAWINGS.

ENGINE COOLANT PIPING – AFTER PRESSURE TESTING, FLUSHING, AND BLEEDING, FILL SYSTEM WITH ETHYLENE GLYCOL SOLUTION. SEE HYDRONIC PIPING SPECIFICATION 23 21 13.

HEAT RECOVERY PIPING – AFTER PRESSURE TESTING, FLUSHING, AND BLEEDING, FILL SYSTEM WITH PROPYLENE GLYCOL SOLUTION. SEE HYDRONIC PIPING SPECIFICATION 23 21 13.

VERIFY OPERATION AND CALIBRATION OF ENGINE COOLANT SYSTEM AND HEAT RECOVERY SYSTEM THERMOSTATIC VALVES.



VERIFY PROPER OPERATION OF THERMOMETERS, PRESSURE GAUGES, AND ELECTRICAL INSTRUMENTATION DEVICES. SET SWITCHES ON DIFFERENTIAL PRESSURE GAUGES TO SETPOINTS INDICATED. CALIBRATE THERMOMETERS AND ALL ELECTRICAL INSTRUMENTATION DEVICES INCLUDING TEMPERATURE TRANSMITTERS, PRESSURE TRANSMITTERS, DIFFERENTIAL PRESSURE SWITCHES, FLOW METERS, ENERGY METERS, LEVEL GAUGES, ETC. SEE INSTRUMENTATION AND CONTROL DEVICES SPECIFICATION 23 09 00.

CLEAN ALL PIPING STRAINERS AFTER FIRST 48 HOURS OR MORE OF OPERATION. MONITOR SYSTEM OPERATION FOR ONE WEEK MINIMUM BEFORE LEAVING SITE. CHANGE GLYCOL FILTER ELEMENTS ON ENGINES AT TIME OF FIRST OIL CHANGE ON EACH ENGINE.



INITIAL TESTING WAS PERFORMED AS PART OF THE  
MODULE ASSEMBLY CONTRACT. FINAL SYSTEM STARTUP,  
TESTING, AND COMMISSIONING IS INCLUDED IN THE ON  
SITE SCOPE.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



 ALASKA ENERGY AUTHORITY		
PROJECT: <b>NELSON LAGOON POWER SYSTEM UPGRADE</b>		
TITLE: <b>SYSTEM START UP &amp; SEQUENCE OF OPERATIONS</b>		
 P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M1	SHEET:
	PROJECT NUMBER:	<b>M1.3</b>





TEMPORARY FUEL TRANSFER SYSTEM GENERAL NOTES:

- 1) THE EXISTING POWER PLANT INTERMEDIATE TANK IS FILLED UNDER MANUAL CONTROL FROM THE TANK FARM USING THE EXISTING 2" BURIED TRANSFER PIPELINE. IN ORDER TO MAINTAIN POWER IN THE COMMUNITY, AN ALTERNATIVE METHOD FOR FILLING THE INTERMEDIATE TANK MUST BE PROVIDED AT THE OLD POWER PLANT FROM THE TIME THE TRANSFER PIPELINE IS CUT UNTIL THE TIME THE NEW POWER PLANT IS COMMISSIONED. PLAN OUT WORK TO MINIMIZE THE TIME REQUIRED TO OPERATE ON THE TEMPORARY FUEL TRANSFER SYSTEM AND COORDINATE THE CHANGEOVER WITH THE UTILITY.
- 2) DURING THE ENTIRE TIME THE TEMPORARY TRANSFER SYSTEM IS IN SERVICE, MONITOR THE INTERMEDIATE TANK LEVEL DAILY AND FILL AS REQUIRED TO MAINTAIN A MINIMUM OF 1,000 GALLONS OF FUEL AT ALL TIMES. NOTE THAT THE POWER PLANT IS ESTIMATED TO USE APPROXIMATELY 100 GALLONS PER DAY. USING THE TRUCK FILL CONTAINMENT AREA AT THE EXISTING TANK FARM, LOAD A PORTABLE TANK OR TRUCK AND TRANSFER INTO EXISTING INTERMEDIATE TANK IN A SAFE AND ENVIRONMENTALLY SOUND MANNER. PROVIDE A RECORD OF THE QUANTITY OF EACH TRANSFER TO THE UTILITY. ALL FUEL REQUIRED FOR POWER GENERATION WILL BE PROVIDED BY THE UTILITY AT NO COST TO THE CONTRACTOR.

EXISTING PIPELINE DRAINING AND DECOMMISSIONING GENERAL NOTES:

- 1) THE FOLLOWING NOTES APPLY TO THE EXISTING 2" POWER PLANT INTERMEDIATE TANK FUEL TRANSFER PIPELINE. NOTE THAT THIS WORK MUST BE COORDINATED WITH THE PRECEDING TEMPORARY FUEL TRANSFER SYSTEM NOTES.
- 2) GROUND SURFACE ELEVATION ALONG THE PIPELINE ROUTE IS ESSENTIALLY LEVEL.
- 3) IDENTIFY ISOLATION VALVE(S) AT TANK FARM, CLOSE VALVE(S) AND LOCKOUT PRIOR TO COMMENCING DRAINING AND DECOMMISSIONING OF PIPELINE.
- 4) DRAIN ALL RESIDUAL FUEL FROM THE PIPELINE. USE 2" PIPE SIZE PIG FOR REMOVING ALL REMAINING FUEL FROM THE PIPELINE AS REQUIRED. CAPTURE FUEL IN CONTAINERS AND TURN OVER ALL CAPTURED FUEL TO THE UTILITY.
- 5) ONE EXISTING MULT-CONDUCTOR C-L-X ARMORED CABLE IS ROUTED ADJACENT TO THE EXISTING PIPELINE, SEE ELECTRICAL. THREE EACH BARGE FILL PIPELINES ARE ALSO ROUTED ADJACENT TO THE EXISTING 2" TRANSFER PIPELINE. LOCATE CABLE AND PIPES CAREFULLY HAND EXCAVATE OR USE AIR SPADE TO AVOID DAMAGE.
- 6) PERFORM ALL CUTTING IN ACCORDANCE WITH APPROPRIATE HOT WORK PROCEDURES PER NFPA 51B.
- 7) SEE SHEET M1.5 FOR ADDITIONAL PIPELINE DEMOLITION & DECOMMISSIONING DETAILS.

ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT


ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: OVERALL PROJECT AREA PLAN & POWER PLANT AREA MECHANICAL SITE PLAN		
DRAWN BY: JTD	SCALE: AS NOTED	SHEET: <b>M1.4</b>
DESIGNED BY: BCG	DATE: 5/30/23	
FILE NAME: NELS PP M1	PROJECT NUMBER:	








**1**  
**M1.5** POWER PLANT ENLARGED MECHANICAL SITE PLAN  
1/4"=1'-0"

**CODE NOTES:**


- 1) SEE CIVIL FOR SITE LAYOUT AND FOR DIMENSIONAL LOCATION OF POWER PLANT AND FUEL TANK ON SITE.
- 2) SEE ARCHITECTURAL FOR CODE ANALYSIS.
- 3) FOR 751-12,000 GALLON BULK STORAGE TANKS, THE INTERNATIONAL FIRE CODE REQUIRES 30' CLEARANCE TO THE NEAREST PROPERTY LINE WHICH IS OR CAN BE BUILT UPON AND 5' CLEARANCE TO THE NEAREST SIDE OF A PUBLIC WAY. THE LOCATION OF THE NEW 4,000 GALLON DOUBLE WALL FUEL TANK HAS A CLEARANCE OF APPROXIMATELY 39' TO THE NEAREST PROPERTY BOUNDARY AND 11' TO AIRPORT ROAD. SEE CIVIL.
- 4) THE INTERNATIONAL BUILDING CODE REQUIRES 10' MINIMUM CLEARANCE FROM THE NEW POWER PLANT TO THE NEAREST PROPERTY LINE WHICH IS OR CAN BE BUILT UPON, SEE SHEET A1. THE LOCATION OF THE NEW POWER PLANT HAS A CLEARANCE OF APPROXIMATELY 20' TO THE NEAREST PROPERTY BOUNDARY. SEE CIVIL.
- 5) THE INTERNATIONAL FIRE CODE REQUIRES FIRE APPARATUS ROADWAY TO PROVIDE ACCESS TO WITHIN 150' OF EVERY PORTION OF THE FACILITY. THE EXISTING GRAVEL ROAD AND GRAVEL PAD PROVIDES ACCESS TO WITHIN 25' OF ALL PORTIONS OF THE NEW POWER PLANT.



**2**  
**M1.5** BURIED FUEL PIPE & CONDUIT INSTALLATION  
NO SCALE

**NOTES:**


- 1) PRIOR TO REMOVING EXISTING VALVE, COORDINATE WITH ELECTRICAL FOR CONDUCTOR IDENTIFICATION.
- 2) INSTALL NEW FLANGE GASKETS AND STAINLESS STEEL BOLT SETS.



**4**  
**M1.5** TANK FARM ACTUATOR ABV-2 INSTALLATION  
NO SCALE

**FUEL PIPELINE MODIFICATION NOTES:**

- 1) PRIOR TO EXCAVATING AND CUTTING EXISTING FUEL PIPELINE DISCONNECT THE FUEL TRANSFER PIPELINE FROM INTERMEDIATE TANK AT EXISTING POWER PLANT AND DRAIN PIPELINE AS INDICATED ON SHEET M1.4.
- 2) FOUR EACH EXISTING FUEL PIPELINES (THREE EACH 3" AND ONE EACH 2") AND ONE MULTI-CONDUCTOR C-L-X ARMORED CABLE ARE ROUTED TOGETHER AS SHOWN. LOCATE EXISTING PIPES AND HAND EXCAVATE OR USE AIR SPADE AS REQUIRED TO EXPOSE PIPE BEING CAREFUL NOT TO DAMAGE ADJACENT CABLE OR PIPES.
- 3) DRAIN AND PURGE EXISTING 2" TRANSFER PIPELINE IN PREPARATION FOR CUT AND RECONNECTION.
- 4) PERFORM ALL CUTTING IN ACCORDANCE WITH APPROPRIATE HOT WORK PROCEDURES PER NFPA 51B. PRIOR TO WELDING INERT OR VAPOR FREE EXISTING PIPE AND COVER ADJACENT PIPE AND CONDUIT.
- 5) WELD NEW 2" 90° ELBOW AND 2" SCH 80 COATED PIPE EXTENSION TO NEW POWER PLANT INTERMEDIATE TANK AS INDICATED. COPE ELBOW AS REQUIRED FOR PIPELINE ALIGNMENT.
- 6) AFTER WELDING, PRESSURE TESTING, AND ANODE INSTALLATION, WRAP ALL BELOW GRADE JOINTS AND FITTINGS WITH HDPE HEAT-SHRINK TAPE TO FORM A CONTINUOUS WATER PROOF SEAL. EXTEND HEAT SHRINK 6" MINIMUM ONTO UNDAAMAGED COATING ON EXISTING PIPE, 6" ONTO NEW COATING ON NEW COATED PIPE, AND 6" MINIMUM ABOVE GRADE.
- 7) PLUG CUT END OF EXISTING PIPELINE THIS AREA WITH NON-SHRINK GROUT. CUT OTHER END AT OLD POWER PLANT 18" MIN BELOW GRADE AND PLUG WITH NON-SHRINK GROUT.





**3**  
**M1.5** FUEL PIPELINE & CONDUIT SLEEPER SUPPORT  
NO SCALE



ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT

ISSUED FOR  
CONSTRUCTION  
MAY 2023




 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: POWER PLANT ENLARGED MECHANICAL SITE PLAN & DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
FILE NAME: NELS PP M1	SHEET:	
	PROJECT NUMBER:	
		<b>M1.5</b>



GENERAL NOTES:


- 1) ALL NIPPLES AND RISER PIPES GALVANIZED STEEL PIPE OR GRC.  
2) COAT ALL PIPING CONNECTIONS TO TANK WITH ANTI-SEIZE INCLUDING MALE PIPE THREADS, FLANGE GASKETS, AND BOLTS.




SPECIFIC NOTES:

- 1 8" FLANGED SECONDARY EMERGENCY VENT.  
2 8" FLANGED PRIMARY EMERGENCY VENT.  
3 THREE POINT FLOAT TYPE LOW/FULL/OVERFILL LEVEL SWITCH LS, SEE DETAIL 6/E1.5.  
4 1" FLANGED ACTUATOR VALVE & DROP TUBE IN 4" BUNG. SEE DETAIL 1/M1.7.  
5 89" LONG LEVEL SENSOR PROBE FOR TANK LEVEL MONITORING IN 2" BUNG, SEE DETAIL 4/E1.5.  
6 2" PRESSURE/VACUUM VENT WITH WHISTLE ALARM ON 3" BUNG, SEE INSTALLATION DETAIL 6/M1.6.  
7 24" MANHOLE. TEMPORARILY REMOVE BOLTS AND COAT WITH ANTI-SEIZE.  
8 2" FILL LIMITER & FLANGED CHECK VALVE, SEE INSTALLATION DETAIL 5/M1.6.  
9 2" MECHANICAL FUEL LEVEL GAUGE ON 2" BUNG, SEE INSTALLATION DETAIL 3/M1.6.  
10 1" WATER DRAW ON 2" BUNG. SEE INSTALLATION DETAIL 4/M1.6.  
11 2" FPT GAUGE HATCH ON 2"x4" NIPPLE.  
12 2" FLANGED STRAINER ON FUEL TRANSFER PIPELINE  
13 2" SECONDARY TANK MONITOR PORT WITH VENT CAP.  
14 SHOP FABRICATED BOLT-ON LADDER.  
15 2" FUEL TRANSFER PIPELINE RISER ON FACE OF TANK.  
16 2" FLANGED BALL VALVE WITH 1" PRV BYPASS.  
17 SUPPORT 2" FILL RISER PIPE FROM TANK HEAD, SEE DETAIL 2/M1.7.  
18 2" FLANGED FLEX BEHIND.  
19 TRANSITION TO BURIED, SEE TANK END ELEVATION 2/M1.6.  
20 ANCHOR TANK TO CONCRETE FOOTING, 4 LOCATIONS TOTAL, SEE DETAIL 7/M1.6.  
21 SUPPORT OVERHEAD PIPING & CONDUIT WITH FIELD-MOUNTED STRUT RACK. SEE DETAIL 1/M1.7.

1 4,000 GALLON INTERMEDIATE TANK INSTALLATION  
M1.6 1/2"=1'-0"




2 4,000 GALLON INTERMEDIATE TANK END ELEVATION  
M1.6 3/4"=1'-0"




NOTES:

- 1) FEED FLOAT CABLE THROUGH NIPPLE PRIOR TO CONNECTING TO TANK.  
2) GREASE FLOAT PRIOR TO INSTALLING IN TANK TO PREVENT FREEZING TO BOTTOM.  
3) CALIBRATE GAUGE AFTER FILLING TANK AND VERIFY WITH MANUAL GAUGING ROD OR TAPE.

3 MECHANICAL LEVEL GAUGE INSTALLATION  
M1.6 NO SCALE




4 WATER DRAW INSTALLATION  
M1.6 NO SCALE




NOTE: PIPING SIZED TO PROVIDE SHUT OFF WHEN ACTUATION LEVEL IS AT 6'-3" ABOVE TANK BOTTOM (95% CAPACITY). FIELD VERIFY SHUT OFF HEIGHT & ADJUST LINKAGE AS REQUIRED.

5 FILL LIMITER INSTALLATION  
M1.6 NO SCALE



6 P/V WHISTLE VENT INSTALLATION  
M1.6 NO SCALE



7 TYPICAL TANK ANCHOR  
M1.6 NO SCALE




ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT

ISSUED FOR  
CONSTRUCTION  
MAY 2023





 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: INTEMEDIATE TANK INSTALLATION ELEVATIONS & DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
FILE NAME: NELS PP M1		SHEET: M1.6
PROJECT NUMBER:		






**1** ACTUATED BALL VALVE & DROP TUBE INSTALLATION  
M1.7 NO SCALE





**2** TANK HEAD PIPE SUPPORT  
M1.7 NO SCALE


ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT

ISSUED FOR  
CONSTRUCTION  
MAY 2023





		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: INTERMEDIATE TANK DETAILS		
	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M1	SHEET: M1.7
P.O. 111405, Anchorage, AK 99511 (907)349-0100 PROJECT NUMBER:		





#### TANK FABRICATION SPECIFIC DETAILS



- 1 > 4" HIGH BLACK LETTERING x1/2" STROKE: "DIESEL FUEL 4,000 GALLONS"
- 2 > SEAL WELD 1/4"x10"Ø STRIKER PLATE TO TANK BOTTOM DIRECTLY BELOW GAUGE HATCH TOP BUNG. PLATE TO BE ROLLED TO MATCH DIAMETER OF TANK.
- 3 > PIPE SUPPORT STAND OFF, 4 THIS END OF TANK.
- 4 > PROVIDE 1/4"x8" DIAMETER DOUBLER PLATE.
- 5 > PIPE SUPPORT STANDOFF, SEE TOP OF TANK SUPPORT BRACKET LAYOUT 3/M1.8.
- 6 > 1-1/8"Ø HOLE, 2 PLACES EACH SKID, SEE DETAIL 7/M1.8.
- 7 > 2-1/2" FLAT FACED FLANGE. FACE OF FLANGE 4" ABOVE TOP OF TANK.
- 8 > PROVIDE SADDLE/SKID ASSEMBLY WITH 12" MAX RISE FROM BOTTOM OF SKID TO BOTTOM OF TANK.



1 SECTION THROUGH TANK  
M1.8 1/2"=1'-0"




2 TANK END ELEVATION  
M1.8 NO SCALE

3 TOP OF TANK STANDOFF BRACKET LAYOUT  
M1.8 NO SCALE



4 TOP OF TANK STANDOFF BRACKET FABRICATION  
M1.8 NO SCALE

6 END OF SKID (TOP VIEW)  
M1.8 NO SCALE




5 TYP. PIPE SUPPORT STAND OFF  
M1.8 NO SCALE

7 TYPICAL TANK SKID HOLE  
M1.8 NO SCALE

8 LADDER FABRICATION  
M1.8 NO SCALE





ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: 4,000 GALLON DOUBLE WALL INTERMEDIATE TANK FABRICATION DETAILS		
	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
P.O. 111405, Anchorage, AK 99511 (907)349-0100	FILE NAME: NELS PP M1	SHEET: M1.8
	PROJECT NUMBER:	








ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
MODULE  
FABRICATION  
MARCH 2023




 <p>ALASKA ENERGY AUTHORITY</p>		
<p>PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE</p>		
<p>TITLE: MECHANICAL PENETRATIONS PLAN, ELEVATIONS &amp; DETAILS</p>		
 <p>Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100</p>	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 3/30/23
	FILE NAME: NELS PP M2-M7	SHEET:
	PROJECT NUMBER:	M2.1







1 TYPICAL ROOF OPENING DETAIL  
2"=1'-0"




2 TYPICAL WALL OPENING - ELEVATION  
1"=1'-0"




3 TYPICAL SECTION THROUGH WALL OPENING  
2"=1'-0"




4 EXHAUST PIPE SUPPORT AT FRAMED OPENING  
2"=1'-0"



5 TYPICAL WALL PENETRATION PIPE SLEEVE  
2"=1'-0"



6 TYPICAL HEAT RECOVERY ARCTIC PIPE WALL PENETRATION  
2"=1'-0"



7 TYPICAL ELECTRIC POWER FEEDER CONDUCTOR WALL PENETRATION  
2"=1'-0"



ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE FABRICATION CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
MODULE  
FABRICATION  
MARCH 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: MECHANICAL PENETRATION DETAILS		
	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 3/30/23
	FILE NAME: NELS PP M2-M7	SHEET: M2.2
P.O. 111405, Anchorage, AK 99511 (907)349-0100		





NOTES:

- 1) MAKE ALL JOINTS WITH CONTINUOUS GROOVE OR FILLET WELDS.
- 2) SLOT FLOOR PLATE 3 SIDES, WELD PEDESTAL TO TOP OF BEAM, THEN SEAL WELD TO FLOOR PLATE ALL AROUND INSIDE & OUT.

4"

6'-11" CENTER OF CORRUGATION ON MODULE CENTERLINE

SEE NOTE 2, TYP

3 SEE NOTE M2.3 1, TYP

11" O.C. TYP (17)


21" 23" 12" 10" 10" 23" 9"

INSIDE FACE OF TS BASIS OF STRUT LAYOUT

55-1 1/4" CORRUGATED PANEL, TYP (3)


NOTES:

- 1) COORDINATE CORRUGATIONS AND STRUT AS INDICATED TO ENSURE STRUT LANDS ON FLAT SECTIONS.
- 2) CENTER PLATE SPLICES ON PURLINS, TYP. SEE SHEET S2.



3 STRUT ATTACHMENT TO CEILING  
M2.3 NO SCALE

## 4 SUPPORT PEDESTAL FABRICATION



## 5 CEILING STRUT SUPPORT LAYOUT PLAN

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE FABRICATION CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE


TITLE: MECHANICAL SUPPORT PLANS & DETAILS

ISSUED FOR  
MODULE  
FABRICATION  
MARCH 2023




 P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 3/30/23
	FILE NAME: NELS PP M2-M7	SHEET:
	PROJECT NUMBER:	M2.3







**1** END WALL (GRID 1) HORIZONTAL WALL STRUT LAYOUT  
M2.4 1/2"=1'-0"




**2** BACK WALL (GRID A) HORIZONTAL WALL STRUT LAYOUT  
M2.4 1/2"=1'-0"




**3** END WALL (GRID 2) HORIZONTAL WALL STRUT LAYOUT  
M2.4 1/2"=1'-0"



**4** FRONT WALL (GRID B) HORIZONTAL WALL STRUT LAYOUT  
M2.4 1/2"=1'-0"




**5** GEN BAY RIGHT WALL HORIZONTAL WALL STRUT LAYOUT  
M2.4 1/2"=1'-0"



**6** CONTROL ROOM LEFT WALL HORIZONTAL WALL STRUT LAYOUT  
M2.4 1/2"=1'-0"

**HORIZONTAL WALL STRUT INSTALLATION NOTES:**

- 1) ALL LOCATIONS ARE CENTERLINE OF STRUT ABOVE FINISHED FLOOR (AFF).
- 2) ALL STRUT SHALL BE 12 GAUGE, 1-5/8" x 1-5/8", PLAIN (UN-FINISHED BLACK) WITH SOLID BACK, B-LINE B22-PLN OR EQUAL.
- 3) PRIOR TO PAINTING MODULE, WELD ALL HORIZONTAL STRUT SECTIONS TO WALLS AS SHOWN. SANDBLAST AND PAINT STRUT WITH MODULE INTERIOR WALLS. SEE SHEET A1 FOR PAINTING SPECIFICATIONS.





**7** HORIZONTAL WALL STRUT ATTACHMENT  
M2.4 NO SCALE


ISSUED FOR  
MODULE  
FABRICATION  
MARCH 2023




ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE FABRICATION CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: MECHANICAL SUPPORT HORIZONTAL WALL STRUT INSTALLATION		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD DESIGNED BY: BCG FILE NAME: NELS PP M2-M7 PROJECT NUMBER:	SCALE: AS NOTED DATE: 3/30/23 SHEET: <b>M2.4</b>







**1** END WALL (GRID 1) VERTICAL WALL STRUT LAYOUT  
1/2"=1'-0"




**3** END WALL (GRID 2) VERTICAL WALL STRUT LAYOUT  
1/2"=1'-0"




**5** GEN BAY RIGHT WALL VERTICAL WALL STRUT LAYOUT  
1/2"=1'-0"



**2** BACK WALL (GRID A) VERTICAL WALL STRUT LAYOUT  
1/2"=1'-0"



**4** FRONT WALL (GRID B) VERTICAL WALL STRUT LAYOUT  
1/2"=1'-0"



**6** CONTROL ROOM LEFT WALL VERTICAL WALL STRUT LAYOUT  
1/2"=1'-0"



**VERTICAL WALL STRUT INSTALLATION NOTES:**

- 1) ALL HORIZONTAL LOCATIONS ARE CENTERLINE OF STRUT FROM FACE OF TS COLUMNS. ALL VERTICAL LOCATIONS ARE END OF STRUT ABOVE FINISHED FLOOR.
- 2) ALL STRUT SHALL BE 12 GAUGE, PRE-GALVANIZED FINISH WITH SLOTTED BACK.  
"STD" DESIGNATES STANDARD 1-5/8" x 1-5/8" SINGLE STRUT, B-LINE B22-SH-GALV OR EQUAL.  
"DEEP" DESIGNATES 3-1/4" x 1-5/8" SINGLE STRUT, B-LINE B11-SH-GALV OR EQUAL.
- 3) FASTEN ALL VERTICAL STRUT SECTIONS TO HORIZONTAL STRUT WITH 1/2"x1" ALLEN HEAD CAP SCREWS & STRUT NUTS.
- 4) ONLY MAJOR WALL MOUNTED EQUIPMENT SUPPORT STRUT SHOWN THIS SHEET. SEE MECHANICAL AND ELECTRICAL DRAWINGS FOR OTHER EQUIPMENT, PIPING, AND WIREWAY STRUT SUPPORT DETAILS.


ISSUED FOR  
CONSTRUCTION  
MAY 2023




ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: MECHANICAL SUPPORT VERTICAL WALL STRUT INSTALLATION		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD DESIGNED BY: BCG FILE NAME: NELS PP M2-M7 PROJECT NUMBER:	SCALE: AS NOTED DATE: 5/30/23 SHEET: <b>M2.5</b>






1 EQUIPMENT LAYOUT PLAN  
3/8"=1'-0"



2 TYPICAL MODULE SECTION/GENERATOR INSTALLATION  
1/2"=1'-0"



3 VIBRATION ISOATOR INSTALLATION  
1"=1'-0"

#### EQUIPMENT LAYOUT GENERAL NOTES:

- SEE M2 SHEETS FOR MECHANICAL AND ELECTRICAL SUPPORTS AND PENETRATIONS
- SEE M3 SHEETS FOR GENERAL EQUIPMENT LAYOUT, BASE SUPPORT, FABRICATIONS, AND GENERATOR ASSEMBLY DETAILS.
- SEE M4 SHEETS FOR ENGINE COOLANT SYSTEM AND HEAT RECOVERY SYSTEM PLANS, ISOMETRICS, AND DETAILS.
- SEE M5 SHEETS FOR DIESEL FUEL AND USED OIL SYSTEM PLANS AND DETAILS.
- SEE SHEET M6 FOR EXHAUST AND CRANK CASE VENTILATION PLANS AND DETAILS.
- SEE M7 SHEETS FOR VENTILATION SYSTEM PLANS AND SHEET METAL FABRICATIONS.

#### ENGINE-GENERATOR SCHEDULE

GENSET	DESCRIPTION
GEN #1	ENGINE - 148 HP, 100 EKW PRIME, JOHN DEERE 4045AFM85, TIER 3 MARINE. 24 VDC STARTING & CONTROL. GENERATOR - MINIMUM 125 KW CONTINUOUS AT 105°C RISE, NEWAGE/STAMFORD UC1274E.
GEN #2	ENGINE - 148 HP, 100 EKW PRIME, JOHN DEERE 4045AFM85, TIER 3 MARINE. 24 VDC STARTING & CONTROL. GENERATOR - MINIMUM 125 KW CONTINUOUS AT 105°C RISE, NEWAGE/STAMFORD UC1274E.
GEN #3	ENGINE - 99 HP, 65 EKW PRIME, JOHN DEERE 4045TFM85, TIER 3 MARINE. 24 VDC STARTING & CONTROL. GENERATOR - MINIMUM 90 KW CONTINUOUS AT 105°C RISE, NEWAGE/STAMFORD UC1274C.

#### ENGINE-GENERATOR CODE COMPLIANCE NOTES

- PER IMC 915.1 THE ENGINE-GENERATORS AND ASSOCIATED MECHANICAL SYSTEMS SHALL BE IN INSTALLED COMPLIANCE WITH NFPA 37. SEE THE ABOVE REFERENCED DRAWINGS FOR ADDITIONAL DETAIL.
- PER IMC 915.1 THE ENGINE-GENERATORS SHALL BE FABRICATED AND ASSEMBLED IN ACCORDANCE WITH U.L. 2200. SEE ENGINE-GENERATOR SPECIFICATIONS FOR ADDITIONAL DETAIL.


ISSUED FOR  
CONSTRUCTION  
MAY 2023




THE MAJORITY OF WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY. FIELD INSTALLATION OF COMPONENTS EXTERIOR TO THE MODULE UNDER THE ON SITE CONTRACT ARE DELINEATED ON SHEETS THAT FOLLOW.

PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: EQUIPMENT LAYOUT PLAN, SECTION, & DETAILS		
	DRAWN BY: JTD DESIGNED BY: BCG FILE NAME: NELS PP M2-M7 PROJECT NUMBER:	SCALE: AS NOTED DATE: 5/30/23 SHEET: M3.1







**1**  
**M3.2** BACK WALL ELEVATION  
1/2"=1'-0"



**2**  
**M3.2** END WALL ELEVATION  
1/2"=1'-0"



**3**  
**M3.2** COOLANT MANIFOLD ENLARGED FABRICATION DETAIL  
1"=1'-0"




ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023




1	DELETE FLOW METER, DELETE BUTTERFLY VALVES FROM TV-1 PORTS A & C	8/16/23	BCG
REV.	DESCRIPTION	DATE	BY
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: WALL ELEVATIONS & PIPING DETAILS			
		DRAWN BY: JTD	SCALE: AS NOTED
DESIGNED BY: BCG		DATE: 5/30/23	SHEET:
FILE NAME: NELS_PP_M2-M7		PROJECT NUMBER:	<b>M3.2</b>
P.O. 111405, Anchorage, AK 99511 (907)349-0100			







1  
M3.3 TYPICAL PIPE SUPPORT AT BACK WALL  
1"=1'-0"



2  
M3.3 GEN#1 DISCHARGE CONNECTION (GEN#2 & GEN#3 MIRROR IMAGE)  
NO SCALE



3  
M3.3 GEN#1 SUCTION CONNECTION (GEN#2 & GEN#3 MIRROR IMAGE)  
NO SCALE





4  
M3.3 REMOVABLE BENCH VISE INSTALLATION  
NO SCALE


ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF  
THE PRIOR MODULE ASSEMBLY CONTRACT AND IS  
SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: MECHANICAL DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M2-M7	SHEET: <b>M3.3</b>
PROJECT NUMBER:		






LEFT SKID PLAN (TOP) VIEW




ELEVATION (SIDE) VIEW




SECTION A-A

NOTE:  
GROUP HOSES ON LEFT SKID AS SHOWN TO COORDINATE WITH COOLANT HOSES ABOVE.


1 FUEL/OIL HOSE & BATTERY CABLE INSTALLATION  
M3.4 NO SCALE




PLAN (TOP) VIEW



ELEVATION (SIDE) VIEW



SECTION A-A




SECTION B-B


NOTES:

- 1) FABRICATE FROM ASTM A-36 STEEL. BEND PLATES & CUT ENDS OF CHANNELS AT 90° & 45° AS SHOWN.
- 2) EXCEPT WHERE INDICATED AS BOLTED MAKE ALL CONNECTIONS WITH CONTINUOUS WELDS (FILLET OR FULL-PENETRATION GROOVE AS REQUIRED) IN ACCORDANCE WITH CURRENT AWS STANDARD CODE.
- 3) ROUND ALL CORNERS & GRIND WELDS SMOOTH AFTER FABRICATION. PAINT TO MATCH ENGINE-GENERATOR.
- 4) PLACE UNIT ON SKID SO THAT THE EXHAUST RISER CENTERLINE IS 39" FROM THE FRONT OF THE SKID.

2 TYPICAL GENERATOR SKID FABRICATION  
M3.4 NO SCALE




3 TYPICAL OIL LEVEL GAUGE/SWITCH INSTALLATION  
M3.4 NO SCALE



4 CONDENSATE TRAP FABRICATION  
M3.4 NO SCALE



ISSUED FOR  
CONSTRUCTION  
MAY 2023




ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF  
THE PRIOR MODULE ASSEMBLY CONTRACT AND IS  
SHOWN HERE FOR REFERENCE ONLY.

PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: GENERATOR FABRICATION DETAILS		
 P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
FILE NAME: NELS PP M2-M7	SHEET: M3.4	
	PROJECT NUMBER:	






2 HEAT EXCHANGER HX-1 SUPPORT FROM WALL  
M4.1 NO SCALE




5 TYP VALVED BRANCH CONNECTION TO STEEL MAIN  
M4.1 NO SCALE




7 HEAT RECOVERY ARCTIC PIPE WALL PENETRATIONS  
M4.1 NO SCALE

**HX CONNECTION NOTES:**

1) PROVIDE MINIMUM 9" LONG STRAIGHT COPPER TUBE SECTION BETWEEN ALL HEAT EXCHANGER NOZZLES AND FIRST SOLDER FITTING TO ALLOW FUTURE INSTALLATION OF NON-DIMPLED REPAIR COUPLING FOR HEAT EXCHANGER TEMPORARY REMOVAL AND/OR REPLACEMENT.



3 TYPICAL HX PIPING CONNECTION  
M4.1 NO SCALE



NOTE: FOR COPPER TUBE DIRECT CONNECTION INSTALL THREAD-O-LET ONE PIPE SIZE LARGER WITH THREADED BRONZE BUSHING FOR COPPER TO STEEL SEPARATION.

6 TYP DIRECT CONNECTION TO STEEL MAIN  
M4.1 NO SCALE

**ARCTIC PIPE GENERAL NOTES:**

1) SEE END WALL ELEVATION 2/M3.2 FOR PIPE WALL PENETRATION LAYOUT.

2) ONE PIPE SHOWN. PROVIDE TWO SIMILAR.


**ARCTIC PIPE SHOP/ON-SITE NOTES:**

1) SHOP INSTALLATION SHOWN. STUB PIPE 8" MIN BEYOND WALL & TEMPORARILY CONNECT SUPPLY TO RETURN FOR TESTING.

2) AFTER TESTING REMOVE TEMPORARY CONNECTION, BREAK FLANGE JOINT, AND STORE PIPE IN MODULE. INSTALL THREADED PIPE CAP FOR SHIPPING.

3) AS PART OF ON-SITE INSTALLATION REMOVE THREADED PIPE CAP, REINSTALL PIPE THROUGH WALL AND CONNECT TO ARCTIC PIPE, SEE SHEET M8.

4) SHOP INSULATE COPPER TUBE UP TO BUTTERFLY VALVE. SHOP CUT & FIT INSULATION & JACKET FOR STEEL PIPE TO WALL BUT SHIP LOOSE FOR FIELD INSTALLATION.




NOTES:

1) SMOOTH EDGES AFTER FABRICATION, WIRE BRUSH, SOLVENT CLEAN, AND PAINT WITH TWO COATS OF COLD GALVANIZING COMPOUND.

2) ONE STRAP SHOWN. INSTALL FOUR IDENTICAL STRAPS.

4 HEAT RECOVERY EXP TANK ET-2 SUPPORT  
M4.1 NO SCALE



8 TV-2 INSTALLATION  
M4.1 NO SCALE

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.

ISSUED FOR CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: COOLANT & HEAT RECOVERY PIPING PLAN & DETAILS		
	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS_PP_M2-M7	SHEET: M4.1
P.O. 111405, Anchorage, AK 99511 (907)349-0100		PROJECT NUMBER:



COOLING SYSTEM ISOMETRIC NOTES:

- 1) ALL PIPING SHOWN THIS ISOMETRIC 4" SCH 40 STEEL WITH WELDED JOINTS UNLESS SPECIFICALLY INDICATED OTHERWISE, SEE DETAIL 3/M3.2 FOR COOLING MANIFOLD DETAILS. ALL ENGINE BRANCH CONNECTIONS SCH 40 STEEL WITH WELDED AND THREADED JOINTS. ALL OTHER PIPE SHOWN THIS ISOMETRIC TYPE "L" HARD DRAWN COPPER WITH SOLDER JOINTS UNLESS SPECIFICALLY INDICATED OTHERWISE.
- 2) SEE COOLANT MANIFOLD FABRICATION DETAIL 3/M3.2 FOR CONNECTIONS TO STEEL MAINS. SEE DETAILS 2&3/M3.3 FOR BRANCH PIPING CONNECTIONS. SEE DETAILS 2/M4.3 FOR INSTRUMENTATION CONNECTIONS.
- 3) ALL COOLANT PRESSURE GAUGES 0-30 PSIG.
- 4) SEE ELECTRICAL INSTRUMENTATION SCHEDULE FOR TEMPERATURE TRANSMITTERS AND OTHER INSTRUMENTATION.
- 5) UPON COMPLETION OF FABRICATION VALVE OFF CABINET UNIT HEATER AND FLUSH PIPING TO REMOVE ALL DEBRIS, SEE SPECIFICATIONS.

- 6) SHOP INSULATE COOLANT PIPING MAINS FROM GENERATOR VALVES TO BUTTERFLY VALVES AT WALL PENETRATIONS. SHOP CUT & FIT INSULATION & JACKET FROM VALVES TO WALL BUT SHIP LOOSE FOR FIELD INSTALLATION. ALL OTHER PIPING NOT INSULATED.
- 7) 3/4" THREADED BALL VALVE, 3/4"MPTx5/8" BARB BRASS KING NIPPLE, & 1/2" HOSE FOR ENGINE VENT & PRE-HEAT.
- 8) SET P-HR1A TO OPERATE ON SPEED CP1.  
SET P-CUH1 TO OPERATE ON SPEED 3




HYDRONIC PIPING SHOP/ON-SITE NOTES:

- 1) SEE SPECIFICATION 23 21 13 FOR COOLING AND HEAT RECOVERY PIPING TESTING, FLUSHING, DRAINING, AND FILLING REQUIREMENTS.
- 2) SEE DETAILS 7/M4.1, 3/M4.2, AND 5/M4.3 FOR SHOP/FIELD REQUIREMENTS FOR PIPING THROUGH THE EXTERIOR WALLS.

1  
M4.2  
NO SCALE



HEAT RECOVERY ISOMETRIC NOTES:

- 1) ALL PIPING SHOWN THIS ISOMETRIC TYPE "L" COPPER WITH SOLDER JOINTS, 2"Ø EXCEPT WHERE SPECIFICALLY INDICATED OTHERWISE. ALL FLANGES ANSI 150# PATTERN TWO-PIECE WITH POWDER COATED STEEL FLANGE AND SOLDER COPPER TUBE ADAPTER. FOR ALL JOINTS EXCEPT BUTTERFLY VALVES INSTALL SPIRAL WOUND METALLIC GASKETS AND COAT GASKETS WITH ANTI-SEIZE COMPOUND PRIOR TO ASSEMBLING.
- 2) MAKE ALL CONNECTIONS FOR INSTRUMENTATION WITH T-DRILL TAP OR REDUCING TEE. SEE DETAIL 3/M4.3.
- 3) ALL HEAT RECOVERY PRESSURE GAUGES 0-100 PSIG.
- 4) SEE INSTRUMENTATION SCHEDULE SHEET M1.1 FOR TEMPERATURE AND PRESSURE TRANSMITTERS.
- 5) UPON COMPLETION OF FABRICATION FLUSH PIPING TO REMOVE ALL DEBRIS, SEE SPECIFICATIONS.
- 6) INSULATE ALL 2" HEAT RECOVERY PIPING MAINS. WRAP HEAT EXCHANGER WITH 1" RIGID FOIL-BACK FIBERGLASS INSULATION ALL AROUND AND TAPE ALL SEAMS.
- 7) SET P-HR1B TO OPERATE ON CP3
- 8) RISE UP BEHIND WIREWAY FOR THIS AIR VENT CONNECTION.



3  
M4.2  
3/4"=1'-0"

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.

1	DELETE FLOW METER & HR RETURN TEMP SENSOR, DELETE VALVES TV-1 PORTS A & C	8/16/23	BCG
REV.	DESCRIPTION	DATE	BY
<div> ALASKA ENERGY AUTHORITY</div>			
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: COOLANT & HEAT RECOVERY ISOMETRICS & DETAILS			
<div> Gray Stassel Engineering, Inc.</div>		DRAWN BY: JTD	SCALE: AS NOTED
DESIGNED BY: BCG		DATE: 5/30/23	SHEET: M4.2
FILE NAME: NELS PP M2-M7		PROJECT NUMBER:	
P.O. 111405, Anchorage, AK 99511 (907)349-0100			








GLYCOL TANK GENERAL NOTES:

- FABRICATE SINGLE WALL 60 GALLON NOMINAL CAPACITY GLYCOL TANK.
- FABRICATE FROM ASTM A-36 STEEL PLATE, 10 GAUGE MINIMUM EXCEPT FOR TOP 3/16" MINIMUM. ALL TANK SEAM JOINTS TO BE FULL CONTINUOUS WELDS.
- PROVIDE WITH ALL OPENINGS AND ATTACHMENTS INDICATED. SEAL WELD ALL TANK ATTACHMENTS.
- ALL FPT OPENINGS TO BE FORGED STEEL HALF COUPLINGS.
- PRESSURE TEST COMPLETED ASSEMBLY TO 5 PSIG MAXIMUM USING SOAPY WATER SOLUTION ON ALL WELD JOINTS.
- UPON COMPLETION OF FABRICATION, ROUND ALL CORNERS AND SHARP EDGES. SANDBLAST TANK EXTERIOR AND ALL ATTACHMENTS IN ACCORDANCE WITH SSPC-SP-6. PRIME AND COVER WITH TWO COATS OF EPOXY, PPG AMERLOC 2 VOC OR APPROVED EQUAL, COLOR ANSI 61 GRAY.
- UPON COMPLETION FLUSH INTERIOR OF TANK TO REMOVE ALL DIRT AND DEBRIS AND AIR DRY INTERIOR. INSTALL 2" SCREENED VENT ON 2" FPT FILL CONNECTION WITH 2" CLOSE NIPPLE FOR SHIPPING. SEAL ALL OTHER OPENINGS WITH PLASTIC OR STEEL PLUGS..


GLYCOL TANK SPECIFIC NOTES:

- 1-1/2" FPT (TANK GAUGE)
- 2" FPT (VENT) - INSTALL 2" THREADED VENT CAP
- 1" SCHEDULE 80 PIPE WITH THREADED TOP CONNECTION (WITHDRAWAL)
- 1" SOCKETWELD 90° ELBOW
- 6" LONG STRUT, END FLUSH WITH FRONT OF TANK
- 2x1/4" FLAT BAR CONTINUOUS THREE SIDES
- 3/8" HOLE AT 8" O.C. ALL AROUND
- L3x3x1/4"x6" LONG FOR FUTURE CONNECTION TO HAND PUMP BY OTHERS. PAINT TO MATCH TANK AND FASTEN TO STRUTS WITH 1/2" BOLTS & STRUT NUTS.



EXPANSION TANK GENERAL NOTES:

- FABRICATE SINGLE WALL 24 GALLON NOMINAL CAPACITY GLYCOL EXPANSION TANK.
- FABRICATE SHELL FROM MINIMUM 3/16" ASTM A-36 PLATE STEEL ROLLED AND WELDED OR 12"Ø SCHEDULE 10 LIGHTWALL ASTM A53 STEEL PIPE. FABRICATE HEADS FROM 1/4" THICK ASTM A-36 PLATE STEEL. FABRICATE SUMP FROM 8"Ø SCHEDULE 40 ASTM A53 STEEL PIPE. FABRICATE SUMP HEAD FROM 1/2" THICK ASTM A-36 PLATE STEEL. MAKE ALL JOINTS WITH CONTINUOUS FULL-PENETRATION WELDS.
- PROVIDE WITH ALL OPENINGS INDICATED USING MINIMUM 3000# FORGED STEEL PIPE HALF COUPLINGS IN ACCORDANCE WITH U.L 142 FIGURE 7.1 #2.
- PRESSURE TEST COMPLETED ASSEMBLY TO 15 PSIG MINIMUM.
- UPON COMPLETION OF FABRICATION, ROUND ALL CORNERS AND SHARP EDGES. SANDBLAST TANK EXTERIOR AND ALL ATTACHMENTS IN ACCORDANCE WITH SSPC-SP-6. PAINT WITH TWO COATS EPOXY, PPG AMERLOC 2 VOC OR APPROVED EQUAL, COLOR ANSI 61 GRAY.
- UPON COMPLETION FLUSH INTERIOR OF TANK TO REMOVE ALL DIRT AND DEBRIS, AIR DRY INTERIOR, AND SEAL ALL TANK OPENINGS WITH PLASTIC PLUGS.



2 24 GALLON GLYCOL EXPANSION TANK  
M4.4 1"=6"

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.


1 60 GALLON GLYCOL STORAGE TANK  
M4.4 1"=6"

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: GLYCOL STORAGE & EXPANSION TANKS FABRICATION		
	DRAWN BY: JTD DESIGNED BY: BCG FILE NAME: NELS PP M2-M7 PROJECT NUMBER:	SCALE: AS NOTED DATE: 5/30/23 SHEET: M4.4





PROJECT:		
NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE:		
DIESEL FUEL & USED OIL PIPING PLAN, DIAGRAM, & DETAILS		
	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M2-M7	SHEET:
	PROJECT NUMBER:	M5.1
P.O. 111405 Anchorage, AK 99511 (907)349-0100		






**1**  
**M5.2** DIESEL FUEL FRONT WALL ELEVATION  
1"=1'

#### GENERAL NOTES:


1. GENERAL LAYOUT SHOWN ONLY THIS ELEVATION. SEE PIPING DIAGRAM FOR COMPLETE INSTALLATION DETAILS.
2. CLAMP PIPE TO STRUT INSTALLED ON WALL, SEE SHEET M2.5.
3. ADD SHORT SECTIONS OF SHALLOW STRUT AT 4 LOCATIONS SHOWN TO OFFSET PIPING OUT TO ALLOW DAY TANK METER TO BE INSTALLED FACING OUT.

#### FUEL SHOP/ON-SITE NOTES:


1. DURING SHOP FABRICATION HOLE SAW 1-1/2" Ø OPENING FOR DAY TANK FILL PIPE, STUB PIPE 12" MIN BEYOND WALL, & TERMINATE WITH 1" MALE THREAD FOR TESTING.
2. UPON COMPLETION OF TESTING CLOSE VALVE, DRAIN PIPE, DISCONNECT FLANGE FROM VALVE THEN SLIDE PIPE OVER & SECURE FOR SHIPPING. SEAL WALL OPENING.
3. AS PART OF ON-SITE INSTALLATION REINSTALL FILL PIPE THEN CUT THREADS OFF EXTERIOR END & INSTALL SOCKET WELD ELBOW.
4. DURING SHOP FABRICATION INSTALL TEMPORARY VENT PIPE OUT WALL. UPON COMPLETION OF TESTING REMOVE TEMPORARY PIPE & SEAL WALL OPENING FOR SHIPPING.
5. AS PART OF ON-SITE INSTALLATION INSTALL 3" GALVANIZED THREADED VENT PIPE OUT WALL & UP TO VENT CAP. SEE DETAIL 3/M5.2.
6. UPON FINAL ON-SITE ASSEMBLY SEAL 1" FILL PIPE TO EXTERIOR WALL & 3" VENT PIPE TO WALL SLEEVE WITH POLYURETHANE CAULKING ALL AROUND.




**2**  
**M5.2** DIESEL FUEL & USED OIL END WALL ELEVATION  
1"=1'




**3**  
**M5.2** DAY TANK VENT INSTALLATION  
1/2"=1'-0"



**4**  
**M5.2** DAY TANK HAND PUMP HP-DT WALL SUPPORT  
NO SCALE



**5**  
**M5.2** ENGINE FUEL PIPING CONNECTION  
NO SCALE



- NOTES:**
- 1) HOSES PROVIDED WITH ENGINE, SIZE VARIES PER ENGINE & PRODUCT. CUT TO LENGTH & INSTALL JIC SWIVELS & 1/2" MPT ADAPTERS.
  - 2) ALL PIPING & NIPPLES SCH 80. ALL VALVES 1/2" SIZE, THREADED BODY.
  - 3) VERIFY PORTS TO USE FOR FLOW IN DIRECTION SHOWN. INSTALL RACOR FURNISHED 3/4" FPT ADAPTERS IN THESE PORTS & RACOR FURNISHED PLUGS IN UNUSED PORTS. CONNECT TO FILTER WITH JIC TO 3/4" MPT HOSE ENDS.
  - 4) WELD STRUT TO FLOOR FOR FILTER SUPPORT AS INDICATED, WIRE BRUSH AND RE-PAINT WELD AREA TO MATCH EXISTING


ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: <b>NELSON LAGOON POWER SYSTEM UPGRADE</b>		
TITLE: <b>DIESEL FUEL &amp; USED OIL PIPING ELEVATIONS &amp; DETAILS</b>		
DESIGNED BY: BCG	DRAWN BY: JTD	SCALE: AS NOTED
FILE NAME: NELS PP M2-M7	PROJECT NUMBER:	SHEET: <b>M5.2</b>
P.O. 111405, Anchorage, AK 99511 (907)349-0100		






1 TOP OF HOPPER - PLAN VIEW  
M5.3 NO SCALE




2 HOPPER BASE ELEVATION  
M5.3 NO SCALE



FILTER #1 INLET SIDE ELEVATION

FRONT ELEVATION

3 FILTER BANK ELEVATIONS  
M5.3 NO SCALE




4 SECTION THROUGH HOPPER  
M5.3 NO SCALE

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: USED OIL HOPPER & BLENDER INSTALLATION DETAILS		
 P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M2-M7	SHEET:
	PROJECT NUMBER:	M5.3











1 OIL FILTER BANK FRONT ELEVATION  
1/4" = 1"



2 SECTION THROUGH FILTER & BASE  
1/4" = 1"



3 OIL FILTER BANK BASE PLAN  
1/4" = 1"



#### FILTER BANK GENERAL NOTES:

1. FABRICATE TWO CHAMBER FILTER BANK AS INDICATED. SEE SHEET M5.5 FOR INTERNAL DETAILS.
2. FABRICATE FROM ASTM A-36 STEEL PLATE AND SHAPES AND ASTM A-53 PIPE. ALL JOINTS TO BE FULL CONTINUOUS SEAL WELDS EXCEPT WHERE SPECIFICALLY INDICATED OTHERWISE.
3. PROVIDE WITH ALL OPENINGS AND ATTACHMENTS INDICATED. INSTALL MINIMUM 3,000# FORGED STEEL HALF COUPLINGS FOR ALL FPT OPENINGS IN ACCORDANCE WITH UL 142 FIGURE 7.1 - #2.
4. PRESSURE TEST COMPLETED ASSEMBLY TO MINIMUM 50 PSIG USING SOAPY WATER SOLUTION ON ALL WELD JOINTS.
5. UPON COMPLETION OF FABRICATION, ROUND ALL CORNERS AND SHARP EDGES. SANDBLAST TANK EXTERIOR AND ALL ATTACHMENTS IN ACCORDANCE WITH SSPC-SP-6. PAINT WITH TWO COATS EPOXY, PPG AMERLOC 2 VOC OR APPROVED EQUAL, COLOR ANSI 61 GRAY.
6. AFTER PAINTING REMOVE LID, WIRE BRUSH MATING SURFACES OF LID AND RING TO REMOVE ALL PAINT AND POLISH SURFACES SMOOTH. APPLY A LIGHT COAT OF GREASE OR ANTI-SIEZE PASTE TO BOTH FACES PRIOR TO INSTALLING GASKET. INSTALL 13.5" O.D. FULL-FACED 1/4" BUNA-N RUBBER GASKET (ALASKA RUBBER OR EQUAL) ON FILTER LIDS.
7. FURNISH FASTENERS AS INDICATED AND COAT WITH ANTI-SIEZE.
8. PRESSURE TEST EACH FILTER HOUSING ASSEMBLY TO 50 PSIG MINIMUM.
9. UPON COMPLETION FLUSH INTERIOR OF TANK TO REMOVE ALL DIRT AND DEBRIS, AIR DRY INTERIOR, AND SEAL ALL TANK OPENINGS WITH PLASTIC PLUGS.


ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: USED OIL BLENDER FILTER BANK LAYOUT & CONFIGURATION		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
FILE NAME: NELS PP M2-M7	SHEET:	M5.5
PROJECT NUMBER:		







**1** TYPICAL FILTER HOUSING – PLAN VIEW  
M5.6 1/2" = 1"




**2** TYPICAL SECTION THROUGH FILTER HOUSING  
M5.6 1/4" = 1"





**3** ELEMENT RETAINER CAP  
M5.6 1/2" = 1"



**4** ELEMENT BASE STAND  
M5.6 1/2" = 1"



**5** SECTION THROUGH ELEMENT GUIDE  
M5.6 1/2" = 1"



**6** LID & MATING RING – PLAN VIEW  
M5.6 1/4" = 1"







ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: USED OIL BLENDER TYPICAL FILTER HOUSING DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M2-M7	SHEET: M5.6
PROJECT NUMBER:		





# 1 HOPPER PLAN & SECTION

## FABRICATION NOTES:

- FABRICATE SINGLE WALL 25 GALLON USABLE CAPACITY HOPPER.
- FABRICATE FROM MINIMUM 10 GAUGE ASTM A-36 STEEL PLATE. ALL TANK SEAM JOINTS TO BE FULL CONTINUOUS WELDS. SEAL WELD ALL TANK ATTACHMENTS.
- PROVIDE WITH ALL OPENINGS AND ATTACHMENTS INDICATED. INSTALL ALL FPT OPENINGS IN ACCORDANCE WITH UL 142 FIGURE 7.1 - #1, #2, #4, OR #6. ALL STRUT TO BE 1-5/8"x1-5/8"x12 GA SOLID BACK PLAIN (BLACK), B-LINE B22 PLN OR EQUAL. FURNISH ALL FASTENERS AS INDICATED.
- UPON COMPLETION OF FABRICATION, ROUND ALL CORNERS AND SHARP EDGES. SANDBLAST TANK EXTERIOR AND ALL ATTACHMENTS IN ACCORDANCE WITH SSPC-SP-6. PAINT WITH TWO COATS EPOXY, PPG AMERLOC 2 VOC OR APPROVED EQUAL, COLOR ANSI 61 GRAY.
- PRIOR TO SHIPPING, SEAL ALL FPT OPENINGS WITH PLASTIC OR STEEL PLUGS.

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: USED OIL BLENDER 25 GALLON HOPPER FABRICATION		
	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
P.O. 111405, Anchorage, AK 99511 (907)349-0100	FILE NAME: NELS PP M2-M7	SHEET: M5.7
	PROJECT NUMBER:	









- 5) IN FIELD REINSTALL PIPING WITH NEW FLANGE GASKETS. RE-INSTALL PIPING INSULATION. INSULATE WALL PENETRATION, INSTALL COVER PLATES, AND SEAL TO WALL.



 P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M2-M7	SHEET:
	PROJECT NUMBER:	M6

A circular professional engineer seal for the State of Alaska. The outer ring contains the text "STATE OF ALASKA" at the top and "REGISTERED PROFESSIONAL ENGINEER" at the bottom, separated by small stars. Inside the ring, a five-pointed star is positioned above the text "49TH". Below this, the name "BRIAN C. GRAY" and the license number "ME 8210" are printed. A stylized signature, "B. C. Gray", is written across the center of the seal.






#### VENTILATION SYSTEM SHOP/ON-SITE NOTES:


- 1) FURNISH ENTIRE VENTILATION SYSTEM AS PART OF MODULE SHOP FABRICATION.
- 2) DURING SHOP FABRICATION INSTALL EXHAUST FAN ASSEMBLIES. TEST FIT EXTERIOR HOODS AND INTAKE DUCTS BUT DO NOT INSTALL.
- 3) DURING SHOP FABRICATION TEMPORARILY CONNECT INTAKE DAMPERS TO ELECTRICAL ROUGH IN AND TEST TO VERIFY FUNCTION. SEE SHEET E4.2.
- 4) AS PART OF ON-SITE WORK INSTALL EXHAUST HOODS AND INTAKE DUCTING AS INDICATED.

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.


ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: VENTILATION PLAN & DETAILS		
DRAWN BY: JTD	SCALE: AS NOTED	
DESIGNED BY: BCG	DATE: 5/30/23	
FILE NAME: NELS PP M2-M7	SHEET:	M7.1
PROJECT NUMBER:		








- NOTES:
- 1) FABRICATE 3 IDENTICAL DUCTS FROM MIN 18 GAUGE GALV SHEET METAL WITH SEALED MECHANICAL JOINTS OR AT CONTRACTORS OPTION 0.090" THICK TYPE 5052 ALUMINUM WITH ALL WELDED SEAMS.
  - 2) DUCTS ARE DESIGNED TO FIELD INSTALL BETWEEN TRUSSES. DO NOT ADD JOINTS.



- NOTES:
- 1) FABRICATE 3 IDENTICAL AIR INTAKE MESH FRAMES.
  - 2) FABRICATE FRAME FROM 2"x2"x3/16" ALUMINUM ANGLE WITH MITERED AND WELDED CORNERS AND 1/4" HOLES AT 6" O.C. ALL AROUND, 1/2" FROM OUTSIDE EDGE OF FRAME.
  - 3) INSTALL 1"x1" STAINLESS STEEL WIRE MESH IN HEMMED STAINLESS STEEL FRAME AND FASTEN TO ANGLE FRAME WITH STAINLESS STEEL SCREWS ALL AROUND.




- NOTES:
- 1) FABRICATE 4 IDENTICAL VENTILATION INTAKE ASSEMBLIES.
  - 2) SHOP MOUNT DUCTMATE FLANGE.
  - 3) PROVIDE MIN 3" DAMPER ROD EXTENSION ON SIDE INDICATED AND FABRICATE SHEET METAL STAND-OFF BRACKET TO FULLY SUPPORT THE ACTUATOR FROM THE DAMPER FRAME. SEE PLAN VIEW FOR DAMPER ACTUATOR ORIENTATION.
  - 4) INSTALL FRAME FOR REMOVABLE 20"x12"x2" MERV 8 FILTERS. FABRICATE FROM "C" CHANNEL THREE SIDES WITH LATCHING HINGED COVER ON BOTTOM TO ALLOW FILTERS TO SLIDE DOWN FOR REMOVAL. ON 20" SIDE EXTEND FILTER FRAME BEYOND DUCT EACH WAY AS REQUIRED.


## 1 INTAKE DUCT FABRICATION

## 2 INTAKE MESH FRAME

## 3 INTAKE AIR DAMPER FABRICATION



- NOTES:
- 1) FABRICATE 2 IDENTICAL ASSEMBLIES COMPLETE WITH FAN AND DAMPER MOUNTED AND SEALED TO DUCT.
  - 2) PROVIDE 2" WIDE MOUNTING FLANGE ON SIDES WITH 1/4" HOLES AT 5" O.C. PROVIDE 1" MOUNTING FLANGE ON TOP AND BOTTOM WITHOUT HOLES.
  - 3) PROVIDE MIN 3" DAMPER ROD EXTENSION ON THE LEFT SIDE AND FABRICATE SHEET METAL STAND-OFF BRACKET TO FULLY SUPPORT THE ACTUATOR FROM THE DAMPER FRAME.



- NOTES:
- 1) FABRICATE HOODS FROM 0.090" THICK TYPE 5052 ALUMINUM WITH ALL WELDED SEAMS.
  - 2) PROVIDE 2" WIDE MOUNTING FLANGE ON TOP & SIDES WITH 1/4" HOLES AT 9" O.C.
  - 3) INSTALL 1"x1" STAINLESS STEEL WIRE MESH IN HEMMED STAINLESS STEEL FRAME AND FASTEN TO ANGLE FRAME WITH STAINLESS STEEL SCREWS ALL AROUND, TYP(2).

## 4 EXHAUST FAN ASSEMBLY FABRICATION

## 5 EXHAUST HOOD FABRICATION

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT:  
NELSON LAGOON POWER SYSTEM UPGRADE


TITLE:  
SHEET METAL FABRICATION DETAILS

 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M2-M7	SHEET: M7.2





**1**  
**M8.1** HEAT RECOVERY SYSTEM OVERALL PIPING SCHEMATIC  
NO SCALE



**2**  
**M8.1** HEAT RECOVERY SYSTEM OVERALL PLAN  
1"=40'

END USER BUILDING HEAT RECOVERY EQUIPMENT SCHEDULE:			
SYMBOL	SERVICE/FUNCTION	DESCRIPTION	MANUFACTURER/MODEL
CUH	STORAGE COMPOUND APARTMENT SPACE HEAT	HOT WATER CABINET UNIT HEATER, 17 MBH AT 1 GPM 180F EWT & 60F EAT	TOYOTOMI HC-190
UH-1	TOURISM BUILDING SPACE HEAT	HORIZONTAL DISCHARGE HOT WATER UNIT HEATER, 21.7 MBH AT 2.3 GPM, 200F EWT AND 60F EAT, 1/25HP, 120V, 1ø	MODINE HC-33
UH-2	STORAGE COMPOUND & ICEHOUSE OCCUPIED AREAS SPACE HEAT	LOW PROFILE HOT WATER UNIT HEATER, 30.9 MBH AT 2 GPM, 180F EWT AND 60F EAT, 405 CFM, 1/20HP, 120V, 1ø	MODINE "HOT DAWG" HHD30
UH-3	ICEHOUSE MAIN FLOOR AREA HEAT	HORIZONTAL DISCHARGE HOT WATER UNIT HEATER, 45.6 MBH AT 4.7 GPM, 200F EWT AND 60F EAT, 1/12HP, 120V, 1ø	MODINE HC-63
P-CUH	CABINET UNIT HEATER CIRC PUMP	1 GPM AT 18' TDH, 1/25HP, 115V, 1ø. WITH 1/2" SOLDER SHUT-OFF FLANGES	GRUNDFOS UPS 15-58FC SPEED 3
P-UH1	TOURISM BUILDING UNIT HEATER CIRC PUMP	4 GPM AT 6' TDH, 1/25HP, 115V, 1ø. WITH 1/2" SOLDER SHUT-OFF FLANGES	GRUNDFOS UPS 15-58FC SPEED 1
P-UH2	STORAGE COMPOUND & ICEHOUSE OCCUPIED AREAS HEATER CIRC PUMP	2 GPM AT 9' TDH, 1/25HP, 115V, 1ø. WITH 1/2" SOLDER SHUT-OFF FLANGES	GRUNDFOS UPS 15-58FC SPEED 1
P-UH3	ICEHOUSE PROCESSING AREA UNIT HEATER CIRC PUMP	5 GPM AT 10' TDH, 1/25HP, 115V, 1ø. WITH 3/4" SOLDER SHUT-OFF FLANGES	GRUNDFOS UPS 15-58FC SPEED 2
NOTE: UNIT HEATER AND CABINET UNIT HEATER RATINGS ON SCHEDULE ARE BASED ON WATER AT STANDARD TEMPERATURE. RATINGS SHOWN ON SCHEMATIC ARE REDUCED FOR 50% GLYCOL AT REDUCED TEMPERATURE.			


- ARCTIC PIPE GENERAL NOTES:**
- THE DRAWINGS SHOW APPROXIMATE LOCATION OF SOME EXISTING UNDERGROUND ELECTRIC POWER. PRIOR TO BEGINNING EXCAVATION, LOCATE ALL UNDERGROUND UTILITIES INCLUDING BUT NOT LIMITED TO ELECTRIC POWER, TELECOMMUNICATIONS, WATER, SEWER, AND FUEL.
  - TAKE CARE TO PROTECT EXISTING BUILDING FOUNDATIONS, SLABS, SIDEWALKS, AND OTHER EXISTING FEATURES WHEN EXCAVATING FOR ARCTIC PIPE. BACKFILL WITH EXCAVATION SPOILS OR SANDY GRAVEL, COMPACT, AND BLEND INTO EXISTING GRADE. RESTORE ALL EXCAVATION AREAS TO ORIGINAL CONDITION UPON COMPLETION.
  - ANY UTILITIES DAMAGED DURING EXCAVATION SHALL BE REPAIRED PROMPTLY TO THE SATISFACTION OF THE AUTHORITY AND THE UTILITY AT NO COST TO THE AUTHORITY.
  - WHERE MULTIPLE UTILITIES ARE BURIED IN A COMMON TRENCH, PLAN OUT WORK AND COORDINATE TRADES TO INSTALL ALL BURIED UTILITIES TOGETHER.
  - ALL BURIED ARCTIC PIPE IS 63mm PEX. ALL ARCTIC PIPE RISERS AT BELOW TO ABOVE GRADE TRANSITIONS ARE WELDED 2" SCH 40 STEEL WITH POLYURETHANE INSULATION AND WATERPROOF HDPE CASING. ALL END USER BUILDING INTERIOR PIPING IS COPPER TUBING.
  - LENGTHS OF BURIED RUNS INDICATED THIS PLAN ARE APPROXIMATE, FIELD VERIFY. FURNISH 63mm PEX ARCTIC PIPE IN ADEQUATE LENGTHS TO ALLOW CONTINUOUS RUNS BETWEEN BUILDING RISERS. DO NOT INSTALL SPLICE JOINTS BETWEEN RISERS.

- HEAT RECOVERY SYSTEM FILLING, FLUSHING, AND PURGING PROCEDURES:**
- AFTER PRESSURE TESTING ALL PIPING, BLEED AIR RESERVOIR ON THE EXPANSION TANK IN THE MODULE AS REQUIRED TO MAINTAIN 10 PSIG RESIDUAL WITH THE SYSTEM EMPTY.
  - AT END USER BUILDINGS, CLOSE ISOLATION VALVES AT EACH UNIT HEATER AND CABINET UNIT HEATER TO ENSURE NO FLOW THROUGH THE HEATER COILS PRIOR TO FILLING SYSTEM.
  - FILL THE ENTIRE HEAT RECOVERY PIPING SYSTEM WITH PROPYLENE GLYCOL SOLUTION TO 20 PSIG MINIMUM WITH SYSTEM COLD. VENT AIR FROM HIGH POINT VENT IN POWER PLANT AND FROM MANUAL VENT/PURGE VALVES IN EACH END USER BUILDING.
  - CYCLE MAIN HEAT RECOVERY LOOP CIRC. PUMP P-HR1B ON AND OFF AND VENT HIGH POINTS UNTIL ALL AIR HAS BEEN PURGED FROM THE MAIN PIPING LOOP. USE HOSES AND BUCKETS TO PURGE AND CAPTURE SALVAGED GLYCOL.
  - ADD PROPYLENE GLYCOL SOLUTION AS REQUIRED TO MAINTAIN 20 PSIG MINIMUM WITH SYSTEM COLD. WITH DIESEL GENERATOR(S) RUNNING, START THE HEAT RECOVERY SYSTEM PRIMARY AND SECONDARY CIRCULATION PUMPS P-HR1A AND P-HR1B. BRING THE ENTIRE HEAT RECOVERY SYSTEM UP TO NORMAL TEMPERATURE (170°F MINIMUM) AND ADD PROPYLENE GLYCOL SOLUTION AS REQUIRED TO BRING SYSTEM PRESSURE TO 30 PSIG MINIMUM AT EXPANSION TANK.
  - CIRCULATE HOT GLYCOL IN MAIN LOOP FOR 24 HOURS MINIMUM THEN SHUT MAIN CIRCULATION LOOP PUMP P-HR1B OFF. ISOLATE AND CLEAN PIPING STRAINERS WHICH ARE LOCATED IN THE POWER PLANT, STORAGE COMPOUND, AND ICEHOUSE. AFTER CLEANING STRAINERS OPEN STRAINER ISOLATION VALVES.
  - USE HOSE AND BUCKET TO PURGE AIR AND DEBRIS FROM HIGH POINT BLEEDS IN END USER BUILDINGS THEN GO TO THE MODULE AND ADD PROPYLENE GLYCOL SOLUTION AS REQUIRED TO BRING SYSTEM PRESSURE TO 30 PSIG MINIMUM AT EXPANSION TANK. START THE MAIN PUMPS P-HR1A AND P-HR1B.
  - GO TO EACH UNIT HEATER (UH-1, UH-2, UH-3) IN THE SYSTEM, SET TO THE PUMP TO THE SPECIFIED SPEED, OPEN THE ISOLATION VALVES, AND TURN UP THE THERMOSTAT TO START THE ASSOCIATED CIRC PUMP.
  - AT THE MEZZANINE APARTMENT CABINET UNIT HEATER (CUH), OPEN THE ISOLATION VALVES AND USING THERMOSTAT CONTROL, CYCLE CABINET UNIT HEATER PUMP ON AND OFF AND VENT BLEED FITTING ON TOP OF CABINET UNIT HEATER.
  - PURGE ANY REMAINING AIR FROM HIGH POINT BLEEDS IN END USER BUILDINGS.
  - WHEN THE ENTIRE SYSTEM COMES UP TO NORMAL TEMPERATURE (170°F MINIMUM) ADD PROPYLENE GLYCOL SOLUTION AS REQUIRED TO BRING SYSTEM PRESSURE TO 30 PSIG MINIMUM AT EXPANSION TANK.
  - VERIFY PROPER FUNCTION OF ALL INSTRUMENTATION AND CALIBRATE ALL DEVICES. VERIFY POWER PLANT HEAT RECOVERY READINGS ON SWITCHGEAR SCADA SYSTEM.
  - GO THROUGH THE ENTIRE SYSTEM INCLUDING ALL END USER BUILDINGS AND CHECK FOR LEAKS. PERFORM FUNCTIONAL TEST OF EACH UNIT HEATER AND CABINET UNIT HEATER THERMOSTATIC CONTROLS VERIFYING THAT FAN AND PUMP CYCLE ON AND OFF TOGETHER.
  - ADD PROPYLENE GLYCOL SOLUTION AS REQUIRED TO BRING SYSTEM PRESSURE TO 30 PSIG MINIMUM AT EXPANSION TANK. FILTER SALVAGED GLYCOL WITH 30 MICRON FILTER AND PLACE BACK IN DRUMS. STORE ALL EXCESS PROPYLENE GLYCOL SOLUTION IN THE ORIGINAL DRUMS SEALED FOR LONG-TERM STORAGE. VERIFY THAT DRUMS ARE CLEARLY LABELED "PROPYLENE GLYCOL" WITH YELLOW LETTERING.

ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.

ISSUED FOR  
CONSTRUCTION  
MAY 2023






ALASKA ENERGY AUTHORITY

PROJECT:

NELSON LAGOON POWER SYSTEM UPGRADE

TITLE:

HEAT RECOVERY SYSTEM OVERALL PLAN,  
SCHEMATIC, & EQUIPMENT SCHEDULE




Gray Stassel Engineering, Inc.

DRAWN BY: JTD  
DESIGNED BY: BCG  
FILE NAME: NELS PP M8  
PROJECT NUMBER:


SCALE: AS NOTED  
DATE: 5/30/23  
SHEET:

**M8.1**







**1**  
**M8.2** ARCTIC PIPE RISER AT NEW MODULAR POWER PLANT  
3/4"=1'-0"



**4**  
**M8.2** TYPICAL ARCTIC PIPE RISER AT END USER BUILDING  
3/4"=1'-0"



**2**  
**M8.2** ARCTIC PIPE WALL ENTRANCE AT MODULE  
NO SCALE



**3**  
**M8.2** TYPICAL BURIED ARCTIC PIPE INSTALLATION WITH ELECTRICAL POWER  
NO SCALE

ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.


ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM ARCTIC PIPE DETAILS		
DRAWN BY: JTD	SCALE: AS NOTED	<b>M8.2</b>
DESIGNED BY: BCG	DATE: 5/30/23	
FILE NAME: NELS PP M8	SHEET:	
PROJECT NUMBER:		









1 TOURISM BUILDING HEAT RECOVERY PLAN  
1/2"=1'-0"



2 TOURISM BUILDING ARCTIC PIPE ENTRANCE  
NO SCALE



3 TOURISM BUILDING ARCTIC PIPE ENTRANCE ELEVATION  
NO SCALE



- NOTES:
- ALL PIPE THIS ISOMETRIC COPPER TUBING UNLESS SPECIFICALLY INDICATED OTHERWISE.
  - CONNECT TO UNIT HEATER WITH 3/4"x1/2" BUSHING & 1/2" MPTxC ADAPTER.
  - PUMP P-UH1 WITH 1/2" SOLDER SHUT OFF FLANGES. SET TO SPEED 1.

4 TOURISM BUILDING HEAT RECOVERY PIPING ISOMETRIC  
NO SCALE



- NOTES:
- ONE ARCTIC PIPE ENTRANCE SHOWN. PROVIDE TWO IDENTICAL.
  - HOLE SAW 3"Ø THROUGH WALL SIDING AND URETHANE INSULATION. TRIM ARCTIC PIPE JACKET AT EXTERIOR OF SIDING AND EXTEND 2" STEEL PIPE THROUGH WALL. CENTER PIPE IN HOLE, PACK GAP WITH FIBERGLASS INSULATION, AND SEAL ALL AROUND INTERIOR WITH POLYURETHANE CAULK.
  - INSTALL FLASHING OVER ARCTIC PIPE JACKET. SEAL TO SIDING WITH POLYURETHANE CAULKING AND FASTEN WITH STAINLESS STEEL SHEET METAL SCREWS ALL AROUND.

- GENERAL NOTES:
- ALL PLANS AND ELEVATIONS THIS SHEET FOR GENERAL PIPING LAYOUT AND ARRANGEMENT ONLY. NOT ALL PIPE, FITTINGS, AND ACCESSORIES SHOWN FOR CLARITY, SEE PIPING ISOMETRIC THIS SHEET FOR ADDITIONAL DETAIL.
  - ALL PIPING INSIDE BUILDING TYPE L COPPER TUBING, 2" MAINS, 1/2" BRANCH.
  - INSULATE ALL 2" MAIN PIPING WITH FIBERGLASS INSULATION WITH PVC JACKET. ALL BRANCH PIPING NOT INSULATED.


ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM TOURISM BUILDING PLAN & DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
FILE NAME: NELS PP M8		SHEET:
PROJECT NUMBER:		M8.3






**1** STORAGE COMPOUND FIRST FLOOR LEVEL HEAT RECOVERY PLAN  
M8.4 1/4"=1'-0"



**2** STORAGE COMPOUND MEZZANINE LEVEL HEAT RECOVERY PLAN  
M8.4 1/4"=1'-0"



**3** STORAGE COMPOUND HEAT RECOVERY 2" MAIN PIPING ELEVATION  
M8.4 NO SCALE

#### GENERAL NOTES:

- ALL PLANS AND ELEVATIONS THIS SHEET FOR GENERAL PIPING LAYOUT AND ARRANGEMENT ONLY. NOT ALL PIPE, FITTINGS, AND ACCESSORIES SHOWN FOR CLARITY, SEE PIPING ISOMETRIC SHEET M8.5 FOR ADDITIONAL DETAIL.
- ALL PIPING INSIDE BUILDING TYPE L COPPER TUBING, 2" MAINS, 1/2" BRANCH.
- INSULATE ALL 2" MAIN PIPING WITH FIBERGLASS INSULATION WITH PVC JACKET. ALL BRANCH PIPING NOT INSULATED..
- WHERE 2" MAINS PENETRATE A WALL, SEAL INSULATION JACKET TO WALL ALL AROUND WITH POLYURETHANE CAULK.
- WHERE 1/2" BRANCH PIPING PENETRATES A WALL, PROVIDE ESCUTCHEON PLATES ON BOTH SIDES.


**ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.**

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM STORAGE COMPOUND PLANS & PIPING ELEVATION		
DRAWN BY: JTD	DESIGNED BY: BCG	SCALE: AS NOTED
FILE NAME: NELS PP M8	PROJECT NUMBER:	SHEET: <b>M8.4</b>
P.O. 111405, Anchorage, AK 99511 (907)349-0100		






## 1 STORAGE COMPOUND HEAT RECOVERY PIPING ISOMETRIC

NO SCALE



## 2 TYPICAL PIPE SUPPORT FROM VESTIBULE CEILING

NO SCALE




## 3 TYPICAL PIPE SUPPORT FROM MEZZANINE WALL

NO SCALE


ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM STORAGE COMPOUND PIPING ISOMETRIC & DETAILS		
DRAWN BY: JTD	SCALE: AS NOTED	SHEET: <b>M8.5</b>
DESIGNED BY: BCG	DATE: 5/30/23	
FILE NAME: NELS PP M8	PROJECT NUMBER:	
Gray Stassel Engineering, Inc.		
P.O. 111405, Anchorage, AK 99511 (907)349-0100		






- NOTES:
- 1) HEAT RECOVERY ARCTIC PIPE SUPPLY AND RETURN ENTRANCES ON OPPOSITE SIDES OF PARTITION WALL AND MOMENT FRAME (STEEL COLUMN), SEE PLAN M8.4.
  - 2) HOLE SAW 3"Ø THROUGH SIDING AND INTERIOR PARTITION WALL. TRIM ARCTIC PIPE JACKET AT EXTERIOR WALL SIDING EXTEND 2" STEEL PIPE THROUGH WALL. CENTER PIPE IN HOLE AND SEAL ALL AROUND INTERIOR WITH POLYURETHANE CAULK.
  - 3) INSTALL FLASHING OVER ARCTIC PIPE JACKET. SEAL TO SIDING WITH POLYURETHANE CAULKING AND FASTEN WITH STAINLESS STEEL SHEET METAL SCREWS ALL AROUND.


**1** STORAGE COMPOUND HEAT RECOVERY ARCTIC PIPE ENTRANCE  
M8.6 NO SCALE



**2** ARCTIC PIPE 45° OFFSET EXTENDED LEG ELBOW  
M8.6 NO SCALE



**4** TYPICAL UNIT HEATER UH-2 CEILING MOUNT INSTALLATION  
M8.6 1-1/2"=1'-0"





**3** APARTMENT CABINET UNIT HEATER INSTALLATION  
M8.6 1-1/2"=1'-0"



ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM STORAGE COMPOUND PIPING DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/30/23
	FILE NAME: NELS PP M8	SHEET: M8.6
PROJECT NUMBER:		






NOTES:

1. ALL PIPE THIS ISOMETRIC COPPER TUBING UNLESS SPECIFICALLY INDICATED OTHERWISE
2. CONNECT TO UNIT HEATER UH-2 WITH 1/2" MPTxC ADAPTER.
3. CONNECT TO UNIT HEATER UH-3 WITH 3/4" MPTxC ADAPTER.
4. PUMP P-UH2 WITH 1/2" SOLDER SHUT-OFF FLANGES. SET TO SPEED 1.
5. PUMP P-UH3 WITH 3/4" SOLDER SHUT-OFF FLANGES. SET TO SPEED 2.
6. ROUTE 1/2" COPPER TUBE DOWN THROUGH MEZZANINE FLOOR IN GIRT SPACE BEHIND BREAK ROOM WALL AND FASTEN UH-2 TO BREAK ROOM CEILING STRUCTURE WITH SHALLOW STRUT. SEE DETAIL 3/M8.8.

2 ICEHOUSE MEZZANINE HEAT RECOVERY PIPING ISOMETRIC

NO SCALE



3 3/4" COPPER TUBING SUPPORT IN GIRT SPACE

NO SCALE

GENERAL NOTES:


1. ALL PLANS AND ELEVATIONS THIS SHEET FOR GENERAL PIPING LAYOUT AND ARRANGEMENT ONLY. NOT ALL PIPE, FITTINGS, AND ACCESSORIES SHOWN FOR CLARITY, SEE PIPING ISOMETRIC THIS SHEET FOR ADDITIONAL DETAIL.
2. ALL PIPING INSIDE BUILDING TYPE L COPPER TUBING, 2" MAINS, BRANCHES 1/2" AND 3/4" AS INDICATED.
3. INSULATE ALL 2" MAIN PIPING WITH FIBERGLASS INSULATION WITH PVC JACKET. ALL BRANCH PIPING NOT INSULATED.

ALL WORK THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM ICEHOUSE PLAN, PIPING ISOMETRIC, & DETAILS		
DRAWN BY: JTD	SCALE: AS NOTED	M8.7
DESIGNED BY: BCG	DATE: 5/30/23	
FILE NAME: NELS PP M8	SHEET:	
PROJECT NUMBER:		




P.O. 111405, Anchorage, AK 99511 (907)349-0100










1 FIRE SUPPRESSION SYSTEM PLAN  
3/8"=1'-0"



2 TYPICAL SECTION THROUGH BUILDING  
3/8"=1'-0"

FIRE SUPPRESSION SYMBOL LEGEND			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
HD135°	NORMAL TEMP. (135°F) DETECTOR	P	MANUAL PULL STATION
HD190°	HIGH TEMP. (190°F) DETECTOR	WP	INTERIOR ALARM HORN/STROBE
FD	FLAME (OPTICAL) DETECTOR	WP	EXTERIOR ALARM HORN/STROBE
SD	SMOKE (IONIZATION) DETECTOR		

FIRE SUPPRESSION PLACARD SCHEDULE (SEE SHEET M1.2)	
SYMBOL	DESCRIPTION
A	"FIRE ALARM"
C	"CAUTION, ROOM PROTECTED BY WATER MIST FIRE PROTECTION SYSTEM, IN CASE OF FIRE KEEP DOOR CLOSED AND DO NOT ENTER"
D	"FLASHING LIGHT MEANS FIRE SUPPRESSION AGENT HAS DISCHARGED"

FIRE SUPPRESSION WIRE SCHEDULE			
SYMBOL	CIRCUIT DESCRIPTION	WIRE TYPE	WIRE COLOR
A	24V DC POWER	#14 AWG SOLID	RED & BLACK
B	DETECTION CIRCUITS	#14 AWG SOLID	BLUE & YELLOW
C	ANNUNCIATION ALARM	#14 AWG SOLID	BROWN & ORANGE
D	ANNUNCIATION DISCHARGE	#14 AWG SOLID	WHITE, & GRAY
E	24V DC AUX POWER	#14 AWG SOLID	RED & BLACK WITH GRAY STRIPE



GENERAL NOTES:

- INTERIOR FINISH OF ALL WALLS AND CEILING METAL SIDING. INTERIOR FINISH OF FLOOR WELDED STEEL PLATE. CEILING HEIGHT IN ALL ROOMS 10'-2" ABOVE FINISHED FLOOR.
- ALL DOORS SELF-CLOSING WITH GASKETS. ALL BUILDING PIPING AND CONDUIT PENETRATIONS SEALED LIQUID TIGHT. ALL BUILDING DUCT PENETRATIONS EQUIPPED WITH MOTORIZED DAMPERS THAT CLOSE ON GENERATOR SHUT DOWN.

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE. SEE SPECIFICATION 21 13 30 FOR DELINEATION OF FINAL RE-ASSEMBLY, TESTING, AND COMMISSIONING THAT IS INCLUDED IN THE ON SITE SCOPE.



























ISSUED FOR  
CONSTRUCTION  
MAY 2023













 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: FIRE SUPPRESSION SYSTEM PLAN, SECTION, LEGEND, & NOTES		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: BCG	SCALE: AS NOTED
	DESIGNED BY: BCG	DATE: 5/20/23
FILE NAME: NELS PP FS1	PROJECT NUMBER:	SHEET: FS1 OF 1


















EQUIPMENT REQUIREMENTS FOR APPROVED EQUALS (APPLIES TO ALL SCHEDULES):  
SPECIFIC PARTS MANUFACTURER AND MODEL SELECTED NOT ONLY TO MEET PERFORMANCE FUNCTION BUT ALSO TO COORDINATE AND INTERFACE WITH OTHER DEVICES AND SYSTEMS. APPROVED EQUAL SUBSTITUTIONS WILL BE ALLOWED ONLY BY ENGINEER'S APPROVAL. TO OBTAIN APPROVAL, SUBMITTALS MUST CLEARLY DEMONSTRATE HOW SUBSTITUTE ITEM MEETS OR EXCEEDS SPECIFIED ITEM QUALITY AND PERFORMANCE CHARACTERISTICS AND ALSO COMPLIES WITH MECHANICAL AND/OR ELECTRICAL CONNECTIONS AND PHYSICAL LAYOUT REQUIREMENTS.

ELECTRICAL EQUIPMENT SCHEDULE			
SYMBOL	SERVICE/FUNCTION	DESCRIPTION	MANUFACTURER/MODEL
	DAY TANK ALARM HORN/STROBE	MULTI-TONE ALARM WITH STROBE, 115V, NEMA 3R, WEATHER RESISTANT SURFACE MOUNT BELL BOX	WHEELLOCK MT4-115-WH-VNS
	DIGITAL THERMOSTAT	MULTIPLE OUTPUT MODULATING DIGITAL THERMOSTAT	HONEYWELL TB7980B
	LINE VOLTAGE THERMOSTAT	HEATING/COOLING THERMOSTAT, 16 FLA @ 120V, SPDT, 50F TO 80F RANGE.	DAYTON 1UHH2
	EXTERIOR LIGHT	AREA LIGHT, WIDE DISPERSION WALL PACK WITH PHOTO CONTROL LED, 17.7W, 120-277V DRIVER	HUBBELL NRG-356L-5K-U-PC
	EMERGENCY LIGHT	WHITE PLASTIC ENCLOSURE, 120-347V INPUT, DUAL 5.3W LED LAMPS, LITHIUM IRON PHOSPHATE BATTERY	LITHONIA EML6L UVOLT LTP SRDT
	EMERGENCY/EXIT LIGHT COMBO	WHITE PLASTIC ENCLOSURE, RED EXIT SIGN, 277/120V INPUT, DUAL 1.5W 9.6V LED LAMPS. OPTIONAL HIGH OUTPUT NI-CAD BATTERY	LITHONIA LHQM LED R HO
	EMERGENCY EXIT REMOTE LIGHT	REMOTE LAMP FIXTURE, DUAL HEAD, RATED FOR EXTERIOR INSTALLATION IN DAMP/WET LOCATIONS, 1.5W 9.6V LED LAMPS.	LITHONIA ELA T QWP L0309
	INTERIOR LIGHT	SURFACE MOUNTED LED STRIPLIGHT FIXTURE, 48" LONG, 34W, 5000°K WITH SNAP ON FROSTED DIFFUSER	LITHONIA L1N-L48-5000LM-FST
	TIMER SWITCH	0-5 MINUTE , 120V, 20A, 1HP RATED, INSTALL IN 4"x4" PRESSED STEEL BOX WITH METAL COVER.	INTERMATIC FF5M
	LIGHT SWITCH	SINGLE POLE SNAP SWITCH, 120V, 20A, METAL, 1-1/2HP RATED, INSTALL IN 4"x4" STEEL BOX WITH METAL COVER, IVORY.	HUBBELL 1221-I
	1Ø SMALL MOTOR DISCONNECT	SINGLE POLE SNAP SWITCH WITH RED PILOT LIGHT, 120V, 20A, 1HP RATED, INSTALL IN 4"x4" STEEL BOX WITH METAL COVER	HUBBELL 1221-PL
	NOT USED	NOT USED	
	STATION SERVICE TRANSFORMER	DRY TYPE, ENERGY STAR, ENCLOSURE TYPE 1 WITH INTEGRAL WALL MOUNT BRACKETS, 15 KVA, HV 480 DELTA, LV 208Y/120	HAMMOND HPS SENTINEL CAT. NO. SG3A0015KB
	STATION SERVICE PANELBOARD	COPPER BUS, 3 PHASE, 4 WIRE, 120/208V, 125A MAIN BREAKER, 42 CIRCUITS, BOLT-IN BREAKERS, 20" WIDE NEMA 1 ENCLOSURE, SURFACE MOUNT, NO KNOCKOUTS	SIEMENS TYPE P1 OR SQUARE D TYPE NQ
	STANDARD RECEPTACLE	SURFACE MOUNT 125V NEMA 5-20R RECEPTACLE. INSTALL IN 4"x4" STEEL BOX WITH METAL COVER	PASS & SEYMOUR 5362W
	EXTERIOR GFCI RECEPTACLE	125V NEMA 5-20R GFCI RECEPTACLE. MOUNT IN CAST FDA BOX WITH WEATHERPROOF COVER	PASS & SEYMOUR 2095-W
	BATTERY CHARGER	12/24-VOLT SOLID STATE 20-AMP AUTO-EQUALIZING BATTERY CHARGER FOR 120 VAC INPUT, WITH OPTIONAL HIGH/LOW VOLTAGE, AC POWER FAILURE, & REMOTE SUMMARY ALARM RELAYS	SENS NRC22-20-RCLS OR LEMARCHE ECSR-40/20-12/24V-AV1
	WELDER/COMPR. RECEPTACLE	NEMA 6-30R , BLACK, 250V, 30A, 2 POLE, WITH GROUND. INSTALL IN DEEP 4"x4" STEEL BOX WITH 2.15"Ø HOLE METAL COVER	PASS & SEYMOUR 3801
	NOT USED	NOT USED	
	RADIATOR MOTOR DISCONNECT	NON-FUSED LOCKABLE SAFETY SWITCH, NEMA 4X ENCLOSURE, 3PST, 600V, 30A, MIN 5HP RATED	SIEMENS HNF361S OR SQUARE D HU361S
	24VAC CONTROL TRANSFORMER	120V PRIMARY, 24V SECONDARY, 20VA OUTPUT, 1/2" THREADED HUB MOUNT	FUNCTIONAL DEVICES TR20VA001
	ENCLOSED POWER RELAY (RIB)	20A, 1HP RATED CONTACT, SPDT, 24VAC COIL, NEMA 1 ENCLOSURE, RED LED PILOT LIGHT	FUNCTIONAL DEVICES RIB2401B
	SNAP SWITCH WITH THERMAL UNIT	600VAC, 1HP, 1ØA MANUAL MOTOR STARTER WITH TYPE S, TYPE A, MELTING ALLOY, CLASS 20 THERMAL UNIT	SQUARE D 2510F01 MOTOR STARTER WITH A14.8 THERMAL UNIT
	ROUTER – HIGH SPEED INTERNET	4-PORT GIGABIT ROUTER, DUAL 2.4 AND 5 GHz WIFI WITH ADJUSTABLE ANTENNAS, 4 GIGABIT LAN, 1 GIGBIT WAN, USB 2.0 AND USB 4.0, MINIMUM 256 MB RAM	ASUS RT-ACI-900P
	480V NON-FUSED SVC. DISCONNECT	NON-FUSED LOCKABLE SAFETY SWITCH, NEMA 4X ENCLOSURE, 3PST, 600V, 200A	SIEMENS HNF364S OR SQUARE D HU364S
	480V FUSED SVC. DISCONNECT	FUSED LOCKABLE SAFETY SWITCH, NEMA 4X ENCLOSURE, 3PST, 600V, 200A, PROVIDE WITH 3 EA. 125A TYPE R FUSES PLUS 3 IDENTICAL SPARE FUSES	SIEMENS HF364S OR SQUARE D H364S



ELECTRICAL CONDUCTOR SCHEDULE			
SERVICE/FUNCTION	DESCRIPTION	MANUFACTURER/MODEL	NOTES:
GENERATOR LEADS (ENGINE STARTER CABLES SIMILAR)	HIGH TEMPERATURE, EXTRA FLEXIBLE CABLE, TIN COATED COPPER CONDUCTOR. THERMOSET EPDM INSULATION, UL 3340/3374, MINIMUM 600V, LISTED 150°C FOR NON-FLEXING	COBRA CABLE, BELDEN, OR OMNI	TERMINATE WITH COPPER COMPRESSION LUGS RATED FOR THE FULL AMPACITY OF THE CABLE AT 150°C
GENERAL USE CONDUCTORS	CLASS B CONCENTRIC STRANDED, SOFT DRAWN COPPER. TYPE XHHW2 INSULATION, 600V AND 90C RATED.		
SHIELDED/TWISTED INSTRUMENT & CONTROL & CANBUS CONDUCTORS	#18 AWG STRANDED TINNED COPPER CONDUCTORS, 600V POLYETHYLENE INSULATION, 100% COVERAGE ALUMINUM FOIL-POLYESTER TAPE SHIELD WITH STRANDED TINNED COPPER DRAIN WIRE & PVC OUTER JACKET	BELDEN PART #’S SINGLE PAIR: #1120A FOUR PAIR: #1049A SINGLE TRIAD: #1121A	GROUND SHIELD DRAIN WIRE AT PANEL END ONLY.
EHTERNET (CAT5e) COMMUNICATION CONDUCTORS	SOLID BARE COPPER CONDUCTORS, 300V FEP INSULATION & JACKET, 100% COVERAGE ALUMINUM FOIL-POLYESTER TAPE SHIELD WITH STRANDED TINNED COPPER DRAIN WIRE	FOUR PAIR #24 BELDEN 1585LC	GROUND SHIELD DRAIN WIRE AT PANEL END ONLY. ROUTE ALL DEVICENET & CAT5e CABLES IN SEPARATE DEDICATED RACEWAY.
UNLESS INDICATED OTHERWISE ALL CONDUCTORS SHALL USE THE FOLLOWING COLOR CODE: 480-VOLT POWER (PHASE) CONDUCTORS PHASE A: BROWN PHASE B: ORANGE PHASE C: YELLOW 120/208-VOLT POWER (PHASE) CONDUCTORS PHASE A: BLACK PHASE B: RED PHASE C: BLUE NEUTRAL: WHITE, NO EXCEPTIONS GROUND: GREEN OR BARE, NO EXCEPTIONS 24 VOLT DC CONDUCTORS +24VDC: RED or RED W/GRAY STRIPE -24VDC: BLACK or BLACK W/GRAY STRIPE CONTROL AND INSTRUMENT CONDUCTORS MAY BE COLOR CODED PER MANUFACTURER’S STANDARD		NOTES: 1) COLOR CODING FOR NO. 6 AWG AND SMALLER CONDUCTORS SHALL BE BY USING CONDUCTORS WITH CONTINUOUS COLOR EMBEDDED IN THE INSULATION. 2) COLOR CODING FOR CONDUCTORS LARGER THAN NO. 6, SHALL BE BY: A) CONTINUOUS COLOR EMBEDDED IN THE INSULATION, OR B) BLACK CABLE WITH SCOTCH 35 OR APPROVED EQUAL MARKING (PHASE) TAPE. AT EVERY ACCESSIBLE LOCATION A MINIMUM 3" LONG SECTION OF CONDUCTOR SHALL BE SPIRAL WRAPPED. NOTE THAT PHASE TAPE MAY NOT BE USED ON COLORED CABLE, BLACK CABLE ONLY. 3) GROUNDING – PROVIDE A SEPARATE GREEN INSULATED EQUIPMENT GROUNDING CONDUCTOR IN EACH RACEWAY. DO NOT USE THE CONDUIT AS AN EQUIPMENT GROUNDING CONDUCTOR. EQUIPMENT GROUNDING CONDUCTORS SHALL BE OF THE SAME TYPE AS THE PHASE CONDUCTORS AND SHALL BE SIZED AS INDICATED ON THE DRAWINGS. CONDUCTORS NOT INDICATED SHALL BE SIZED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.	

WIRING & DEVICE SYMBOL LEGEND			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	HOME RUN TO PANEL & BREAKER(S) INDICATED. SHORT DASH INDICATES HOT CONDUCTOR, LONG DASH INDICATES NEUTRAL CONDUCTOR, CURVED DASH INDICATES GROUND CONDUCTOR. IF NOT SPECIFICALLY INDICATED, PROVIDE 2#12 AWG & 1#12 AWG GROUND.		125V, 20A, DUPLEX RECEPTACLE
			LINE VOLTAGE THERMOSTAT
			DIGITAL THERMOSTAT, MODULATING
	ELECTRICAL ITEM – SEE EQUIPMENT SCHEDULE		SNAP SWITCH / SMALL MOTOR DISCONNECT
	MOTOR (HORESPOWER INDICATED)		TIMER SWITCH
	MOTORIZED DAMPER – SEE MECHANICAL		GROUND


DISTRIBUTION PLAN SYMBOL LEGEND			
EXISTING	NEW		
		PADMOUNT TRANSFORMER ID AND KVA INDICATED	
		PRIMARY SECTIONALIZING CABINET, ID INDICATED, 3Ø OR 1Ø AS INDICATED IN STAKING SHEETS	
		3Ø BURIED 15kV PRIMARY JCN CIC (NEW)	
		1Ø BURIED 15kV PRIMARY JCN CIC (NEW)	
		3Ø BURIED 15kV PRIMARY JCN CIC (EXISTING)	
		3Ø DIRECT BURIED 600V UD CABLE	

INSTRUMENTATION & ENERGY MEASUREMENT LEGEND			
NOTE: SEE SCHEDULES SHEET M1.1 FOR EQUIPMENT SPECIFICATIONS.			
SYMBOL	SERVICE/FUNCTION	SYMBOL	SERVICE/FUNCTION
	TEMPERATURE TRANSMITTER		DAY TANK/HOPPER FLOAT SWITCH
	PRESSURE TRANSMITTER		GLYCOL TANK LEVEL SENSOR PROBE
	TANK LEVEL MONITOR PANEL		GLYCOL TANK LOW COOLANT ALARM
	TANK LEVEL SENSOR PROBE		


ALL MATERIALS AND EQUIPMENT ON SCHEDULES THIS SHEET WERE FURNISHED AS PART OF THE PRIOR MODULE ASSEMBLY PROJECT EXCEPT FOR THOSE ITEMS SPECIFICALLY INDICATED IN RED CLOUDS WHICH ARE TO BE FURNISHED AND INSTALLED AS PART OF THE ON SITE SCOPE.

1	DELETED FLOW METER	7/7/23	BCG
REV.	DESCRIPTION	DATE	BY
			
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: ELECTRICAL LEGENDS & SCHEDULES			
		DRAWN BY: JTD	SCALE: NO SCALE
		DESIGNED BY: CWV/BCG	DATE: 5/30/23
		FILE NAME: NELS PP E1	SHEET: E1.1
P.O. 111405, Anchorage, AK 99511 (907)349-0100		PROJECT NUMBER:	

REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023







1 POWER PLANT AREA ELECTRICAL SITE PLAN  
E1.2 1"=30'

#### DEMOLITION GENERAL NOTES:

- 1) ALL EXISTING ENERGY INFRASTRUCTURE REPLACED THIS PROJECT TO BE ABANDONED IN PLACE UNLESS SPECIFICALLY INDICATED OTHERWISE.
- 2) ALL UNDERGROUND CONDUCTORS BEING TAKEN OUT OF SERVICE SHALL BE CUT OFF AT BOTH ENDS 18" MINIMUM BELOW GRADE AT BOTH ENDS AND ABANDONED IN PLACE.

#### NEW WORK GENERAL NOTES:

- 1) ALL INSTALLATION SHALL MEET THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL SAFETY CODE (NESC), ANSI C2, AND THE NATIONAL ELECTRICAL CODE, NFPA 70, INCLUDING ANY STATE OF ALASKA AMENDMENTS. RUS BULLETIN 1728F-806 (RD-GD-2018-93), SPECIFICATIONS AND DRAWINGS FOR UNDERGROUND ELECTRIC DISTRIBUTION SHALL BE FOLLOWED UNLESS SPECIFICALLY MODIFIED BY THESE DRAWINGS OR SPECIFICATIONS. ALL MATERIAL SHALL BE RUS APPROVED. OBTAIN COPIES OF THE RUS BULLETINS AND MAINTAIN COPIES OF THE BULLETINS AND SPECIFICATIONS AT THE JOB SITE AT ALL TIMES.
- 2) THE DRAWINGS SHOW APPROXIMATE LOCATION OF SOME EXISTING UNDERGROUND ELECTRIC POWER. PRIOR TO BEGINNING EXCAVATION, LOCATE ALL UNDERGROUND UTILITIES INCLUDING BUT NOT LIMITED TO ELECTRIC POWER, TELECOMMUNICATIONS, WATER, SEWER, AND FUEL.
- 3) ANY UTILITIES DAMAGED DURING EXCAVATION SHALL BE REPAIRED PROMPTLY TO THE SATISFACTION OF THE AUTHORITY AND THE UTILITY AT NO COST TO THE AUTHORITY.
- 4) WHERE MULTIPLE UTILITIES ARE BURIED IN A COMMON TRENCH, PLAN OUT WORK AND COORDINATE TRADES TO INSTALL ALL BURIED UTILITIES TOGETHER.
- 5) TAKE CARE TO PROTECT EXISTING BUILDING FOUNDATIONS, SLABS, SIDEWALKS, AND OTHER EXISTING FEATURES WHEN EXCAVATING FOR ARCTIC PIPE. BACKFILL WITH EXCAVATION SPOILS OR SANDY GRAVEL, COMPACT, AND BLEND INTO EXISTING GRADE. RESTORE ALL EXCAVATION AREAS TO ORIGINAL CONDITION UPON COMPLETION.


#### SPECIFIC NOTES:



- 1) EXISTING POWER PLANT TO BE TAKEN OUT OF SERVICE AND ABANDONED IN PLACE UPON COMMISSIONING OF NEW POWER PLANT.
- 2) EXISTING STEP UP TRANSFORMER BANK TO BE TAKEN OUT OF SERVICE AND ABANDONED IN PLACE UPON COMMISSIONING OF NEW POWER PLANT. CUT OFF ALL BELOW GRADE CONDUCTORS AND REMOVE 480V SECONDARY CONDUCTORS FROM POWER PLANT.
- 3) INSTALL NEW 1Ø TRANSFORMER TO SERVE GCI EARTH STATION. CONNECT NEW 240/120V SERVICE TO EXISTING METER BASE.
- 4) CAREFULLY REMOVE EXISTING INTERMEDIATE TANK CONTROL PANEL AND SALVAGE FOR REUSE IN NEW MODULAR POWER PLANT.
- 5) THE EXISTING BURIED CLX MULTI-CONDUCTOR ARMORED CABLE PRESENTLY CONNECTS THE EXISTING INTERMEDIATE TANK CONTROL PANEL TO THE TANK FARM MAIN CONTROL PANEL FOR CONTROL OF POWER PLANT FUEL TRANSFERS. CUT AND REROUTE TO NEW POWER PLANT, SEE ENLARGED PLAN SHEET E1.3.
- 6) EXISTING SECTIONALIZING CABINET IS PROTECTED BY PIPE RAIL BOLLARD, SEE PHOTO BELOW. POSITION NEW SECTIONALIZING CABINET TO CONNECT TO EXISTING CABLES, TO PROVIDE REQUIRED ACCESS, AND TO INSTALL IN ACCORDANCE WITH DETAIL. REMOVE HORIZONTAL PIPE RAIL ACROSS FRONT OF SECTIONALIZING CABINET AND GRIND CUTS SMOOTH. WIRE BRUSH REMAINING PIPE RAIL BOLLARD AND PAINT SAFETY YELLOW. SEE PHOTO BELOW.




ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: POWER PLANT AREA ELECTRICAL SITE PLAN		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: NO SCALE
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
	FILE NAME: NELS PP E1	SHEET:
	PROJECT NUMBER:	E1.2





EXISTING BURIED CABLE SPECIFIC NOTES:

- EXISTING BURIED MULTI-CONDUCTOR DIRECT BURY ARMORED CABLE IS 14-#14 AWG TYPE CLX CABLE WITH ALUMINUM SHEATH AND PVC JACKET, APPROXIMATELY 1.25" O.D.
- LOCATE EXISTING ARMORED CABLE & FUEL PIPELINES IN THIS AREA. HAND EXCAVATE OR USE AIR SPADE AS REQUIRED TO EXPOSE ARMORED CABLE, BEING CAREFUL NOT TO DAMAGE CABLE OR FUEL PIPELINES. MEASURE THE LINEAL FEET FROM A POINT ON THE ARMORED CABLE (LOCATION "0" AS SHOWN ON PLAN) TO THE NEW MODULE CABLE ENTRANCE FOLLOWING THE NEW TRENCH ROUTE. THIS MEASUREMENT IS DESIGNATED AS DISTANCE "L".
- CAREFULLY EXCAVATE AND EXPOSE L+15' OF ADDITIONAL EXISTING ARMORED CABLE FOR RE-ROUTING TO MODULE
- CAREFULLY CUT ARMORED CABLE AT DISTANCE L+15' FROM LOCATION "0".
- L+15' LENGTH OF UNEARTHED ARMORED CABLE TO BE ROUTED TO MODULE WITH NEW BURIED FUEL PIPELINE.
- AFTER FILLING TANK, MEASURE FUEL HEIGHT THEN CALIBRATE LEVEL SENSOR PROBE USING TANK LEVEL MONITOR PANEL IN FACE OF DAY TANK CONTROL PANEL.
- PRIOR TO INSTALLING FLOAT SWITCH IN TANK, MAKE TEMPORARY ELECTRICAL CONNECTIONS AND MANUALLY MANIPULATE EACH FLOAT IN ORDER TO TO VERIFY ACTUATION LENGTH AND N.O./N.C. FUNCTION IN ACCORDANCE WITH SPECIFICATIONS ON INSTRUMENTATION SCHEDULE SHEET M1.1. AFTER INSTALLATION, VERIFY PROPER CONTROL FUNCTION USING TEMPORARY JUMPERS.

GENERAL GROUNDING & FEEDER NOTES:

- CAD-WELD ALL GROUNDING GRID CABLE AND GROUND ROD CONNECTIONS.
- MAKE ALL GROUND CONNECTIONS TO SKID BEAMS WITH COPPER COMPRESSION LUGS AND STAINLESS STEEL BOLTS. DRILL AND TAP BEAMS TO ENSURE FULL CONTACT OF THREADS TO CLEAN BARE STEEL. SEE DETAIL 2/E2, SIMILAR. ALTERNATELY, CAD WELD TO UNPAINTED BOTTOM FACE OF BEAM.
- NEW PAD MOUNT TRANSFORMER, SEE SHEET E1.4 FOR SCHEDULE AND INSTALLATION DETAIL.
- FOR ALL EXTERIOR GRC, CLEAN AND DE-GREASE THREADS AFTER CUTTING AND SPRAY WITH COLD GALV PRIOR TO ASSEMBLY.
- SEE STATION SERVICE SHEET E4.2 AND SHEETS E7.1-E7.4 FOR INTERIOR FUEL SYSTEM WIRING ROUTING AND TERMINATIONS.

ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT:  
NELSON LAGOON POWER SYSTEM UPGRADE

TITLE:  
POWER PLANT ENLARGED ELECTRICAL SITE PLAN


Gray  
Stassel  
Engineering, Inc.  
P.O. 111405, Anchorage, AK 99511 (907)349-0100

DRAWN BY: JTD	SCALE: NO SCALE
DESIGNED BY: CWV/BCG	DATE: 5/30/23
FILE NAME: NELS PP E1	SHEET:
PROJECT NUMBER:	E1.3




STAKING SHEET																	
LOCATION NUMBER	PRIMARY					XFMR	SECONDARY CONDUCTOR					SECONDARY SERVICE		MISCELLANEOUS CONSTRUCTION UNITS		REMARKS, COMMENTS, NOTES	
	CONDUCTOR			PRIMARY ASSEMBLY			SERVICE		BACKFEED								
	No.	SIZE/TYPE	BACK SPAN	No.	UNITS		No.	UNITS	No.	SIZE/TYPE	BACK SPAN	No.	SIZE/TYPE	No.	UNITS		No.
<u>TR-0-1</u>				1	UF3.BNa	1	UG3.3-150								1	UH1.1	STEP-UP TRANSFORMER. SEE DETAILS AND ONE-LINE DIAGRAM FOR CONDUCTORS FROM SWITCHGEAR TO SECONDARY TERMINALS.
				3	UM6.EL2										6	UM6.C2	
				3	UM6.PK2												
<u>SC-0</u>	3	#2 AL JCN, CIC	15	1	15US3.PJ.2222a										1	UH1.1	SEE NOTE 2.
				7	UM6.EL2										8	UM6.C2	
				3	UM6.PK2												
				3	UM6.JN2222												
<u>TR-0-2</u>	1	#2 AL JCN, CIC	170	1	UF1.BNa	1	UG1.3-15	2	#2 TPLX				2	SEE PLAN DWG	1	UH1.1	ONE SINGLE-PHASE SERVICE TO GCI LAND STATION.
				1	UM6.EL2										2	UM6.C2	
				1	UM6.PK2												
<u>SC-1</u>	3	#2 AL JCN, CIC	260	1	15US3.PJ.2222a										4	UM6.C2	SEE NOTES 2, 4, AND 5. FOR 7 EXISTING CONDUCTORS BEING RECONNECTED REMOVE OLD LOAD BREAK ELBOWS AND REPLACE WITH NEW.
				8	UM6.EL2												
				3	UM6.PK2												
				3	UM6.JN2222												

STAKING SHEET NOTES														
1. DIMENSIONS SHOWN IN STAKING SHEET ARE APPROXIMATE. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.														
2. SEE PLAN DRAWINGS FOR ADDITIONAL REQUIREMENTS.														
3. INSTALL NEW CONDUCTORS TO SECTIONALIZING CABINET AND INSTALL EQUIPMENT SHOWN OR SPECIFIED. CABLE SHALL BE INSTALLED AS INDICATED FOR NEW SECTIONALIZING CABINETS.														
4. INSTALL NEW SECTIONALIZING CABINET IN LOCATION OF THE EXISTING SECTIONALIZING CABINET. MODIFY PIPE RAIL BOLLARD AS REQUIRED TO PROVIDE FRONT ACCESS TO THE NEW SECTIONALIZING CABINET. RECONNECT THE EXISTING DISTRIBUTION PRIMARY CONDUCTORS TO THE NEW CABINET. PERFORM WORK IN A MANNER TO MINIMIZE COMMUNITY POWER OUTAGES.														
5. AFTER OLD POWER PLANT IS DE-ENERGIZED, REMOVE THE EXISTING STEP-UP TRANSFORMER FEED AND INSTALL INSULATED CAPS OVER JUNCTION POINTS. CUT THE EXISTING DE-ENERGIZED CABLES OUTSIDE OF THE CABINET.														
6. BURY SECONDARY CABLE 24" DEEP.														
7. ALL HARDWARE AND FASTENERS SHALL BE 316 STAINLESS STEEL.														
8. RUS UNIT US3.PJa, SECTIONALIZING CABINET, IS NOT COMPLETE AS SHOWN ON THE RUS CONSTRUCTION UNIT. REFER TO DETAILS ON THE DRAWINGS AND SPECIFICATIONS TO DETERMINE COMPLETE REQUIREMENTS FOR SECTIONALIZING CABINETS.														



- NOTES:
1. INSTALL GROUNDING LUG, HUBBELL/FARGO CC-207P ON EACH MOUNTING BOARD AND CONNECT TO GROUND.
  2. SEE RUS US3.PJ FOR ADDITIONAL GROUNDING NOTES.
  3. INSTALL DRAIN WIRE ON EACH UM6.C2.
  4. ENSURE THAT ALL METAL COMPONENTS ARE GROUNDING.
  5. PROVIDE SLACK IN THE CABLE TO THE MAXIMUM EXTENT PRACTICABLE. IF POSSIBLE, PROVIDE ONE FULL LOOP AROUND THE BASE OF THE GROUND SLEEVE OR SECTIONALIZING CABINET. SEE SPECIFICATIONS.
  6. INSTALL EQUIPMENT NAME ON OUTSIDE OF CABINET. SEE SPECIFICATIONS.
  7. PROVIDE 18" CABINET EXTENSION. SEE SPECIFICATIONS
  8. RUS CONSTRUCTION UNITS MAY NOT BE COMPLETE. SEE STAKING SHEET FOR COMPLETE UNIT NUMBERS.
  9. ALL METAL MATERIAL SHALL BE TYPE 316 STAINLESS STEEL.

1  
E1.4  
RUS US3.PJa PRIMARY SECTIONALIZING CABINET INSTALLATION  
NO SCALE




- NOTES:
1. THREE PHASE OR SINGLE PHASE AS INDICATED ON THE DRAWINGS AND STAKING SHEETS.
  2. PROVIDE SLACK IN THE CABLE TO THE MAXIMUM EXTENT PRACTICABLE. IF POSSIBLE, PROVIDE ONE FULL LOOP AROUND THE BASE OF THE GROUND SLEEVE.
  3. INSTALL DRAIN WIRE TO EACH UM6.EL2 AND UM6.C2.
  4. SEE RUS CONSTRUCTION UNITS UH1.1 FOR ADDITIONAL REQUIREMENTS.
  5. RUS CONSTRUCTION UNITS MAY NOT BE COMPLETE. SEE STAKING SHEET FOR COMPLETE UNIT NUMBERS.

2  
E1.4  
RUS UF1.BNa & UF3.BNa TRANSFORMER GROUND SLEEVE INSTALLATION  
NO SCALE

GENERAL NOTES					
1) ALL INSTALLATION SHALL MEET THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL SAFETY CODE (NEC), ANSI C2, INCLUDING ANY STATE OF ALASKA AMENDMENTS. RUS BULLETIN 1728F-806 (RD-GD-2018-93), SPECIFICATIONS AND DRAWINGS FOR UNDERGROUND ELECTRIC DISTRIBUTION SHALL BE FOLLOWED UNLESS SPECIFICALLY MODIFIED BY THESE DRAWINGS OR SPECIFICATIONS. ALL MATERIAL SHALL BE RUS APPROVED. OBTAIN COPIES OF THE RUS BULLETINS AND MAINTAIN COPIES OF THE BULLETINS AND SPECIFICATIONS AT THE JOB SITE AT ALL TIMES.					
2) THE DRAWINGS, STAKING SHEETS, AND SPECIFICATIONS ARE COMPLEMENTARY. WHAT IS SHOWN ON ONE IS BINDING WHETHER SHOWN ON THE OTHER OR NOT. DEFECTS OR DEFICIENCIES SHALL BE CORRECTED IN ACCORDANCE WITH ALL REQUIREMENTS OF THE DRAWINGS, STAKING SHEETS, AND SPECIFICATIONS.					


DISTRIBUTION TRANSFORMER SCHEDULE (OWNER FURNISHED)					
TRANSFORMER NUMBER	CAPACITY	PHASE	HIGH VOLTAGE	LOW VOLTAGE	NOTES
TR-0-1 COMMUNITY FEEDER	150kVA	3ø	12.47/7.2 kV GROUNDED WYE	480/277V	WITH FIBERGLASS GROUND SLEEVE
TR-0-2 GCI EARTH STATION	15kVA	1ø	7.2kV	240/120V	WITH FIBERGLASS GROUND SLEEVE

- NOTES:
- 1) BURY PRIMARY CABLE IN DUCT 48" MIN. BURY SECONDARY UD CABLE 36" MIN.
  - 2) INSTALL SECONDARY UD CABLE IN PVC CONDUIT WHERE INDICATED ON PLANS.



3  
E1.4  
TYPICAL BURIED PRIMARY INSTALLATION  
NO SCALE


- NOTES:
- 1) SEE MECHANICAL FOR LOCATIONS WHERE POWER CABLES ARE BURIED WITH ARCTIC PIPE.
  - 2) COORDINATE TRADES TO INSTALL ALL BURIED UTILITIES TOGETHER.



4  
E1.4  
TYPICAL BURIED PRIMARY INSTALLATION WITH OTHER UTILITIES  
NO SCALE


ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT. NOTE THAT THE PAD MOUNT TRANSFORMERS, GROUND SLEEVES, AND FIBERGLASS SECTIONALIZING CABINETS ARE OWNER PROVIDED AND CONTRACTOR INSTALLED.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NESLON LAGOON POWER SYSTEM UPGRADE		
TITLE: POWER PLANT AREA STAKING SHEET & DISTRIBUTION DETAILS		
	DRAWN BY: JTD	SCALE: NO SCALE
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
P.O. 111405, Anchorage, AK 99511 (907)349-0100	FILE NAME: NELS PP E1	SHEET: E1.4
	PROJECT NUMBER:	






1 TANK FARM CONDUCTOR BREAK-OUT/J-BOX INSTALLATION  
E1.5 NO SCALE

- NOTES:
- 1) PRIOR TO REMOVING EXISTING VALVE, VERIFY CONNECTIONS & FUNCTION. RECONNECT EXISTING CONDUCTORS TO NEW VALVE TO MATCH FUNCTION.
  - 2) SEE MECHANICAL FOR ACTUATED BALL VALVE SPECIFICATIONS & INSTALLATION.




2 TANK FARM ACTUATOR ABV-2 CONNECTION  
E1.5 NO SCALE


- NOTES:
- 1) ACTUATED BALL VALVE CONTROLLED FROM FUEL SYSTEM CONTROL PANEL IN POWER PLANT, SEE LOGIC DIAGRAM SHEET E7.1 FOR CONDUCTOR TERMINATIONS.
  - 2) SEE MECHANICAL FOR ACTUATED BALL VALVE SPECIFICATIONS & INSTALLATION.



3 INT. TANK ACTUATOR ABV-1 CONNECTION  
E1.5 NO SCALE




4 INTERMEDIATE TANK LEVEL SENSOR PROBE INSTALLATION  
E1.5 NO SCALE



TANK FARM MULTI-CONDUCTOR ARMORED CABLE BREAK-OUT WIRE/SPLICE SCHEDULE					
NEW J-BOX TERMINAL NUMBER (ABOVE)	WIRE TAG NUMBER	INTERMEDIATE TANK CONTROL PANEL TERMINAL NUMBER	FUNCTION	EXISTING WIRE COLORS: #14 BREAK OUT CONDUCTORS FROM TANK FARM TO NEW J-BOX TERMINAL	NEW WIRE COLORS: CONDUCTORS FROM NEW J-BOX TERMINAL TO INTERMEDIATE TANK CONTROL PANEL
1	73	101	PANEL POWER	BLACK	BLACK
2	74	102	PANEL NEUTRAL	WHITE	WHITE
3	76	105	PUMP TP-1 LATCH	BLACK/DARK BLUE	BLUE WITH 105 TAG
4	77	106	CONTACTOR M1 COIL	BLACK/ORANGE	BLUE WITH 106 TAG
5	71	107	REMOTE ALARM HORN	BLACK/LIGHT BLUE	BLUE WITH 107 TAG
6	72	108	REMOTE ALARM HORN	RED/BLUE	BLUE WITH 108 TAG
7	77	109	OVERFILL INDICATION	BROWN/RED	BLUE WITH 109 TAG
8	N/A	8	SPARE	RED	
9	N/A	9	SPARE	BLUE	
10	N/A	10	SPARE	ORANGE	
11	N/A	11	SPARE	YELLOW	
12	N/A	12	SPARE	BROWN	
13	N/A	13	SPARE	BLACK/BROWN	
14		GROUND	GROUND	GREEN	GREEN

NOTE: ALL NEW CONDUCTORS THIS SCHEDULE #14 AWG XHHW. COLOR & TAG AS INDICATED.

5 TANK FARM CONDUCTOR BREAK-OUT/JUNCTION BOX DETAILS  
E1.5 NO SCALE





- NOTES:
- 1) PRIOR TO INSTALLING IN TANK, MAKE TEMPORARY ELECTRICAL CONNECTIONS AND MANUALLY MANIPULATE EACH FLOAT IN ORDER TO VERIFY ACTUATION LENGTH AND N.O./N.C. FUNCTION IN ACCORDANCE WITH SPECIFICATIONS ON INSTRUMENTATION SCHEDULE SHEET M1.1.
  - 2) LABEL FLOAT SWITCH TERMINALS WITH THE NUMBER OF THE ASSOCIATED HOME RUN LANDING ON THE TERMINALS IN THE INTERMEDIATE TANK CONTROL PANEL. SEE EXISTING TANK FARM PANEL REFERENCE DRAWINGS SHEET E-09.
  - 3) AFTER INSTALLATION, VERIFY PROPER CONTROL FUNCTION USING TEMPORARY JUMPERS.

6 LEVEL SWITCH INSTALLATION  
E1.5 NO SCALE


ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




 ALASKA ENERGY AUTHORITY		
PROJECT: NESLON LAGOON POWER SYSTEM UPGRADE		
TITLE: POWER PLANT SITE ELECTRICAL DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: NO SCALE
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
FILE NAME: NELS PP E1	SHEET: E1.5	
	PROJECT NUMBER:	





1 MODULE PARTIAL SOUTH END WALL FEEDER ELEVATION  
E1.6 NO SCALE




NOTES:

- 1) CONDUIT WALL PENETRATION INSTALLED AS PART OF MODULE SHOP FABRICATION. REMOVE CAP AND INSTALL EXTERIOR CONDUIT AS SHOWN. LEAVE SPARE CONDUIT CAPPED.
- 2) INSTALL HEAT SHRINK TAPE TO FORM WATERTIGHT SEAL FROM LT FLEX ONTO GRC COUPLING.
- 3) UPON COMPLETION OF TESTING, PACK GRC NIPPLE THROUGH WALL WITH DUCT SEAL.
- 4) PROVIDE TRANSFORMER GROUNDING IN ACCORDANCE WITH RUS CONSTRUCTION UNIT UH1.1. BOND TRANSFORMER NEUTRAL AND GROUND TO #2/0 FROM SWITCHGEAR AND TO GROUND ROD.
- 5) INSTALL LIQUID TIGHT FLEX RISER WITH SLACK BENDS TO ALLOW FOR POTENTIAL DIFFERENTIAL GROUND MOVEMENT FLEX.

2 TRANSFORMER FEEDER ENTRANCE  
E1.6 NO SCALE


ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NESLON LAGOON POWER SYSTEM UPGRADE		
TITLE: MODULE FEEDER DETAILS		
 P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: NO SCALE
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
	FILE NAME: NELS PP E1	SHEET: E1.6
PROJECT NUMBER:		







1 POWER PLANT COMMUNICATIONS PLAN  
E1.7 1/4"=1'-0"

- INTERNET SERVICE GENERAL NOTES:
- 1) THE INTERNET SERVICE SHALL HAVE THE FOLLOWING MINIMUM PERFORMANCE CHARACTERISTICS:  
20 MBPS DOWNLOAD  
5 MBPS UPLOAD  
NO MONTHLY DATA LIMIT  
STARLINK STANDARD OR APPROVED EQUAL.
  - 2) FURNISH AND INSTALL COMPLETE SYSTEM WITH ANTENNA, PIPE MOUNT ADAPTER, MODEM, CABLE, CONNECTORS, ETHERNET ADAPTER, AND ACCESSORIES REQUIRED TO PROVIDE INTERNET SERVICE TO THE NEW POWER PLANT.
  - 3) UPON COMPLETION OF INSTALLATION THE INTERNET SYSTEM SHALL BE COMMISSIONED IN ACCORDANCE WITH THE SERVICE PROVIDER'S REQUIREMENTS.
  - 4) IN ADDITION TO FURNISHING AND INSTALLING SYSTEMS, THE CONTRACTOR SHALL PRE-PAY FOR A 1 YEAR INTERNET SERVICE CONTRACT.



2 COMMUNICATIONS ANTENNA & MAST INSTALLATION DETAILS  
E1.7 1/2"=1'-0"

ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT.

1	CHANGED INTERNET SERVICE TO STARLINK	11/13/23	BCG
REV.	DESCRIPTION	DATE	BY
 ALASKA ENERGY AUTHORITY			
PROJECT: NESLON LAGOON POWER SYSTEM UPGRADE			
TITLE: POWER PLANT COMMUNICATION PLAN & DETAILS			
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100		DRAWN BY: JTD	SCALE: NO SCALE
		DESIGNED BY: CWV/BCG	DATE: 5/30/23
		FILE NAME: NELS PP E1	SHEET: E1.7
		PROJECT NUMBER:	

REV#1  
ISSUED FOR  
CONSTRUCTION  
NOV 2023








EXISTING METER BASE, SERVICE DISCONNECT, AND TRANSFER SWITCH TO REMAIN, SEE NEW WORK FOR METER BASE REFURBISHMENT

DISCONNECT EXISTING FEEDER CONDUCTORS FROM MAIN BREAKER IN METER BASE

DEMOLISH EXISTING FEEDER CONDUCTORS & CONDUIT TO 18" BELOW GRADE & ABANDON IN PLACE



ICE HOUSE 480V 3Ø SERVICE NEW WORK

1 ICE HOUSE 480V SERVICE ENTRANCE ELEVATION  
E1.8 3/4"=1'-0"




DISCONNECT EXISTING FEEDER CONDUCTORS FROM MAIN BREAKER IN INTERIOR PANEL MDP-1

EXISTING 3" LB CONDUIT BODY TO REMAIN, SEE NEW WORK FOR REFURBISHMENT

EXISTING BURIED FEEDERS TO REMAIN, TYP(3)

DEMOLISH EXISTING FEEDER CONDUCTOR & CONDUIT TO 12" BELOW GRADE AND ABANDON IN PLACE




STORAGE COMPOUND 480V 3Ø SERVICE NEW WORK

STORAGE COMPOUND 480V 3Ø SERVICE DEMOLITION

3 STORAGE COMPOUND 480V SERVICE ENTRANCE ELEVATION  
E1.8 3/4"=1'-0"

2 ICEHOUSE 480V SERVICE CONDUCTOR SPLICE J-BOX  
E1.8 NO SCALE



4 TRANSITION TO DIRECT BURY UD CABLE  
E1.8 NO SCALE

NOTES:

1. BED UD CABLE WITH 3/4" MINUS SAND/GRAVEL MINIMUM 4" ALL AROUND.
2. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT TO 95% DENSITY.


ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NESLON LAGOON POWER SYSTEM UPGRADE		
TITLE: ICE HOUSE & STORAGE COMPOUND ELECTRICAL SERVICE DETAILS		
DRAWN BY: JTD	DESIGNED BY: CWV/BCG	SCALE: NO SCALE
FILE NAME: NELS PP E1	PROJECT NUMBER:	SHEET: E1.8






1  
E2

POWER PLANT GROUNDING PLAN

3/8"=1'-0"



2  
E2

GENERATOR GROUNDING

NO SCALE

GROUNDING GENERAL NOTES:

- 1) SEE ON-SITE WORK FOR POWER PLANT GROUNDING GRID.
- 2) CONTINUOUSLY WELDED STEEL STRUCTURE PROVIDES GROUND PATH THROUGH MODULE.
- 3) IN FEEDER SECTION PROVIDE #2/0 BARE COPPER JUMPER FROM GROUND BUS TO STEEL FLOOR. SEE DETAIL 2/E2, SIMILAR.



GROUNDING SHOP/ON-SITE NOTES:

- 1) ALL WORK SHOWN THIS SHEET TO BE PERFORMED AS PART OF THE MODULE ASSEMBLY SHOP FAB WORK.
- 2) AS PART OF MODULE ASSEMBLY WORK, TEMPORARILY BOND SWITCHGEAR NEUTRAL BUS TO GROUND BUS FOR LOAD BANK TESTING AND LEAVE IN PLACE.
- 3) AS PART OF ON-SITE WORK LEAVE NEUTRAL TO GROUND BUS BONDING JUMPER IN PLACE AS REQUIRED FOR LOAD BANK TESTING.
- 4) REMOVE JUMPER AFTER LOAD BANK TESTING AND PRIOR TO CONNECTING TO THE GRID FOR COMMISSIONING.


ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: MODULE GROUNDING PLAN & DETAILS		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: JTD	SCALE: AS NOTED
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
	FILE NAME: NELS PP E2-E5	SHEET: E2
PROJECT NUMBER:		






1 EQUIPMENT LAYOUT & WIREWAY PLAN  
3/8"=1'-0"



2 TYPICAL MODULE SECTION  
3/4"=1'-0"





5 4" WIREWAY SUPPORT FROM WALL  
NO SCALE

ENGINE-GENERATOR SCHEDULE	
GENSET	DESCRIPTION
GEN #1	ENGINE - 148 HP, 100 EKW PRIME, JOHN DEERE 4045AFM85, TIER 3 MARINE. 24 VDC STARTING & CONTROL. GENERATOR - MINIMUM 125 KW CONTINUOUS AT 105°C RISE, NEWAGE/STAMFORD UCI274E.
GEN #2	ENGINE - 148 HP, 100 EKW PRIME, JOHN DEERE 4045AFM85, TIER 3 MARINE. 24 VDC STARTING & CONTROL. GENERATOR - MINIMUM 125 KW CONTINUOUS AT 105°C RISE, NEWAGE/STAMFORD UCI274E.
GEN #3	ENGINE - 99 HP, 65 EKW PRIME, JOHN DEERE 4045TFM85, TIER 3 MARINE. 24 VDC STARTING & CONTROL. GENERATOR - MINIMUM 90 KW CONTINUOUS AT 105°C RISE, NEWAGE/STAMFORD UCI274C.



REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023





ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

1	CHANGED CONTROL CONDUCTOR SHIELDED PAIR COUNT PER NEW ENGINE MONITORING	8/15/23	BCG
REV.	DESCRIPTION	DATE	BY
 ALASKA ENERGY AUTHORITY			
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: WIREWAY PLAN, BUILDING SECTION, & DETAILS			
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100		DRAWN BY: JTD DESIGNED BY: CWV/BCG FILE NAME: NELS PP E2-E5 PROJECT NUMBER:	SCALE: AS NOTED DATE: 8/30/23 SHEET: E3.1






NOTE:  
CENTER OPENING IN BACK OF FEEDER/VFD SECTION OVER TWO STEEL NIPPLES SHOP WELDED IN WALL FOR FEEDER CABLE ENTRANCE. SEE DETAIL 9/E3.3.



GENERAL NOTE:  
WALL ELEVATIONS SHOWN PRIMARILY FOR GENERAL LAYOUT OF MAJOR RACEWAY, EQUIPMENT, AND DEVICES REQUIRING REGULAR ACCESS FOR NORMAL PLANT OPERATIONS. ALL EQUIPMENT, DEVICES & INSTRUMENTATION CIRCUITS NOT SHOWN FOR CLARITY. SEE PLANS & DETAILS FOR COMPLETE ELECTRICAL INSTALLATIONS.




ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: ELEVATIONS & DETAILS		
DRAWN BY: JTD	DESIGNED BY: CWV/BCG	SCALE: AS NOTED
FILE NAME: NELS PP E2-E5	PROJECT NUMBER:	SHEET: E3.2
P.O. 111405, Anchorage, AK 99511 (907)349-0100		






**1** BACK WALL EXTERIOR ELEVATION  
3/8"=1'-0"




**2** RADIATOR POWER CONNECTION  
3/4"=1'-0"




**3** RADIATOR TEMPERATURE TRANSMITTER  
3/4"=1'-0"

**RADIATOR SHOP/ON-SITE NOTES:**

- 1) DURING SHOP FABRICATION INSTALL ALL DEVICES AND RACEWAYS AS INDICATED.
- 2) AS PART OF ON-SITE WORK, IF RADIATORS ARE REMOVED FOR SHIPPING DISCONNECT LIQUID TIGHT FLEXES AND SEAL ENDS. COIL AND SECURE CONDUCTORS AND FLEXES FOR SHIPPING.
- 3) AS PART OF ON-SITE WORK REINSTALL AS INDICATED.




**4** TYPICAL INTERIOR DEVICE MOUNTING  
NO SCALE




**5** TYP ENCLOSURE CONNECTION  
NO SCALE

**NOTES:**

- 1) THIS DETAIL APPLIES TO CONNECTIONS TO WIREWAY, GENERATOR ENCLOSURES, SWITCHGEAR, AND PANELS.
- 2) AT A MINIMUM INSTALL GROUNDING BUSHING ON ALL GENERATOR POWER CONDUIT, COMMUNITY FEEDER CONDUIT, STATION SERVICE FEEDERS, AND WHERE OTHERWISE INDICATED OR REQUIRED. BOND GROUNDING BUSHING TO EQUIPMENT GROUNDING CONDUCTOR.
- 3) INSTALL PLASTIC BUSHING WHERE GROUNDING BUSHING IS NOT REQUIRED.
- 4) ON GENERATOR ENCLOSURES PROTECT CABLES FROM WEAR BY INSTALLING 2 LAYERS OF HEAVY WALL HEAT SHRINK. BASE LAYER 12" LONG & SECOND LAYER 8" LONG, CENTERED IN CONNECTOR.



**6** ENGINE WIRING J-BOX SUPPORT  
NO SCALE



**7** STATION SERVICE TRANSFORMER SUPPORT  
NO SCALE

NOTE: UPON COMPLETION OF CIRCUIT TESTING PACK GRC NIPPLE THROUGH WALL WITH DUCT SEAL.


**INTERIOR**

GRC NIPPLE CUT TO LENGTH, SEE NOTE 1  
4"-SQUARE BOX, FASTEN TO WALL WITH #10 SHEET METAL SCREWS  
LOCKNUT & BUSHING, TYP(2)


**EXTERIOR**

WEATHERPROOF BELL BOX, SEAL TO WALL WITH POLYURETHANE CAULKING ALL AROUND

**8** TYP EXTERIOR WALL-MOUNT DEVICE  
NO SCALE



**9** FEEDER ENTRANCE DETAIL  
1"=1'-0"



**10** TYP CONDUIT WALL PENETRATION  
NO SCALE

**FEEDER SHOP/ON-SITE NOTES:**

- 1) DURING SHOP FABRICATION INSTALL TEMPORARY FEEDER CABLES THROUGH ONE NIPPLE AS SHOWN. SPARE NIPPLE TO REMAIN CAPPED.
- 2) ROUTE TEMPORARY CABLES TO LOAD BANK FOR TESTING. AFTER TESTING INSTALL THREADED CAP ON EXTERIOR END OF NIPPLE.
- 3) INSTALL FEEDER TO TRANSFORMER AS PART OF ON-SITE WORK, SEE SHEET E1.3 FOR CONTINUATION.
- 4) UPON COMPLETION OF TESTING PACK GRC NIPPLES THROUGH WALL WITH DUCT SEAL.

NOTE: UPON COMPLETION OF CIRCUIT TESTING PACK GRC NIPPLE THROUGH WALL WITH DUCT SEAL.

**INTERIOR**

SEAL TO WALL WITH POLYURETHANE CAULKING ALL AROUND INSIDE & OUT

**EXTERIOR**

HOLE SAW OPENING THROUGH WALL

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.

ISSUED FOR  
CONSTRUCTION  
MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: ELEVATIONS & DETAILS		
DRAWN BY: JTD	SCALE: AS NOTED	
DESIGNED BY: CWV/BCG	DATE: 5/30/23	
FILE NAME: NELS PP E2-E5	SHEET:	E3.3
PROJECT NUMBER:		

**Gray Stassel Engineering, Inc.**  
P.O. 111405, Anchorage, AK 99511 (907)349-0100









1  
E4.2  
STATION SERVICE PLAN  
3/8"=1'-0"


STATION SERVICE GENERAL NOTES:

- 1) ALL WIRING RUNS 2#12, #12G UNLESS SPECIFICALLY NOTED OTHERWISE.
- 2) MOUNT ALARMS HORNS WITH TOP AT 9'-0" AFF TO MATCH EXTERIOR LIGHTS, SEE SHEET E4.1
- 3) SEE SHEETS E7.1-E7.4 FOR DAY TANK AND WATER INDICATION PANEL DESIGN AND WIRING TERMINATIONS. ALL ACCESSORIES NOT SHOWN ON PLANS. SEE LOGIC DIAGRAMS FOR ADDITIONAL DETAIL.
- 4) SEE SWITCHGEAR SHOP DRAWINGS FOR TERMINATION OF ALL POWER AND CONTROL WIRING.
- 5) NOT USED.
- 6) ROUTE RADIATOR VFD POWER CONDUCTORS IN SEPARATE EXTERIOR CONDUIT, SEE ELEVATION 1/E3.3. DO NOT ROUTE IN WIREWAY. NOTE THAT CONDUCTORS ARE OVSIZED FOR 80% DE-RATE AND PROVIDED WITH 15A BREAKER IN SWITCHGEAR.
- 7) ROUTE BATTERY CABLES TO FRONT OF SKID SUPPORTED WITH CUSHIONED CLAMPS, SEE SHEET M3.4. ROUTE FROM SKID DIRECTLY UNDER FUEL HOSES TO WALL AND TYWRAP CABLES TO USED OIL PIPE ALONG WALL, SEE DETAIL 2/E3.1. CUT TO PROVIDE 6"± SERVICE LOOP FOR FINAL TERMINATION ON BATTERIES.
- 8) MOUNT BATTERY CHARGER TO WALL ON SHALLOW STRUT AND INSTALL BATTERIES IN RACK ON FLOOR BELOW, SEE ELEVATION 1/E3.2.


STATION SERVICE SHOP/ON-SITE NOTES:

- 1) DURING SHOP FABRICATION INSTALL WALL PENETRATION AND CONDUIT INTO DAY TANK PANEL. SEE ELEVATION 5/E3.2.
- 2) AS PART OF ON-SITE WORK INSTALL CONDUIT AND CONDUCTORS TO INTERMEDIATE TANK, SEE SHEET E1.6.
- 3) DURING SHOP FABRICATION INSTALL CEILING MOUNTED BOX ADJACENT TO DAMPER ACTUATOR AND TEMPORARILY CONNECT DAMPER TO VERIFY OPERATION.
- 4) AS PART OF ON-SITE WORK INSTALL CONDUIT AND CONDUCTORS TO DAMPER ACTUATOR. SEE SHEET M7.
- 5) EXISTING INTERMEDIATE TANK CONTROL PANEL SALVAGED FROM OLD INTERMEDIATE TANK AND INSTALLED IN MODULE AS PART OF ON-SITE WORK. SEE SHEET E1.2 FOR EXISTING LOCATION OF PANEL. SEE WALL ELEVATION 3/E3.2 FOR NEW LOCATION AND MOUNTING.
- 6) SEE ORIGINAL BULK FUEL UPGRADE PROJECT SHEETS E6-E9 FOR PANEL DESIGN AND LOGIC. NOTE THAT THIS PANEL IS POWERED FROM THE TANK FARM CONTROL PANEL, NOT THE MODULE. INSTALL DECAL 71 ON FACE. SEE SHEET M1.2.
- 7) SEE SHEET E1.5 FOR RE-CONNECTION OF EXISTING RE-ROUTED ARMORED CABLE FROM TANK FARM.
- 8) ROUTE NEW CONDUCTORS TO NEW INTERMEDIATE TANK FLOAT SWITCH IN SAME RACEWAY AS DAY TANK CONTROL PANEL CONDUCTORS, SEE SHEET E1.3. CONNECT NEW SWITCH TO MATCH ORIGINAL TERMINATIONS IN PANEL AND VERIFY FUNCTION.


MAKE THE FOLLOWING SETTINGS ON DIGITAL THERMOSTAT:  
APPLICATION = 0 (INTERNAL SENSOR)  
OUTPUT 1 = 0 (COOL/0-10V)  
OUTPUT 2 = 0 (NOT USED)  
OUTPUT 3 = 0 (NOT USED)  
OUTPUT 3 ACTIVATION = 0 (100%)  
NSB VALUE = 3 (6°F)  
OUTPUT 1 MIN = 0 (0%)  
MAX SETPOINT = 90°F  
MIN SETPOINT = 50°F



3  
E4.2  
EXHAUST FAN WIRING DIAGRAM  
NO SCALE




2  
E4.2  
STATION SERVICE PANEL "SS"  
NO SCALE




4  
E4.2  
CUH-1 WIRING DIAGRAM  
NO SCALE


ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.

REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023



1	DELETED FLOW METER & ADDED CAT5e FROM PUMP P-HR1B	8/15/23	BCG
REV.	DESCRIPTION	DATE	BY
 ALASKA ENERGY AUTHORITY			
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: STATION SERVICE PLAN, DETAILS, & PANELBOARD			
DRAWN BY: JTD		SCALE: AS NOTED	
DESIGNED BY: CWV/BCG		DATE: 5/30/23	
FILE NAME: NELS PP E2-E5		SHEET:	
PROJECT NUMBER:		E4.2	





1  
E5

INSTRUMENTATION & DATA PLAN


3/8"=1'-0"

INSTRUMENTATION & DATA PLAN NOTES:

- RTD TEMPERATURE SENSOR PROVIDED WITH SWITCHGEAR. ROUTE #18 SHIELDED PAIR TO SWITCHGEAR MASTER SECTION. SEE DETAIL 3/E5 AND NOTE 10.
- INSTALL DSL MODEM AND INTERNET ROUTER ON TOP OF MASTER SECTION IN RACK OR CABINET. CONNECT MODEM TO ROUTER AND TO TELEPHONE LINE. CONNECT ROUTER TO ETHERNET SWITCH INSIDE MASTER SECTION. CONNECT BOTH TO 120VAC UPS. SEE NOTE 10 AND SHOP/ON SITE NOTES 1 AND 2.
- LOW COOLANT LEVEL ALARM SWITCH INSTALLED AT EXPANSION TANK, SEE MECHANICAL. CONNECT TO N.C. SWITCH (WHITE & RED) AND ROUTE 2#14 TO SWITCHGEAR MASTER SECTION. SEE NOTE 10.
- GLYCOL LEVEL SENSOR PROBE INSTALLED IN EXPANSION TANK, SEE MECHANICAL. ROUTE #18 SHIELDED PAIR TO SWITCHGEAR. SEE NOTE 10.
- INSTALL TEMP TRANSMITTER IN EACH RADIATOR, SEE DETAIL 3/E3.3. ROUTE #18 SHIELDED PAIR FROM EACH TO SWITCHGEAR VFD SECTION. SEE ELEVATION 1/E3.3 AND NOTE 10.
- INSTALL COOLANT RETURN TEMP TRANSMITTER IN PIPING MAIN WHERE SHOWN ON COOLING PIPING ISOMETRIC 1/M4.2. ROUTE #18 SHIELDED PAIR TO SWITCHGEAR MASTER SECTION, SEE NOTE 10.
- INSTALL ONE TEMP TRANSMITTER (SUPPLY) AND ONE PRESSURE TRANSMITTER FOR HEAT RECOVERY MONITORING WHERE SHOWN ON HEAT RECOVERY PIPING ISOMETRIC 2/M4.2. ROUTE #18 SHIELDED PAIR FROM EACH TO SWITCHGEAR MASTER SECTION. SEE NOTE 10.
- PUMP P-HR1B HAS INTERNAL MONITORING FOR FLOW RATE AND TEMPERATURE. INSTALL OWNER FURNISHED PUMP CIM CARD AND ROUTE CAT5e TO ETHERNET SWITCH IN MASTER SECTION. INSTALL IN SEPARATE DEDICATED RACEWAY OR WITH OTHER INSTRUMENT CABLES. DO NOT ROUTE WITH STATION SERVICE OR POWER CONDUCTORS.
- ROUTE 2#14 FROM BATTERY CHARGER ALARM CONTACTS TO ASSOCIATED SWITCHGEAR GENERATOR SECTION, SEE NOTE 10 AND WIRING DIAGRAM 2/E5.
- SEE SWITCHGEAR SHOP DRAWINGS FOR TERMINATION OF ALL INSTRUMENTATION AND DATA WIRING INCLUDING CONTROL POWER.
- ROUTE ENGINE-GENERATOR CONTROL CONDUCTORS TO SWITCHGEAR IN 10x10 WIREWAY WITH POWER CONDUCTORS. SEE DETAIL 2/E3.1, SHEET E6.3, AND NOTE 10.
- SEE SHEETS E7.1-E7.4 FOR DAY TANK AND WATER INDICATION CONTROL PANEL DESIGN AND WIRING TERMINATIONS. ALL ACCESSORIES NOT SHOWN ON PLANS. SEE LOGIC DIAGRAMS FOR ADDITIONAL DETAIL.
- ROUTE CAT5e CONDUCTORS FROM DAY TANK PANEL REMOTE I/O AND TANK LEVEL MONITOR TO ETHERNET SWITCH IN SWITCHGEAR MASTER SECTION. INSTALL IN SEPARATE DEDICATED RACEWAY. DO NOT ROUTE WITH STATION SERVICE OR POWER CONDUCTORS.
- ROUTE CAT5e FOR DATA AND 2#14 FOR GENERATOR SHUT DOWN FROM FIRE PANEL TO SWITCHGEAR MASTER SECTION, SEE SHEET FS1 AND NOTE 10. INSTALL IN SEPARATE DEDICATED RACEWAY, COLOR RED. DO NOT ROUTE WITH STATION SERVICE OR POWER CONDUCTORS.
- ROUTE CAT5e FROM RJ-45 JACK TO ETHERNET SWITCH IN MASTER SECTION. INSTALL IN SEPARATE DEDICATED RACEWAY. DO NOT ROUTE WITH STATION SERVICE OR POWER CONDUCTORS.

INSTRUMENTATION SHOP/ON-SITE NOTES:

- AS PART OF SHOP FABRICATION INSTALL ETHERNET SWITCH IN MASTER SECTION.
- AS PART OF ON-SITE WORK INSTALL STARLINK MODEM WITH ETHERNET ADAPTER IN BOTTOM OF MASTER SECTION. CONNECT MODEM TO ETHERNET SWITCH AND TO 120VAC UPS INSIDE MASTER SECTION. SEE NOTE 10.
- AS PART OF SHOP FABRICATION INSTALL WALL PENETRATION AND CONDUIT INTO DAY TANK PANEL. SEE ELEVATION 5/E3.2.
- AS PART OF ON-SITE WORK INSTALL CONDUIT AND CONDUCTORS TO INTERMEDIATE TANK, SEE SHEET E1.6.




NOTE: PRIOR TO ENERGIZING MAKE THE FOLLOWING SETTINGS ON CHARGER:

- AC LINE VOLTAGE SWITCH TO "115V".
- AUTO BOOST JUMPER TO "NORM".
- FLOAT VOLTAGE JUMPER TO "13.50/27.00" (FOR GEL CELL).
- BATTERY RANGE JUMPER TO "24V".

2  
E5

BATTERY CHARGER ALARM WIRING DIAGRAM

NO SCALE





3  
E5


AMBIENT AIR TEMP RTD TERMINATION

NO SCALE

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT EXCEPT AS SPECIFICALLY INDICATED IN THE SHOP/ON SITE NOTES.


2	CHANGED INTERNET SERVICE TO STARLINK	11/13/23	BCG
1	DELETED FLOW METER & HRR, ADDED CAT5e FROM PUMP P-HR1B, SEE NOTES 7 & 8	8/15/23	BCG
REV.	DESCRIPTION	DATE	BY
 ALASKA ENERGY AUTHORITY			
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: INSTRUMENTATION & DATA PLAN & DETAILS			
 Gray Stassel Engineering, Inc.		DRAWN BY: JTD DESIGNED BY: CWV/BCG FILE NAME: NELS PP E2-E5 PROJECT NUMBER:	SCALE: AS NOTED DATE: 5/30/23 SHEET: E5
P.O. 111405, Anchorage, AK 99511 (907)349-0100			

REV#1  
ISSUED FOR  
CONSTRUCTION  
NOV 2023







Demand Control Table (PLC)				
Demand Control	Generator(s) On Line	On-line kW (Overload)	Level Increase	Level Decrease
Level 1	#3	65	55	---
Level 2	#1 or #2	100	90	45
Level 3	#3 & #1 or #2	165	145	80
Level 4	All	265	---	125
Note : Gen #1 & #2 are equal capacity. Manually select lead unit.				
Engine-Generator Alarm Settings (Easygen - EZGN)				
Function	Normal Range		Alarm	Shut Down
Overspeed	1795-1805		----	1900 RPM
Oil Pressure	30-50 PSI		14.5 PSI	10 PSI
Air Filter Vacuum	1-10" H2O		15" H2O	20" H2O
Coolant Temp.	180-200°F		210°F	215°F
Exhaust Temp.	500-850°F		900°F	-----
Under Frequency	59.5-60.5 Hz		----	58.2 Hz
Over Frequency	59.5-60.5 Hz		----	61.8 Hz
Under Voltage	470-490 V		----	432 V
Over Voltage	470-490 V		----	528 V
Reverse Power	0		----	10%
Generator Breaker Settings (Easygen - EZGN)				
Function				Setting
Gen #1 Breaker Trip Setpoint (EZGN Rated Current)				200 A
Gen #2 Breaker Trip Setpoint (EZGN Rated Current)				200 A
Gen #3 Breaker Trip Setpoint (EZGN Rated Current)				150 A
Gen Breaker Level 1 (100%) Time Over Current				3 sec.
Gen Breaker Level 2 (120%) Time Over Current				1 sec.
Gen Breaker Level 3 (250%) Time Over Current				0.4 sec.
Feeder Breaker Settings (Feeder Protection Relay - FPR)				
Function (Note: Element 1 is the only active element)				Setting
T.O.C. Trip Pickup (amps) Note: 5A = 100% of CT rating				5.0
T.O.C. Curve Selection				U4
T.O.C. Time Dial				5.00
E.M Reset delay (Y/N)				N
Constant Time Adder (seconds)				0.00
Minimum Response Time (seconds)				0.00
Maximum Phase T.O.C. Torque Control				1
Radiator VFD Settings				
Function				Setting
Min PID Feedback				20
Max PID Feedback				240
rSL (Wake UP Threshold)				1
PID Reference Temperature				175°F
Proportional Gain				0.93
Integral Gain				0.3
Derivative				0
Minimum Speed				10 Hz.
Low Speed Timeout				10 sec.
Loss of Phase				Ignore



1 SWITCHGEAR ENCLOSURE LAYOUT  
E6.1 NO SCALE



2 COMMUNICATION SCHEMATIC  
E6.1 NO SCALE



EASYGEN INTERFACE CONTROLS

3 GENSET CONTROL (EZGN) INTERFACE CONTROLS  
E6.1 NO SCALE

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023







1	CHANGED COMM SCHEMATIC TO MATCH SWITCHGEAR SHOP DRAWINGS & ADDED P-HR1B	8/15/23	BCG
REV.	DESCRIPTION	DATE	BY
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: SWITCHGEAR ENCLOSURE LAYOUT, SETTING TABLE, & DETAILS			
DRAWN BY: JTD		SCALE: NO SCALE	
DESIGNED BY: CWV/BCG		DATE: 4/10/23	
FILE NAME: NELS PP E6		SHEET: E6.1	
PROJECT NUMBER:			






- 1) PERMANENTLY AFFIX ARC FLASH LABELS TO EACH SECTION WITH 480V POWER AS INDICATED.
- 2) SCALED PDF IMAGES OF THESE LABELS WILL BE FURNISHED TO THE FABRICATOR UPON REQUEST.




1	REVISE VFD TO MATCH SHOP AS BUILT (DELETE ENABLE TIMER)	11/13/23	BCG
REV.	DESCRIPTION	DATE	BY
 <p>ALASKA ENERGY AUTHORITY</p>			
PROJECT:			
NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE:			
SWITCHGEAR ONE-LINE & SCHEMATICS			
 <p><b>Gray Stassel Engineering, Inc.</b></p>		DRAWN BY: JTD DESIGNED BY: CWB/BCG FILE NAME: NELS PP E6 PROJECT NUMBER:	SCALE: NO SCALE DATE: 4/10/23 SHEET: <b>E6.2</b>
P.O. 111405, Anchorage, AK 99511 (907)349-0100			







1 JUNCTION BOX FRONT PANEL LAYOUT  
E6.3 NO SCALE




2 JUNCTION BOX SUB PANEL LAYOUT  
E6.3 NO SCALE



4 CIRCUIT BREAKER CONNECTIONS  
E6.3 NO SCALE



3 TERMINAL STRIP CONNECTIONS  
E6.3 NO SCALE



5 TERMINAL STRIP CONNECTIONS  
E6.3 NO SCALE

BILL OF MATERIALS			
TAG	MANUFACTURER	MODEL	DESCRIPTION
21 PIN	JOHN DEERE OR	DEUTZ	21 PIN CUSTOMER CONNECTION ASSY
CBR-A/B/C	ALLEN-BRADLEY	1489-M1-C010	RAIL MOUNT CIRCUIT BREAKER, 1P, 1A
CBR-1	ALLEN-BRADLEY	1489-M1-C050	RAIL MOUNT CIRCUIT BREAKER, 1P, 5A
DG	JOHN DEERE	DG-14	DIAGNOSTIC GAUGE WITH HARNESS
ENCL.	PROGRAMMED FOR	MARINE TIER 3 WITH UNIQUE JOHN DEERE FAULT CODE	
SS	HOFFMAN	A20H20ALP	20x20x8" NEMA 12
SW-TR	HOFFMAN	A20P20	BACK PANEL
	JOHN DEERE	AT145341	STARTER AUXILIARY SOLENOID, 24V
	ALLEN-BRADLEY	194L-A12-225-2	CHANGEOVER SWITCH, 12A, 2P
	ALLEN-BRADLEY	194L-HE-4A-175	90 DEGREE I-O HANDLE
TB-1	IDEC	BNH15LW	15A DIN RAIL-MOUNT TERMINAL BLOCK
TB-2	IDEC	BNH50W	50A DIN RAIL-MOUNT TERMINAL BLOCK
VR	BASLER	DECS-150 5NS1V1N1S	DIGITAL VOLTAGE REGULATOR


BRAND SPECIFIC NOTE: SPECIFIC PARTS MANUFACTURER AND MODEL SELECTED NOT ONLY TO MEET PERFORMANCE FUNCTION BUT ALSO TO COORDINATE AND INTERFACE WITH OTHER DEVICES AND SYSTEMS. APPROVED EQUAL SUBSTITUTIONS WILL BE ALLOWED ONLY BY ENGINEER'S APPROVAL. TO OBTAIN APPROVAL, SUBMITTALS MUST CLEARLY DEMONSTRATE HOW SUBSTITUTE ITEM MEETS OR EXCEEDS SPECIFIED ITEM QUALITY AND PERFORMANCE CHARACTERISTICS AND ALSO COMPLIES WITH MECHANICAL AND/OR ELECTRICAL CONNECTIONS AND PHYSICAL LAYOUT REQUIREMENTS.

#### SHOP FABRICATION NOTES:


- PROVIDE ASSEMBLY WITH ALL DEVICES AND WIRING INDICATED.
- INSTALL IN A NEMA 12 ENCLOSURE WITH MOUNTING FLANGES AT BACK, A MIN 14 GAUGE INTERIOR BACK PANEL AND HINGED LOCKABLE DOOR. SIZE AS INDICATED.
- PROVIDE DIN RAIL, TERMINAL END PLATES, TERMINAL END STOPS, TERMINAL DUST COVERS AND OTHER MISCELLANEOUS HARDWARE AS REQUIRED TO MATCH TERMINALS. LABEL ALL TERMINALS EXACTLY AS INDICATED ON THE DETAILS.
- ALL WIRE #14AWG EXCEPT WHERE SPECIFICALLY INDICATED OTHERWISE. LABEL BOTH ENDS OF ALL JUMPERS WITH THE ENGINE PANEL TERMINAL NUMBER.
- PROVIDE MECHANICAL GROUND LUGS FASTENED TO BACK PANEL AND GROUNDED TO ENGINE-GENERATOR. GROUND ALL SHIELD DRAIN WIRES TO LUGS AT BACK PANEL ONLY.
- PROVIDE WIRING HARNESSES FOR CONNECTION TO GENERATOR AND TO ENGINE. INSTALL WIRES IN LIQUID TIGHT FLEX OR FLEXIBLE PLASTIC WIRE LOOM AND PROVIDE SERVICE LOOPS IN ACCORDANCE WITH SPECIFICATIONS.
- SHOP TEST EACH NEW ENGINE-GENERATOR WITH ASSOCIATED JUNCTION BOX PERMANENTLY CONNECTED. UPON COMPLETION OF TESTING, COIL WIRING HARNESSES AND SECURE JUNCTION BOX TO GENERATOR FOR SHIPPING.

#### FIELD INSTALLATION NOTES:

- PERFORM ALL FIELD WIRING IN ACCORDANCE WITH SPECIFICATIONS. LABEL BOTH ENDS OF ALL FIELD WIRING WITH THE ENGINE PANEL TERMINAL NUMBER.
- ON SHIELDED CONDUCTORS GROUND ALL SHIELD DRAIN WIRES AT ENGINE J-BOX ONLY. CLIP DRAIN WIRES AT OPPOSITE ENDS.



6 STARTER AUX SOLENOID SS WIRING  
E6.3 NO SCALE



7 EXHAUST RTD CONNECTOR  
E6.3 NO SCALE

8 TEST-IDLE/RUN-RATED SWITCH SW-TR WIRING  
E6.3 NO SCALE

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

2	DELETED EXHAUST RTD & VACUUM SENSOR PER NEW J1939 ENGINE MONITORING	8/15/23	BCG
1	UPDATED TO ADD 21 PIN CUSTOMER CONNECTION	5/30/23	BCG
REV.	DESCRIPTION	DATE	BY
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE			
TITLE: 24VDC ENGINE WIRING JUNCTION BOX			
		DRAWN BY: JTD	SCALE: NO SCALE
		DESIGNED BY: CWV/BCG	DATE: 4/10/23
		FILE NAME: NELS PP E6	SHEET: E6.3
		PROJECT NUMBER:	

REV#1  
ISSUED FOR  
CONSTRUCTION  
AUGUST 2023









**Gray  
Stassel  
Engineering, Inc.**  
P.O. 111405, Anchorage, AK 99511, (907)249-0100






1 FRONT PANEL LAYOUT  
E7.2 NO SCALE




2 SUB PANEL LAYOUT  
E7.2 NO SCALE



NOTES:

1. INSTALL TERMINAL STRIP TB-2 AND ETHERNET PATCH PANEL PP-1 ON VERTICAL DIN RAIL AS SHOWN. LOCATE TERMINAL STRIP IN THE UPPER RIGHT CORNER OF PANEL TO ACCOMMODATE CONDUCTOR ENTRY THROUGH RIGHT SIDE OF PANEL, SEE SUB-PANEL LAYOUT.

3 TB-2 TERM STRIP LAYOUT  
E7.2 NO SCALE



NOTES:

- 1) INSTALL TERMINAL STRIP TB-1 ON HORIZONTAL DIN RAIL AS SHOWN. LOCATE TERMINAL STRIP BELOW PANEL DEVICES TO ACCOMMODATE CONDUCTOR ROUTING FROM CONDUITS CONNECTING TO BOTTOM OF PANEL, SEE SUB-PANEL LAYOUT.
- 2) IN ADDITION TO THE TERMINAL STRIPS SHOWN, PROVIDE 6 EACH 35A SCREW TERMINAL GROUNDING BUS.

4 TB-1 TERMINAL STRIP LAYOUT  
E7.2 NO SCALE

ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE EXCEPT FOR TERMINATION AT THE PANEL OF EXTERIOR INTERMEDIATE TANK FIELD CONDUCTORS WHICH IS INCLUDED IN THE ON SITE WORK.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: DAY TANK CONTROL PANEL LAYOUT & TERMINAL STRIPS		
	DRAWN BY: BCG/JTD	SCALE: AS NOTED
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
P.O. 111405, Anchorage, AK 99511 (907)349-0100	FILE NAME: NELS PP E7	SHEET: E7.2
	PROJECT NUMBER:	



PANEL NOTES:

- 1) PROVIDE COMPLETE LISTED PANEL ASSEMBLY WITH ALL DEVICES INDICATED IN LOGIC DIAGRAM EXCEPT FOR FIELD DEVICES. INSTALL IN A NEMA 12 ENCLOSURE WITH 4 EACH INTEGRAL MOUNTING LUGS AT BACK. SEE SHEET E7.2 FOR PANEL LAYOUT DETAILS.
- 2) USE MIN #12 WIRE FOR ALL CIRCUITS UP TO FIRST IN-LINE PANEL BREAKERS (FOR 20A FEED). USE MIN #16 AWG ON ALL 5 AMP CIRCUITS AND MIN #14 AWG WIRE ON ALL 15A CIRCUITS. TAG EACH END OF ALL JUMPERS WITH DEVICE OR TERMINATION DESIGNATOR OF LANDING OF OPPOSITE END OF JUMPER (REVERSE ADDRESS).
- 3) LABEL ALL PANEL DEVICES ON BASE OR BACK PANEL ADJACENT TO ITEM. LABEL REMOTE EQUIPMENT CONNECTIONS AT EACH TERMINAL BLOCK BY THE ITEM TITLE AS SHOWN ON THE FIELD SIDE OF THE TERMINAL STRIP DRAWING. PROVIDE BEVELED EDGE WHITE CORE NAMEPLATES AS SHOWN ON THE PANEL FACE LAYOUT AND SECURE TO PANEL FACE WITH A MINIMUM OF TWO STAINLESS STEEL MOUNTING SCREWS, COLOR AS INDICATED.
- 4) BENCH TEST COMPLETED UNIT. PROVIDE MIN 48 HOURS NOTICE TO ENGINEER TO SCHEDULE OBSERVATION OF BENCH TEST. PROVIDE SWITCHES AND LAMPS TO SIMULATE OPERATION OF ALL FIELD DEVICES.
- 5) DEVICES AND WIRING NOTED AS "FIELD" AND SHOWN WITH DASHED LINES WILL BE FIELD INSTALLED AND ARE NOT PART OF THE PANEL SHOP FABRICATION. FOR BENCH TEST, PROVIDE TEMPORARY DEVICES AND WIRING AS REQUIRED TO SIMULATE FIELD DEVICES.
- 6) POWER TO PANEL PROVIDED FROM DEDICATED 20A 2-POLE CIRCUIT BREAKER IN LISTED LOAD CENTER. SEE FIELD INSTALLATION NOTE #3.

FIELD INSTALLATION NOTES:


- 1) SEE MECHANICAL FOR DAY TANK INSTALLATION & PIPING. INSTALL CONTROL PANEL & FIELD DEVICES AS INDICATED TO PROVIDE REDUNDANT HIGH & LOW LIMIT CONTROLS & OVERFILL PROTECTION.
- 2) FIELD WIRING TO FLOAT SWITCHES, SOLENOID VALVES, ACTUATOR VALVE, & ALARM HORN #14 AWG. ALL OTHER FIELD WIRING #12 AWG. LABEL BOTH ENDS OF ALL CONDUCTORS WITH CONTROL PANEL TERMINAL BLOCK TERMINATION NUMBERS. WHEN NOT IN CONDUIT, MAKE JACKETED COM CABLE ENCLOSURE ENTRIES WITH CABLE GLAND CONNECTORS.
- 3) PERFORM ALL FIELD WIRING IN ACCORDANCE WITH ELECTRICAL SPECIFICATIONS ON SHEET E2. PROVIDE POWER TO DAY TANK PANEL FROM DEDICATED 20A 2-POLE CIRCUIT BREAKER IN STATION SERVICE PANELBOARD.
- 4) VERIFY THAT ALL DAY TANK FLOAT SWITCHES ARE ORIENTED FOR N.C. (OPEN ON RISE) OPERATION PRIOR TO INSTALLATION. ALL FLOATS SHOWN ON LOGIC DIAGRAM WITH TANK AT FULL (PUMP STOP) LEVEL. VERIFY THAT THE HOPPER FLOAT SWITCH IS ORIENTED FOR N.O. (CLOSE ON RISE) OPERATION.
- 5) FILL PUMP CAVITIES WITH LUBE OIL PRIOR TO INITIAL OPERATION. VERIFY PROPER ROTATION OF PUMPS. PRIME SYSTEM WITH HAND PRIMING PUMP PRIOR TO BEGINNING DAY TANK FILL.
- 6) FIELD TEST COMPLETED UNIT TO VERIFY ALL CONTROL AND ALARM FUNCTIONS. MANIPULATE FLOAT SWITCHES BY REACHING IN THROUGH ADJACENT 4" BUNG. TEMPORARILY SET TIMING RELAY TO 30 SECONDS TO VERIFY TIME-OUT AND RESET FUNCTIONS.
- 7) SET TIMING RELAY TIME DELAY TO 30 MINUTES (APPROX. 55 GALS. REQUIRED FROM PUMP START TO PUMP STOP LEVEL @ APPROX. 4 GPM). ON THE INITIAL TANK FILL, THE PUMP TEST/RESET BUTTON MAY HAVE TO BE MANUALLY RESET IN ORDER TO GET THE FUEL LEVEL TO WITHIN THE NORMAL OPERATING RANGE. SEE SEQUENCE OF OPERATIONS.

DAY TANK FILL SEQUENCE OF OPERATIONS:


- 1) WHEN THE DAY TANK CIRCUIT BREAKER AND CONTROL POWER SWITCH ARE CLOSED, THE POWER LIGHT IS ON AND POWER IS PROVIDED TO THE REMOTE ACTUATOR VALVE HEATER/OPEN LIGHT CIRCUIT.
- 2) WHEN THE DAY TANK IS NOT CALLING FOR FUEL, POWER IS PROVIDED TO THE REMOTE ACTUATOR VALVE CLOSE CIRCUIT. WHEN THE ACTUATOR IS IN THE FULLY CLOSED POSITION, THE CLOSING CIRCUIT IS BROKEN BY INTERNAL ACTUATOR LIMIT SWITCH #2 AND THE REMOTE ACTUATOR VALVE "OPEN" LIGHT IS OFF.
- 3) NORMAL FILL OPERATION – WHEN THE FUEL LEVEL DROPS TO THE "PUMP START" SWITCH, THE TIMER IS STARTED, THE N.C. DAY TANK SOLENOID VALVE OPENS, THE REMOTE ACTUATOR VALVE OPENS & THE VALVE "OPEN" LIGHT TURNS ON, THE DAY TANK PUMP IS ENERGIZED, THE PUMP "ON" LIGHT TURNS ON, AND THE USED OIL BLENDER RUN SIGNAL DRY CONTACT CLOSSES. WHEN THE ACTUATOR IS IN THE FULLY OPEN POSITION, THE OPENING CIRCUIT IS BROKEN BY INTERNAL ACTUATOR LIMIT SWITCH #7 AND THE REMOTE ACTUATOR VALVE "OPEN" LIGHT REMAINS ON. WHEN FUEL REACHES THE "PUMP STOP" FLOAT SWITCH BEFORE THE TIMER TIMES-OUT, THE TIMER IS RESET, THE N.C. DAY TANK SOLENOID VALVE AND REMOTE ACTUATOR VALVE CLOSE, THE REMOTE ACTUATOR VALVE "OPEN" LIGHT TURNS OFF, THE PUMP DE-ENERGIZES, THE PUMP "ON" LIGHT TURNS OFF, AND THE USED OIL BLENDER RUN SIGNAL DRY CONTACT OPENS.
- 4) TIMER OPERATION – IF THE TIMER TIMES-OUT THE N.C. DAY TANK SOLENOID VALVE AND REMOTE ACTUATOR VALVE CLOSE, THE REMOTE ACTUATOR VALVE "OPEN" LIGHT TURNS OFF, THE PUMP DE-ENERGIZES, THE PUMP "ON" LIGHT TURNS OFF, THE USED OIL BLENDER RUN SIGNAL DRY CONTACT OPENS, THE "TIME-OUT" ALARM LIGHT TURNS ON, AND THE TIME-OUT ALARM HORN SOUNDS. PRESSING THE "TIME-OUT ALARM SILENCE / PUMP RESTART" BUTTON RESETS THE TIMER, SILENCES THE ALARM HORN, AND STARTS THE NORMAL FILL OPERATION. SEE FIELD INSTALLATION NOTES FOR TIMER SETTING.
- 5) OVERFILL FUEL LEVEL – IF THE TANK OVERFILLS AND THE FUEL LEVEL REACHES THE "OVERFILL" FLOAT SWITCH, THE N.O. DAY TANK SOLENOID VALVE CLOSSES, THE "OVERFILL LEVEL" ALARM LIGHT TURNS ON, THE N.C. DAY TANK SOLENOID VALVE AND REMOTE ACTUATOR VALVE CLOSE, THE VALVE "OPEN" LIGHT TURNS OFF, THE PUMP DE-ENERGIZES, THE PUMP "ON" LIGHT TURNS OFF, THE USED OIL BLENDER RUN SIGNAL DRY CONTACT OPENS, THE "OVERFILL LEVEL" ALARM LIGHT TURNS ON, AND THE ALARM HORN SOUNDS. PRESSING THE LEVEL ALARM HORN "SILENCE" BUTTON SILENCES THE ALARM HORN WHILE LEAVING THE "OVERFILL LEVEL" ALARM LIGHT ON. WHEN THE FUEL LEVEL FALLS BELOW THE "OVERFILL" FLOAT SWITCH, THE "OVERFILL LEVEL" ALARM LIGHT TURNS OFF, THE N.O. DAY TANK SOLENOID VALVE OPENS AND THE ALARM HORN TURNS OFF (IF NOT PREVIOUSLY SILENCED). WHEN THE FUEL LEVEL REACHES THE "PUMP START" FLOAT SWITCH, THE NORMAL FILL OPERATION IS REPEATED.
- 6) LOW FUEL LEVEL – IF THE FUEL LEVEL FALLS BELOW THE "LOW ALARM" FLOAT SWITCH, THE "LOW FUEL LEVEL" ALARM LIGHT TURNS ON, THE ENGINE RUN-DRY PREVENTION DRY CONTACT OPENS, AND THE ALARM HORN SOUNDS. THE LEVEL ALARM HORN "SILENCE" BUTTON SILENCES THE ALARM HORN WHILE LEAVING THE "LOW FUEL LEVEL" ALARM LIGHT ON. WHEN THE FUEL LEVEL RISES ABOVE THE "LOW ALARM" FLOAT SWITCH THE "LOW FUEL LEVEL" ALARM LIGHT TURNS OFF, THE ENGINE RUN-DRY PREVENTION DRY CONTACT CLOSSES, AND THE ALARM HORN TURNS OFF (IF NOT PREVIOUSLY SILENCED).
- 7) PUMP & HORN TEST – MOMENTARY CONTACT BUTTONS ARE PROVIDED TO TEST FUNCTION OF THE DAY TANK PUMP AND ALARM HORN. PRESSING THE "PUSH TO TEST DAY TANK PUMP" BUTTON STARTS THE TIMER, MOMENTARILY OPENS THE N.C. DAY TANK SOLENOID VALVE & ACTUATED BALL VALVE, ENERGIZES THE DAY TANK PUMP, TURNS ON THE DAY TANK PUMP "RUNNING" LIGHT AND CLOSSES THE USED OIL BLENDER RUN SIGNAL DRY CONTACT. THE "PUSH TO TEST DAY TANK PUMP" BUTTON IS LOCKED OUT IF THE DAY TANK IS AT THE OVERFILL LEVEL. PRESSING THE "PUSH TO TEST DAY TANK ALARM" BUTTON MOMENTARILY ENERGIZES THE ALARM HORN/STROBE.

USED OIL BLENDER SYSTEM SEQUENCE OF OPERATIONS:


- 1) WHEN THE BLENDER CIRCUIT BREAKER AND CONTROL POWER SWITCH ARE CLOSED; THE GREEN POWER LIGHT IS ON AND POWER IS PROVIDED TO ALL CONTROL DEVICES.
- 2) NORMAL OPERATION – WHENEVER THE DAY TANK FILL SEQUENCE IS INITIATED, BOTH THE DIESEL CIRCULATING PUMP P-DF2 AND THE USED OIL INJECTION PUMP P-U02 RUN AND THE ASSOCIATED GREEN PUMP RUNNING LIGHTS ARE ON.
- 3) PLUGGED FILTER – IF THE DIFFERENTIAL PRESSURE ACROSS A FILTER REACHES THE ALARM SETPOINT, BOTH PUMPS STOP RUNNING AND THE RED FILTER PLUGGED LIGHT FOR THE ASSOCIATED FILTER TURNS ON. THE ALARM LATCHES AND THE SYSTEM WILL NOT OPERATE UNTIL THE PROBLEM IS CORRECTED. AFTER THE FILTER ELEMENT HAS BEEN CHANGED THE BLACK RESET BUTTON MUST BE PRESSED TO RESUME NORMAL OPERATION.
- 4) HOPPER LOW OIL LEVEL – WHEN THE OIL LEVEL FALLS BELOW THE LOW LEVEL FLOAT SWITCH, USED OIL INJECTION PUMP P-U02 STOPS RUNNING AND THE AMBER HOPPER LOW OIL LEVEL LIGHT TURNS ON. PUMP P-U02 WILL NOT OPERATE UNTIL THE USED OIL LEVEL IN THE HOPPER RISES ABOVE THE LOW LEVEL. RESET IS NOT REQUIRED.



1 TANK LEVEL MONITOR (TLM) CONSOLE CONNECTIONS



2 DAY TANK CONTROL PANEL & DEVICE INSTALLATION



3 ETHERNET POINT I/O CONNECTIONS


ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.

ISSUED FOR CONSTRUCTION MAY 2023




PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: DAY TANK CONTROL PANEL NOTES, SEQUENCE OF OPERATIONS & INTERCONNECT DETAILS		
	DRAWN BY: BCG/JTD	SCALE: AS NOTED
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
	FILE NAME: NELS PP E7	SHEET: E7.3
P.O. 111405, Anchorage, AK 99511 (907)349-0100 PROJECT NUMBER:		






1 PANEL WIRING DIAGRAM  
E7.4 NO SCALE



2 FRONT PANEL LAYOUT  
E7.4 NO SCALE




3 SUB PANEL LAYOUT  
E7.4 NO SCALE

PANEL BILL OF MATERIALS				
TAG	QTY	MANUFACTURER	MODEL	DESCRIPTION
CBR-1	1	ALLEN-BRADLEY	1489-M1-C020	RAIL-MOUNT CIRCUIT BREAKER, 1 POLE, 2A
LNR	3	ALLEN-BRADLEY	800HORH2R	RED LED PILOT LIGHT, 12-130V, NEMA 4X
PS	1	PULS	CP5.241-S1	5A, 120VAC/24VDC POWER SUPPLY
R	3	ALLEN-BRADLEY	700HA32A1	2PDT RELAY
	3	ALLEN-BRADLEY	700HN100	8 PIN SOCKET BASE
TB	15	ALLEN-BRADLEY	1492CAM1L	35A, 600V, LARGE-HEAD SCREW TERMINALS

#### PANEL SHOP FABRICATION NOTES:


- FURNISH COMPLETE PANEL ASSEMBLY WITH ALL DEVICES INDICATED IN WIRING DIAGRAM AND BILL OF MATERIALS ALONG WITH ALL PANEL DEVICE ACCESSORIES, DIN RAIL, & HARDWARE REQUIRED FOR COMPLETE INSTALLATION.
- INSTALL IN A 16"x16"x8" NEMA 12 STEEL ENCLOSURE WITH INTEGRAL MOUNTING FLANGES AT BACK, A MIN 16 GAUGE INTERIOR BACK PANEL, AND HINGED DOOR. ENCLOSURE COLOR ANSI 61 GRAY AND BACK PANEL COLOR WHITE.
- PROVIDE BEVELED EDGE WHITE CORE NAMEPLATES, FACE COLOR AS INDICATED. SECURE TO PANEL FACE WITH A MINIMUM OF TWO MOUNTING SCREWS.
- CONNECT DEVICES WITH MANUFACTURER PROVIDED CABLES IN ACCORDANCE WITH INSTALLATION INSTRUCTIONS.



#### NOTES:

- INSTALL TERMINAL STRIP TB-1 HORIZONTALLY AS SHOWN. LOCATE TERMINAL STRIP BELOW WIRE TRAY TO ACCOMMODATE FIELD CONDUCTORS ENTERING BOTTOM OF PANEL, SEE SUB-PANEL LAYOUT.
- IN ADDITION TO THE TERMINAL STRIPS SHOWN, PROVIDE 2 EACH 60A SCREW TERMINAL GROUNDING BUS.

4 TERMINAL STRIP TB-1 LAYOUT  
E7.4 NO SCALE




5 FIELD WIRING SCHEMATIC  
E7.4 NO SCALE



#### NOTES:

- THREE EACH RACOR WATER DETECTION PROBE KITS, MODEL RK30880E, SHIPPED LOOSE WITH 3-FILTER BANK. NOT ALL KIT COMPONENTS USED THIS INSTALLATION. KEEP THREE EACH WATER DETECTION PROBE CABLES WITH MOLDED MALE CONNECTORS AND KEEP THREE EACH 3-WIRE CABLE BUNDLES WITH MOLDED FEMALE CONNECTORS. DISCARD THREE EACH PILOT LIGHTS AND DISCARD THREE EACH MOUNTING PANELS.
- PRIOR TO FLOODING SYSTEM WITH FUEL INSTALL WATER DETECTION PROBES IN EACH FILTER ACCORDING TO MANUFACTURER'S INSTRUCTIONS. ROUTE FACTORY LOOMED CABLES WITH MOLDED FEMALE CONNECTORS BACK TO WALL IN NEAT AND ORGANIZED FASHION FOR CONNECTION TO WIRE EXTENSION CONNECTORS. TYWRAP LOOM TO CONDUIT OR PIPING.
- FACTORY 3-WIRE CABLE BUNDLES FURNISHED WITH MOLDED MALE CONNECTORS. FIELD INSTALL IN 3/8" PLASTIC WIRE LOOM FROM CONNECTOR TO PANEL ENTRY AND ROUTE TO PANEL IN NEAT AND ORGANIZED FASHION. TYWRAP LOOM TO ADJACENT CONDUIT, PIPING, OR STRUT.


ISSUED FOR  
CONSTRUCTION  
MAY 2023



ALL WORK ON THIS SHEET WAS PERFORMED AS PART OF THE PRIOR MODULE ASSEMBLY CONTRACT AND IS SHOWN HERE FOR REFERENCE ONLY.


 ALASKA ENERGY AUTHORITY		
PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: DAY TANK FILTER WATER INDICATION PANEL		
 Gray Stassel Engineering, Inc. P.O. 111405, Anchorage, AK 99511 (907)349-0100	DRAWN BY: BCG/JTD	SCALE: AS NOTED
	DESIGNED BY: CWV/BCG	DATE: 5/30/23
FILE NAME: NELS PP E7	SHEET: E7.4	
	PROJECT NUMBER:	





1 TOURISM BUILDING ELECTRICAL PLAN  
E8 1/2"=1'-0"


2 STORAGE COMPOUND ELECTRICAL PLAN  
E8 3/16"=1'-0"



3 ICEHOUSE ELECTRICAL PLAN  
E8 3/16"=1'-0"

GENERAL NOTES:

- 1) SEE SHEET E1.2 FOR BUILDING LOCATIONS.
- 2) SEE MECHANICAL FOR EQUIPMENT INSTALLATION DETAILS IN EACH BUILDING.



4 CUH WIRING DIAGRAM  
E8 NO SCALE

ALL WORK ON THIS SHEET IS INCLUDED IN THE ON SITE CONTRACT UNDER ADDITIVE ALTERNATE #1.

ISSUED FOR  
CONSTRUCTION  
MAY 2023



PROJECT: NELSON LAGOON POWER SYSTEM UPGRADE		
TITLE: HEAT RECOVERY SYSTEM BUILDING A ELECTRICAL PLAN & DETAILS		
DRAWN BY: JTD	DESIGNED BY: BCG	SCALE: AS NOTED
FILE NAME: NELSS PP E8	PROJECT NUMBER:	SHEET: E8
P.O. 111405, Anchorage, AK 99511 (907)349-0100		



EXISTING TANK FARM PANEL DRAWING PROVIDED FOR REFERENCE  
DRAWING PREPARED BY OTHERS AND NOT FIELD VERIFIED



CE2  
ENGINEERS,  
INC.

ANCHORAGE, ALASKA

NELSON LAGOON, ALASKA  
COMMUNITY FUEL FACILITIES UPGRADE  
LADDER DIAGRAM - TANK FARM CONTROL








State of Alaska  
Department of Community  
and Economic Development  
AIDEA/AEA  
Rural Energy Group  
813 West Northern Lights Blvd.  
Anchorage, Alaska 99503

CHECKED BY: BED  
DRAWN BY: LAW  
DATE: APRIL 2004  
W.O. No:


REVISION:  
REV 1 06/04 BED

DRAWING NO.  
E-07




RECORD DRAWING





PANEL BILL OF MATERIALS:

Tag Name	Qty	Part Number	Description
C	1	100LA20ND4 195-B410	Allen-Bradley-Contactor, 4 pole, 120 Vac, 20A Allen-Bradley-Auxiliary contact, NO
CB	1	Q115	Siemens-Q-Circuit breaker, 1 pole 15A
CB	9	Q120	Siemens-Q-Circuit breaker, 1 pole 20A
CB	7	Q220	Siemens-Q-Circuit Breaker, 2 pole 20A
CB	2	G122ML1125	Siemens-Load Center, single phase, main lug, 100A, 26 space min
LNA	2	800HORL10A	Allen-Bradley-Amber LED pilot light, 120V, NEMA 4X
LNG	3	800HORL10G	Allen-Bradley-Green LED pilot light, 120V, NEMA 4X
LNR	2	800HORL10R	Allen-Bradley-Red LED pilot light, 120V, NEMA 4X
M	7	100C23D10	Allen-Bradley-Contactor, 3 pole, 120 Vac, 20A
	7	193ES1CB	Allen-Bradley-Overload relay
	2	100SA11	Allen-Bradley-Auxiliary contact, NO, NC
PBB	5	800HAR2A4 800HN101B 800TXD2	Allen-Bradley-Momentary push-button, 2 N.C. NEMA 4X black Allen-Bradley-Silicone boot push button Allen-Bradley-Contact Block, 1 N.C.
PBG	4	800HAR1D1 800HN101G	Allen-Bradley-Momentary push-button, 1 N.O. NEMA 4X green Allen-Bradley-Silicone boot push button
PBR	4	800HAR6D2 800HN101R	Allen-Bradley-Momentary push-button, 1 N.C. NEMA 4X red Allen-Bradley-Silicone boot push button
R	11	700HA32A1 700HN125	Allen-Bradley-Relay DPDT Allen-Bradley-8-pin relay socket
R	6	700HA33A1 700HN126	Allen-Bradley-Relay 3PDT Allen-Bradley-11-pin relay socket
SS	7	800HHR2D1 800HNR101	Allen-Bradley-Selector Switch, 2 pos. 1 N.O. Allen-Bradley-Silicone switch cover
T	8	700HA32A1 700HN202 700HT1	Allen-Bradley-Relay DPDT Allen-Bradley-8-pin relay socket Allen-Bradley-Series-B timing module
TB-#	135	1492CAM1	Allen-Bradley-Screw terminals blocks, 35Amp, 600V
TB-B	4	1492PDM3141	Allen-Bradley-Screw terminals blocks, 100Amp, 600V
H1,2,3,4	4	D-AH301	Hoffman Panel Heater, 30W
TEM	2	A-TEMNC	Hoffman Panel Thermostat
ISR-#	9	144600	Gem Sensors intrinsically safe relay



NOTE: INSTALL 100 AMP TERMINAL STRIP HORIZONTALLY AS SHOWN. LOCATE TERMINAL STRIP BELOW PANEL DEVICES TO ACCOMMODATE CONDUCTOR ROUTING FROM CONDUITS CONNECTING TO BOTTOM OF PANEL.

TERMINAL STRIP TB-B

PANEL	TB-1	FIELD
CB-1 / SS-6	1	TANK FARM AREA LIGHTING
CB-2	2	SPARE POWER
CB-3	3	CONTROL POWER (NO FIELD WIRING)
CB-4	4	PANEL HEATER POWER (NO FIELD WIRING)
CB-9	5	TANK FARM RECEPTACLE 1
CB-10	6	TANK FARM RECEPTACLE 2
CB-5 / C1-1	7	DISPENSERS & DISP AREA LIGHTS
	8	ALARM HORN/STROBE POWER
CB-6 / C1-3	9	SPARE POWER
	10	SPARE
PANEL NEUTRAL	11	TANK FARM AREA LIGHTING NEUT
PANEL NEUTRAL	12	SPARE POWER NEUTRAL
PANEL NEUTRAL	13	CONTROL NEUTRAL (NO FIELD WIRING)
PANEL NEUTRAL	14	PANEL HEATER NEUTRAL (NO FIELD WIRING)
PANEL NEUTRAL	15	TANK FARM RECEPT. 1 NEUT
PANEL NEUTRAL	16	TANK FARM RECEPT. 2 NEUT
PANEL NEUTRAL	17	DISPENSER & AREA LIGHTING NEUTRAL
PANEL NEUTRAL	18	ALARM HORN/STROBE NEUTRAL
PANEL C1-4 NEUTRAL	19	SPARE POWER NEUTRAL
	20	SPARE
	21	EMERGENCY SW (DISP & TRUCK LOAD)
	22	EMERGENCY SW (DISP & TRUCK LOAD)
	23	SPARE
	24	SPARE
	25	AVGAS DISP. HOOKSWITCH
	26	AVGAS DISP. HOOKSWITCH
CB-17 / M5-T2	27	AVGAS DISPENSING PUMP DP-1
CB-19 / M5-T3	28	AVGAS DISPENSING PUMP DP-1
	29	SPARE
	30	SPARE
	31	#1 FO DISP. HOOKSWITCH
	32	#1 FO DISP. HOOKSWITCH
CB-21 / M7-T2	33	#1 FUEL OIL DISPENSING PUMP DP-3
CB-23 / M7-T3	34	#1 FUEL OIL DISPENSING PUMP DP-3
	35	SPARE
	36	SPARE
	37	UNLEAD DISP. HOOKSWITCH
	38	UNLEAD DISP. HOOKSWITCH
CB-18 / M6-T2	39	UNLEAD DISPENSING PUMP DP-2
CB-20 / M6-T3	40	UNLEAD DISPENSING PUMP DP-2

INTRINSICALLY SAFE TERMINAL STRIP. MUST BE PHYSICALLY ISOLATED FROM ALL OTHER CIRCUITS.

PANEL	TB-3	FIELD
	81	FLOAT SWITCH (SW-2A) OVERFILL
	82	FLOAT SWITCH (SW-2A) OVERFILL
	83	FLOAT SWITCH (SW-2B) FULL LEVEL
	84	FLOAT SWITCH (SW-2B) FULL LEVEL
	85	FLOAT SWITCH (SW-2C) LOW LEVEL
	86	FLOAT SWITCH (SW-2C) LOW LEVEL
	87	FLOAT SWITCH (SW-3A) OVERFILL
	88	FLOAT SWITCH (SW-3A) OVERFILL
	89	FLOAT SWITCH (SW-3B) FULL LEVEL
	90	FLOAT SWITCH (SW-3B) FULL LEVEL
	91	FLOAT SWITCH (SW-3C) LOW LEVEL
	92	FLOAT SWITCH (SW-3C) LOW LEVEL
	93	FLOAT SWITCH (SW-4A) OVERFILL
	94	FLOAT SWITCH (SW-4A) OVERFILL
	95	FLOAT SWITCH (SW-4B) FULL LEVEL
	96	FLOAT SWITCH (SW-4B) FULL LEVEL
	97	FLOAT SWITCH (SW-4C) LOW LEVEL
	98	FLOAT SWITCH (SW-4C) LOW LEVEL

PANEL NOTES:

- PROVIDE COMPLETE UL LISTED PANEL ASSEMBLY WITH LOAD CENTERS, AND ALL DEVICES INDICATED IN LOGIC DIAGRAM EXCEPT FOR FIELD DEVICES. FIELD DEVICES ARE INDICATED WITH DASHED OUTLINE.
- INSTALL IN A 36"x48"x12" NEMA 4X ENCLOSURE WITH 4 EACH INTEGRAL MOUNTING LUGS AT BACK. INSTALL WEATHERPROOF HINGED WINDOW AND DRIP SHIELD AS INDICATED ON PANEL FACE LAYOUT.
- SEE SHEET E7 FOR PANEL FACE LAYOUT, SUB-PANEL LAYOUT, ONE-LINE DIAGRAM, AND SEQUENCE OF OPERATIONS.
- LABEL ALL REMOTE EQUIPMENT CONNECTIONS AT THE TERMINAL BLOCK BY THE ITEM TITLE AS SHOWN ON THE DRAWING. TAG EACH END OF ALL JUMPERS WITH DEVICE OR TERMINATION DESIGNATOR OF LANDING OF OPPOSITE END OF JUMPER (REVERSE ADDRESS).
- PROVIDE SHOP DRAWING WITH ALL TERMINAL BLOCK TERMINATION NUMBERS AND DEVICE CONNECTION NUMBERS.
- BENCH TEST THE COMPLETED ASSEMBLY PRIOR TO SHIPPING. PROVIDE MIN 48 HOURS NOTICE TO ENGINEER TO SCHEDULE OBSERVATION OF BENCH TEST. PROVIDE SWITCHES AND LAMPS TO SIMULATE OPERATION OF ALL FIELD DEVICES.

FIELD INSTALLATION NOTES:


- PRIOR TO PLACING IN THE TANK, VERIFY PROPER OPERATION OF EACH FLOAT SWITCH (ACTUATION LENGTH AND NO/NC FUNCTION). LABEL FLOAT SWITCH TERMINALS WITH THE NUMBER OF THE ASSOCIATED HOME RUN LANDING ON TB-1 IN THE CONTROL PANEL.

PANEL	TB-2	FIELD
	41	TP1 MOTOR OPERATED VALVE-OPEN
	42	TP1 MOTOR OPERATED VALVE-CLOSE
	43	TP1 MOTOR OPERATED VALVE-NEUTRAL
	44	TP1 MOTOR OPERATED VALVE-NEUTRAL
	45	#2 DIESEL TRANSFER PUMP TP-1
	46	#2 DIESEL TRANSFER PUMP TP-1
	47	SPARE
M1 AUX NO CONTACT	48	TP1 MOTOR OPERATED VALVE-OPEN
M1 AUX NO CONTACT	49	TP1 MOTOR OPERATED VALVE-CLOSE
PANEL NEUTRAL	50	TP1 MOTOR OPERATED VALVE-NEUTRAL
CB-9 / M1-T2	51	#2 DIESEL TRANSFER PUMP TP-1
CB-11 / M1-T3	52	#2 DIESEL TRANSFER PUMP TP-1
	53	SPARE
	54	SPARE
CB-13 / M3-T2	55	UNLEAD GAS TRANSFER PUMP TP-3
CB-15 / M3-T3	56	UNLEAD GAS TRANSFER PUMP TP-3
	57	SPARE
	58	SPARE
CB-10 / M2-T2	59	AVGAS TRANSFER PUMP TP-2
CB-12 / M2-T3	60	AVGAS TRANSFER PUMP TP-2
	61	SPARE
	62	SPARE
	63	TRUCK LOADING METER PERMISSIVE SWITCH
	64	TRUCK LOADING METER PERMISSIVE SWITCH
CB-14 / M4-T2	65	#1 DIESEL BULK TRANSFER PUMP TP-4
CB-16 / M4-T3	66	#1 DIESEL BULK TRANSFER PUMP TP-4
	67	SPARE
	68	SPARE
	69	SPARE
	70	SPARE
	71	#2 OVERFILL LOCKOUT
	72	#2 OVERFILL LOCKOUT
	73	120 VAC CONTROL PWR TB4-101
	74	120 VAC CONT PWR NEUT TB4-102
	75	M1 LATCH TB4-105
	76	CONTROL PWR TO M1 TB4-106
	77	HIGH LEVEL LOCKOUT LIGHT TB4-109
	78	SPARE
	79	SPARE
	80	SPARE

LOCATED ON THE INTERMEDIATE TANK CONTROL PANEL AT THE POWER PLANT.

PANEL	TB-4	FIELD
	101	120 VAC CONTROL POWER TB2-73
	102	120 VAC CONTROL NEUTRAL TB2-74
AVGAS DISP TANK	103	CABINET STRIP HEATER THERMOSTAT
	104	SPARE
	105	M1-14 LATCH TB2-75
	106	CONT PWR TO M1 COIL TB2-76
	107	LOCKOUT RELAY OVERFILL TB-1-71
	108	LOCKOUT RELAY OVERFILL TB-1-72
UNLEAD DISP TANK	109	HIGH LEVEL LOCKOUT LIGHT TB2-77
	111	FLOAT SWITCH (SW-1) POWER
	110	FLOAT SWITCH (SW-1A) LOW LEVEL
	112	FLOAT SWITCH (SW-1B) FULL LEVEL
	113	FLOAT SWITCH (SW-1C) OVERFILL
#1 FUEL OIL DISP TANK	114	LOW LEVEL CONTACT SPARE
	115	LOW LEVEL CONTACT SPARE


LEGEND



EXISTING TANK FARM  
PANEL DRAWING  
PROVIDED FOR  
REFERENCE  
DRAWING PREPARED  
BY OTHERS AND NOT  
FIELD VERIFIED



RECORD DRAWING



CE2  
ENGINEERS,  
INC.  
ANCHORAGE, ALASKA

NELSON LAGOON, ALASKA  
COMMUNITY FUEL FACILITIES UPGRADE  
INTERCONNECT DIAGRAM AND NOTES

State of Alaska  
Department of Community  
and Economic Development  
AIDEA/AEA  
Rural Energy Group  
813 West Northern Lights Blvd.  
Anchorage, Alaska 99503

CHECKED BY: BED  
DRAWN BY: LAW  
DATE: APRIL 2004  
W.O. No:

REVISION:  
REV 1 06/04 BED

DRAWING NO.  
E-08



