

# STATE OF ALASKA

Department of Public Safety  
Division of Administrative Services



## Fairbanks Post Impound Lot & Fencing

ITB 26MUL0808C

### Amendment 2

September 25, 2025

**This amendment is being issued to answer vendor submitted questions and extend the deadline for bids.**

**Important Note to Offerors:** You must sign and return this page of the amendment document with your bid. Failure to do so may result in the rejection of your bid. Only the ITB terms and conditions referenced in this amendment are being changed. All other terms and conditions of the ITB remain the same.

Olivia Jewell  
Facilities Manager  
Phone: (907) 269-5647  
Email: Olivia.jewell@alaska.gov

---

COMPANY SUBMITTING BID

---

AUTHORIZED SIGNATURE

---

DATE

### Vendor Questions:

**Question 1:** The specs appear to require bottom rail, but the drawings show bottom tension wire. Which is correct.

*Answer:* Tension wire shall be installed on the bottom of the fencing fabric.

---

**Question 2:** The existing fence that we are supposed to be tying into, is privacy fence. Is the rest of the fence, or any portion, supposed to be privacy fence to match?

*Answer:* Privacy slats are not required in the impound yard fencing or connection to existing fencing.

---

**Question 3:** Fence assembly specs call for 2-3/8" line posts 10'o.c. and 2-7/8" terminal posts. Please verify that this is the proper sizing for a 10' tall fence.

*Answer:* Line posts shall be 2-7/8" and terminal posts shall be 4"

---

**Question 4:** Please confirm the depth of excavation required. Is the intent to excavate and remove enough organics/subgrade to place 34" of structural fill, per drawings? Or is the intent to remove all organics regardless of the depth? If the requirement is to remove all organics, regardless of depth, please provide expected quantities of removal and backfill.

*Answer:* The intent is to remove all organics. See Note 2 on sheet C100.

---

**Question 5:** Due to the colder temperatures approaching, can the deadline be extended to next summer? If it freezes that will make meeting compaction and pouring concrete a challenge.

*Answer:* This project is an essential element of the critical path for summer 2026 construction on a separate project. The pad must be available to the Owner per the current schedule.

---

**Question 6:** Can you provide an exact length and width of the pad?

*Answer:* Exact length of the pad is given by survey points. Approximate dimensions of the top of pad are 252' x 184'.

---

**Question 7:** How many cubic yards of fill is there?

*Answer:* Contractor shall calculate anticipated fill volumes based on information provided.

---

**Question 8:** How many cubic yards of excavation is there?

*Answer:* Contractor shall calculate anticipated excavation volumes based on information provided.

---

**Question 9:** The site appears to have restricted access, will it be open during project work?

*Answer:* Access is unrestricted for vetted contractors. The on-site work hours are from 7:00 AM to 5:00 PM, seven days a week. It is essential to maintain access to the current impound lot and AWT areas.

---

### Changes to the ITB:

**Change 1:** Extend the deadline for bids to 1:30 PM local time (per the Department's time source) on the 1st day of October 2025.

---

**Change 2:** Clarify bid delivery format under Page 3, Submission of Bidding Documents. Remove paragraph one and replace with:

Bidders **must** submit bidding documents electronically to **dps.das.solicitations@alaska.gov**. For electronically submitted bids with a paper bid guaranty, the bid guaranty shall be submitted in a sealed envelope marked as follows:

Bidding Documents for Project:  DPS Headquarters 5700 E Tudor Road, Anchorage, AK 99507 Project No: 26MUL0808C	ATTN: State of Alaska Department of Public Safety DAS, Facilities Olivia Jewell, Facilities Manager 907-269-5647, Olivia.jewell@alaska.gov
--	---

---