



Alaska Railroad Corporation  
327 W. Ship Creek Ave.  
Anchorage, AK 99501

October 17, 2025

Addendum 2  
ITB #25-56-213663  
Healy Slope Stabilization 357.1

**Addendum number 2 has been issued for answering of questions and new Cost Schedule.**

The Closing Date for this ITB has not changed.  
Bids will be received until October 22, 2025 @ 3:00 PM Alaska time.

- 
1. What is the completion date or duration of the project?
    1. 12/30/2026
  2. What are the liquidated damages amount?
    1. The Alaska Railroad SSC breaks LD's on page 78/79  
<https://www.alaskarailroad.com/corporate/procurement/forms-and-resources>
  3. The bid schedule describes item 610.0005 as Porous Backfill Material, the specs identify it as Ditch Lining, please clarify. If it is porous backfill is it type A or type B?
    1. Bid schedule on the plans and appendix H have 605.0005 as Porous Backfill Material, MBI Desires porous backfill type A to be consistent with callout on sheet C-103. No changes to the plans item # or description.
    2. ARRC to clarify Porous Backfill Type A in a statement referencing C-103 section E .
    3. Spec 610 and pay item 610.0005 are consistent as the 'rubber liner' but in the Appendix H Cost Schedule we need to update 610.005 description/unit/quantity. In Appendix E specials fix the 203-5.01 header for basis of payment and 203.0005 pay item in the text.
  4. The bid schedule calls for item 603.0025 to be paid per each, the specs call for that to be paid by the foot, please clarify.
    1. Correct the appendix E special to EACH.
    2. Inside the 4.01 spec section, add the expected length of the HDPE liner.
  5. The reusable material is by the ton. Shouldn't that be by the cubic yard otherwise a set of scales will have to be set up where as a cross section would suffice for measurement?
    1. Update to cubic yards, and make pay item # 205.0005.C. We agree that cross-section measurements under construction surveying should be sufficient.
    2. Will then also update the pay item for Borrow, Type A to 205.0005.A

6. Can the access road be wider than 10 feet since most of our construction equipment will be wider?
  1. The road may be maintained and the surface improved with gravel, but it cannot be widened beyond its existing width. Imported gravel can be graded, but the existing surface may not be graded.
7. We are still a little confused on what type of drug testing program that we will have for example, will beacon out of Alaska suffice since most of our work takes place further than 4 feet away from the track and what is the protocol to get across the tracks when we place class I and II rip rap on the downhill side of the rammed pipes?
  1. **Testing program will conform to specifications**
  2. ARRC expects to put in a temporary crossing allowed for use when flaggers present.
8. Appendix B addresses a requirement of the Contractor that "All contractors and subcontractors providing Roadway Worker services for ARRC will be required to register with Avetta..." Will this contract be subject to that requirement? I cannot find any definition of "Roadway Worker services, and it does not appear that any trackwork will be involved."
  1. All workers on site are required to register.
9. Appendix C indicates flaggers are restricted to 10 hours per day, 60 hours per week. Will ARRC flaggers be available to the project for a full 10 hour window of work, or is some of their 10 hour day comprised of other duties (transportation, etc)?
  1. ARRC to Respond with statement: Expect flaggers to be availability onsite for the full 10 hour work window.
10. Can classified materials not produced at the site be stockpiled at start of trail to be reloaded in off road haul trucks for transport to site?
  1. ARRC to Respond with statement: Yes, if offsets maintained, and excess material removed at project completion.
11. **Is the intent that select material, reusable be ripped, excavated, and placed or stockpiled without further processing like screening or crushing?**
  1. Yes, no additional screening or crushing of select material reusable is expected before placement as reusable excavation or stockpiling as non-reusable/excess material within the project disposal limits.  
\*If the contractor intends to produce other materials (i.e. porous backfill gradation A) with excavated materials it must be sufficiently demonstrated to the construction manager that the gradations and material requirements in section 703 are being met.
  2. Clarify 203.0005.C with a special: Place all reusable excavation following **203-3.05 Compaction Without Moisture and Density Control** except deposit embankment materials in layers not exceeding 6 inches in thickness before compaction.
  3. Moe to confirm the additional disposal requirements we previously discussed at 90/100% are accounted for in specs.
12. Will Geotechnical Report be made available for this project?
  1. Yes, Geotech report has been uploaded to the AKRR website under this solicitation.
13. Is work more than 50' from tracks subject to working restrictions listed in bidding documents? If yes, what distance from can work take place without delays from scheduled train traffic?
  1. Work with a potential to foul within 25' of centerline will be required to be protected with a flagman.

## APPENDIX I COST SCHEDULE

**COST SCHEDULE:** A Bidder's Failure to provide the information requested in this Appendix may be cause for rejection of the bid on the basis on non-responsiveness. Cost shall be bid in accordance with all specifications and any Technical Specifications incorporated herein.

**AWARD CRITERIA:** A contract award resulting from this solicitation may be made to the low, responsive, responsible bidder who meets the requirements as set forth in the Plans and specifications and compliance thereof. An award may be made in the aggregate of Base Bid. The successful bidder shall hold unit prices of all additives firm for a period of thirty (30) days from the date of bid opening. Award is contingent on the availability of FTA and ARRC funds.

### BASE BID: ITEMS

| Item No.   | Item Description                                       | Unit | Quantity <sup>1</sup> | Unit Bid Price | Amount Bid |
|------------|--------------------------------------------------------|------|-----------------------|----------------|------------|
| 201.0003   | Clearing and Grubbing                                  | Acre | 5.5                   |                |            |
| 203.0003   | Unclassified Excavation                                | CY   | 23,000                |                |            |
| 203.0005.1 | Borrow, Type A                                         | CY   | 100                   |                |            |
| 203.0005.2 | Selected Material, Type C                              | CY   | 12000                 |                |            |
| 603.0001   | CSP 24 Inch                                            | LF   | 26                    |                |            |
| 603.0023.1 | Smooth Steel Pipe, 8"ø                                 | LF   | 140                   |                |            |
| 603.0023.2 | Smooth Steel Pipe, 36"ø                                | LF   | 55                    |                |            |
| 603.0024   | Pipe Cleaning and Repair                               | Each | 1                     |                |            |
| 603.0025   | Liner for Storm Drain, 36"ø                            | Each | 1                     |                |            |
| 603.0026.1 | Driven Pipe, 8"ø                                       | LF   | 140                   |                |            |
| 603.0026.2 | Driven Pipe, 36"ø                                      | LF   | 55                    |                |            |
| 605.0005   | Porous Backfill Material, Type A                       | CY   | 2,000                 |                |            |
| 605.0006   | Perforated Corrugated HDPE Pipe for Underdrain, 6 inch | LF   | 2,620                 |                |            |
| 610.0005   | Ditch Lining                                           | SY   | 2,800                 |                |            |
| 611.0001.1 | Riprap, Class I                                        | CY   | 2,000                 |                |            |

**BASE BID: ITEMS**

| Item No.       | Item Description                                        | Unit | Quantity <sup>1</sup> | Unit Bid Price | Amount Bid |
|----------------|---------------------------------------------------------|------|-----------------------|----------------|------------|
| 611.0001.2     | Riprap, Class II                                        | CY   | 180                   |                |            |
| 618.0004       | Seeding                                                 | AC   | 2                     |                |            |
| 631.0001       | Geotextile, Drainage, Class 2                           | SY   | 6,500                 |                |            |
| 631.0002       | Geotextile, Erosion Control, Class 1                    | SY   | 3,900                 |                |            |
| 633.0001       | Silt Fence                                              | LF   | 1250                  |                |            |
| 640.0001       | Mobilization and Demobilization                         | LS   | All Required          |                |            |
| 641.0001       | Erosion, Sediment, and Pollution Control Administration | LS   | All Required          |                |            |
| 641.0003       | Temporary Erosion, Sediment, and Pollution Control      | LS   | All Required          |                |            |
| 641.0007       | SWPPP Manager                                           | LS   | All Required          |                |            |
| 642.0001       | Construction Surveying                                  | LS   | All Required          |                |            |
| 646.0001       | CPM Scheduling                                          | LS   | All Required          |                |            |
| Total Base Bid |                                                         |      |                       |                | \$         |

Notes:

<sup>1</sup> Bid quantities are approximate. Contractor is responsible for their own quantity take-offs using the information within the Contract Documents to verify the quantities in the Bid Schedule.

NON-COLLUSION AFFIDAVIT: The Undersigned declares, under penalty of perjury under the laws of the United States, that neither he/she nor the firm, association, or corporation of which he/she is a member, has, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this Bid.

The Undersigned has read the foregoing proposal and hereby agrees to the conditions stated therein by affixing his/her signature below:

BIDDERS NAME AND ADDRESS

\_\_\_\_\_  
COMPANY NAME

\_\_\_\_\_  
SIGNATURE BY AND FOR THE BIDDER

\_\_\_\_\_  
COMPANY MAILING ADDRESS

\_\_\_\_\_  
PRINTED NAME OF ABOVE BIDDER

\_\_\_\_\_  
CITY, STATE ZIP CODE


\_\_\_\_\_  
DATE OF BID

\_\_\_\_\_  
CONTACT PHONE NUMBER

\_\_\_\_\_  
CONTACT E-MAIL

All other terms and conditions remain unchanged.  
If there are any questions regarding this addendum, please let me know.

Thank you,

A handwritten signature in black ink, appearing to read "Rob Walker". The signature is fluid and cursive, with the first name "Rob" and last name "Walker" clearly distinguishable.

***Rob Walker***  
Logistics Manager  
Alaska Railroad Corporation