THE STATE of ALASKA
GOVERNOR MIKE DUNLEAVY

Department of Military and Veterans Affairs

FMO Design and Construction
57024 Roosevelt Rd
PO Box 5169
JBER, AK 99505

Email: scott.higbee@alaska.gov

Issue Date: October 14, 2026

ATTN: Vendors

RE: **Project Name:** BAAF – 47430 Hangar 1 – Roof and Envelope Project
Project Number: 02A7026003
Project Location: JBER, Alaska

Addendum # Seven
(7)

This addendum forms a part of the contract documents and modifies the original drawings and/or specifications for the subject work. In case of conflicts between this addendum and previously issued documents, this addendum shall take precedence.

The following questions have been received, answered, and changes below are required:

1. Question: Please clarify the qualifications required for the contractor's representative performing the roof assessment under §1.02.01.A and the governing standard and acceptance criteria for determining whether existing roofing components may remain or require replacement.

   Answer: There are no stringent qualifications to meet this requirement. The Contractor's representative should of course be familiar with the roofing UFCs, typical building codes, etc. but do not need to hold a specific certification. The intent of this language in the ITB is to ensure that proper analysis of the existing roof and associated components is conducted by the contractor and relayed to the Project Manager, so we know what we're dealing with.

2. Question: UFC requires a fall protection system, the other hangers have one and this one does not. Given that we are just recovering this roof and not tearing it off down to the deck is a new fall protection system required on Hanger 1?

   Answer: Per the ITB the Contractor must adhere to all applicable UFC and OSHA requirements so a fall protection system will be required.

Respectfully,

Scott M. Higbee
Building Management Specialist
907-428-7175
scott.higbee@alaska.gov

End of Addendum