Basis for Ratio of Indirect to Direct Costs

										DEC Suggestions		tions
Indirect Cost Category	SMCRA	Fort Knox (2013)	Greens Creek (2013)	Kensington (2013)	Nixon Fork (2012)	Pogo (2012)	Red Dog (2009)	Rock Creek (2012)	State Draft Guidance (incl BLM/USFS	New Facilitie s (operati ng <10 yrs)	Intermediate Facilities (operating <15 yrs)	Mature Facilities (operating 15 or more yrs)
Contractor Profit	15 - 30	15	5% x O&M	10	10	7.5	10% x labor/equip costs	15	10 - 20	12.5	12.5	12.5
Contractor Overhead				5	4	7.5	10% x labor		5 - 10	6.25	6.25	6.25
Performance Bond		3	2% x O&M	0	1.5	3	1.5	1.5	1.5	1.5	1.5	1.5
Payment Bond		0	0	0	1.5	0	1.5	1.5	1.5	1.5	1.5	1.5
Liability Insurance		1.5% x labor	4.6% x labor	0	1.5	1.5% x direct	1.6% x labor/equip costs	1.6% x equip. cost	1.5% x labor cost	0.5	0.5	0.5
Contract Administration	2 - 7	8	2	7	9.4 (BLM) 1.5 (state)	4	1	1	2 - 7	5	5	5
Engineering Redesign	2.5 - 6	4	2	5	6	3	3	3	3 - 6	5.75	3.75	2.75
Scope Contingency	3 - 5	10	4	12	6	7.5	10	12 (10% x direct +	10 - 20 6 - 10 4 - 7	8.5	7	5
Bid Contingency			4	5	6	7.5	10	indirect) 0	10 - 20	8.5	7	5
Other	10% (Mob/ Demob)			\$695K long term dam inspection & maintenance		5% (Mob/ Demob)	12% x materials (freight transport)					
Other (road maintenance)							\$300,000/ yr					
Inflation				3.5 over 5 more yrs (\$4.43 M)	2.67	2.66						
Direct Costs (\$M)		68.559	61.846	16.0	4.003	29.008		9.952				
Indirect Cost (\$M)		27.609	12.189	7.6	1.873	14.271		3.454				
Direct + Indirect (\$M)		96.168	74.035	23.6	5.876	43.280		13.405				
Indirect/Direct	0.325 – 0.58	0.40 (3 rd permit)	0.20 (2 nd permit)	0.475 (1 st or 2 nd permit)	0.47 (2 nd permit)	0.49 (2 nd permit)	(1 st permit)	0.35 (2 nd permit)		0.5	0.45	0.4

FORT KNOX MINE – DRAFT PERMIT

DIRECT COSTS	
Waste Rock Dumps	\$6,526,000
Heap Leach	\$2,509,000
Building Demo	\$861,000
Roads & Laydown Yards	\$633,000
North Wetlands Complex and Spillway	\$2,773,000
Growth Media Stockpiles	\$51,000
Pit Safety Berm	\$123,000
Water Management	\$42,418,000
TSF Earthwork	\$4,137,000
Closure Studies and Reports	\$1,177,000
Pipeline & Powerline Removal	\$1,424,000
Fence Removal	\$12,000
Well Closure	\$526,000
Post Closure Monitoring	\$616,000
Road Maintenance	\$539,000
Pit Water Treatment	\$2,060,000
Tailings Storage Facility Maintenance	\$1,053,000
Water Supply Reservoir Maintenance	\$519,000
Pit Rim Warning Signs and Maintenance	\$241,000
Dam Security Gate Installation	\$11,000
Mobilization & Demobilization	\$350,000
DIRE	CT COSTS SUBTOTAL

INDIRECT COSTS (% x direct costs subtotal)							
Engineering & Redesign	4%	\$2,742,000					
Contractor Profit & Overhead	15%	\$10,284,000					
Performance Bond	3%	\$2,057,000					
Contract Administration	8%	\$5,485,000					
Contingencies	10%	\$6,856,000					
Insurance Premiums (labor = \$12,193,000)	labor x 1.5%	\$185,000					

INDIRECT COSTS SUBTOTAL \$27,609,000

<u>\$96,168,000</u>

TOTAL FINANCIAL RESPONSIBILITY

NIXON FORK MINE

CLOSURE & MAINTENANCE	FINANCIAL RESPONSIBILITY						
Direct Costs							
Equipment Capital Costs	\$947,234						
Equipment Operation & Maintenance	Costs	\$310,491					
Revegetation		\$109,949					
Manpower		\$1,137,390					
Manpower Support		\$324,974					
Materials, Supplies, Other		\$379,458					
Post-Closure Monitoring		\$242,507					
One Year Holding Period			\$551,379				
Direct Costs Subtotal*		\$3,452,000	\$551,000	\$4,003,000			
Indirect Costs	Percent	No Holding Period	One Year Holding Period				
Contractor Profit	10%	\$345,000	\$55,000				
Contractor Overhead	4%	\$138,000	\$22,000				
indirect + direct s	subtotals ¹	\$3,935,000	\$628,000				
Performance and Payment Bond	3%	\$118,000	\$19,000				
Liability Insurance	1.5%	\$17,000	\$3,000				
indirect + direct	subtotals	\$4,070,000	\$650,000				
BLM Contract Administration	9.4%	\$324,000	\$52,000				
Engineering Redesign Plan	6%	\$207,000	\$33,000				
Contingency	12%	\$414,000	\$66,000				
State Agency Oversight	1.5%	\$52,000	\$8,000				
indirect + direct	subtotals	\$5,067,000	\$809,000				
Indirect Costs Subtotal	\$1,873,000						
Direct + Indirect Total	\$5,876,000						
Inflation (one year at 2.67%)	\$157,000						
	<u>\$6,033,000²</u>						
¹ All subtotals and totals rounded to the nearest \$1,000							
² The financial responsibility will be r	eevaluated	l and adjusted	as allowed in se	ction 1.10.2.			

POGO MINE

CLOSURE MAINTENANCE ITEM	FINANCIAL RESPONSIBILITY
Direct Costs	
1 Year Holding Cost	\$1,952,300
Phase II: Reclamation Concurrent with Mining	\$797,400
Phase III: Reclamation and Closure of Mine Site	\$10,622,300
Phase IV: Continued Water Treatment	\$10,639,328
Phase IV: Continued Reclamation	\$4,892,300
Phase V: Post Closure Monitoring	\$104,800
Direct Cost Subtotal	\$29,008,428
Indirect Costs	
Mobilization/Demobilization (5%)	\$820,840
Contractor Profit and Overhead (15%)	\$4,474,390
Performance Bond (3%)	\$1,029,110
Insurance (1.5%)	\$514,555
Contract Administration (4%)	\$1,433,893
Engineering Redesign (3%)	\$621,460
Contingency (15%)	\$5,377,098
Indirect Cost Subtotal	\$14,271,346
Direct + Indirect Total	\$43,279,773
Inflation (2.66%)	\$1,150,099
TOTAL	<u>\$44,430,000¹</u>
¹ The financial responsibility will be reevaluated and adjusted as 1.11.2 or as requested by the permittee.	allowed in section

RED DOG MINE

Premature Closure Scenario							
Years	Suspension	Closure Earthwork	Closure Water	Post-Closure	Cash Flows	Net Present Value	
(after	(site maintenance	and other	Treatment	(perpetual		(at a 4.3%	
suspension	& ongoing water	Reclamation		annual water		estimated real	
of mining)	treatment)			treatment)		rate of return)	
1	\$13,290,000				\$13,290,000	\$305,150,000	
2	\$13,290,000				\$13,290,000		
3	\$13,290,000				\$13,290,000		
4	\$13,290,000				\$13,290,000		
5	\$13,290,000				\$13,290,000		
6		\$25,900,000	\$7,850,000		\$33,750,000		
7		\$25,900,000	\$7,850,000		\$33,750,000		
8				\$10,540,000	\$255,656,279		
9 and thereafter				\$10,540,000	\$10,540,000		

Cash flow for year 8 equals the present value of an account that earns \$10,540,000 annually in perpetuity plus first year post-closure expenses of \$10,540,000.

ROCK CREEK MINE

Cost Element	Tota	
Direct Costs		
Area 1: Plant Site	\$	936,124
Area 2: Main & Walsh Pits	\$	2,447,036
Area 3: Tailings Storage Facility & DC #3	\$	1,540,006
Area 4: Injection Well Fields & DC #2	\$	455,273
Area 5: Explosive Storage Area & West Pit	\$	487,089
Area 6: Diversion Channel #1	\$	362,760
Area 7 Roads & Rock Creek Causeway	\$	621,159
Standby Adjustment	\$	89,055
Long Term Monitoring	\$	92,000
Water Treatment	\$	144,567
Mobilization	\$	449,968
Demobilization	\$	299,979
Freight costs (12% of material cost)	\$	79,400
Haul Road Maintenance	\$	206,907
Man Camp @ 152.40/man-day	\$	624,992
Field Support Labor	\$	1,040,961
Administrative Cost	\$	74,230
Direct Subtotal	\$	9,951,506
Indirect Costs		
Insurance (1.6% of equipment cost)	\$	43,582
Contractor overhead and profit (15%)	\$	1,405,514
Engineering Re-Design (3%)	\$	323,268
Performance & Payment Bond (3%)	\$	342,018
State Management and Oversight (1%)	\$	120,659
Indirect Subtotal	\$	2,235,041
Contingency (Direct + Indirect)*10%	\$	1,218,655
Phase 2 Project Estimate	\$	13,405,202

Phase 2 Rock Creek Reclamation and Bond Estimate Summary

KENSINGTON MINE

	Percentage	Amount	Subtotal	Total
Direct & Post-Closure Cost Subtotal			\$16,001,492	
Indirect Cost Category				
Contractor Profit	10.00%	\$1,600,14 9		
Contractor Overhead	5.00%	\$800,075		
Performance Bond	1.50%	\$240,022		
Payment Bond	1.50%	\$240,022		
Liability Insurance	1.50%	\$240,022		
Contract Administration	7.00%	\$1,120,10 4		
Engineering Redesign	5.00%	\$800,075		
Scope Contingency	12.00%	\$1,920,17 9		
Bid Contingency	4.00%	\$640,060		
Indirect Cost Subtotal			\$7,600,709	
Other (inflation compounded over 5 more years)	3.50%		\$4,429,810	
Other (long term dam inspections and maintenance)			\$695,000	
Total				\$28,727,011
Direct Costs (\$Million)			\$16.00	
Indirect Cost (\$Million)			\$7.60	
Indirect/Direct			0.475	